

Completion of Mukhya Mantri Sabha Ghar at Ainlasari, GP-Samalaichuan

| Slno | Item of the work | Unit | Qty | Rate | Amount |
|------|--|------|--------|----------|----------|
| 1 | Brick masonry in foundation & superstructure in c. m. (1:6) using fly ash bricks including cost, conveyance, royalty of all materials, T & P etc. complete. | | | | |
| a | Super structure | cum | 7.30 | 4316.80 | 31513.00 |
| 2 | RCC M-20 work with 20mm down grade course aggregate including hoisting and laying. with cost, conveyance, royalty of all materials, T & | | | | |
| a | Ground Floor | cum | 6.37 | 5215.60 | 33223.00 |
| 3 | Rigid and smooth centering & shuttering for RCC works including false works and dismantling then after casting including cost of materials complete in ground. | | | | |
| a | Ground Floor | | | | |
| | (i) Plinth Bend | sqm | 4.83 | 103.40 | 499.00 |
| | (ii) Column | sqm | 13.24 | 761.20 | 10078.00 |
| | (iii) Stair case | sqm | 16.20 | 620.40 | 10050.00 |
| | (iv) Roof Slab | sqm | 10.88 | 442.50 | 4814.00 |
| 4 | Supplying of H Y S D bar reinforcement in R.C.C. works with Labour charges for cutting, bending , binding of bars , including cost,conveyance & taxes of H Y S D bars and binding wire , T & P etc. complete | | | | |
| a | | Qntl | 6.00 | 10335.35 | 62012.00 |
| 5 | 6mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials etc. | | | | |
| | | sqm | 118.64 | 166.90 | 19801.00 |
| 6 | 12mm (½") thick cement plaster (1:6) finishing smooth to outside smooth surface of brick walls including cost, conveyance, royalties and taxes of all materials and cost of all labour charges . | | | | |
| a | Ground Floor | sqm | 293.60 | 149.80 | 43981.00 |
| 7 | 16mm (¾") thick cement plaster (1:6) finished smooth to inside rough surface including cost and conveyance, royalties and taxes of all materials and labour charges . | | | | |
| a | Ground Floor | sqm | 460.42 | 213.00 | 98069.00 |

| Slno | Item of the work | Unit | Qty | Rate | Amount |
|------|--|------|---------|---------|-----------|
| 8 | Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete | | | | |
| | | sqm | 721.41 | 74.70 | 53889.00 |
| 9 | Priming one coat over the finished wall surface,including cost, conveyance & taxes etc complete | | | | |
| a | Ground Floor | sqm | 1003.94 | 61.60 | 61843.00 |
| 10 | Wall painting with 2 coats with plastic emulsion paint of approved shade on new wrk to give an even shade including cost and conveyance, royalties and taxes of all materials and labour charges . Etc complete | | | | |
| a | Ground Floor | sqm | 710.34 | 86.15 | 61196.00 |
| 11 | Wall painting with 2 coats with weather coat of approved shade on new work to give an even shade including cost, taxes , conveyance etc complete. | | | | |
| a | Ground Floor | sqm | 308.60 | 83.50 | 25768.00 |
| 12 | Supplying of M.S. Door & Window shutters including cost, conveyance & taxes of all labour & material etc complete. | | | | |
| | | Kg | 1201.90 | 147.40 | 177160.00 |
| 13 | Painting two coats over one coat of primer on new steel work including cost ,conveyance of material & labour charges. | | | | |
| | | sqm | 48.83 | 199.80 | 9756.00 |
| 14 | Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thickness of 10mm and filling joints with epoxy grout of approved | | | | |
| a | Ground Floor | sqm | 179.37 | 989.50 | 177487.00 |
| 15 | Fixing tiles in floors,treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles | | | | |
| a | Ground Floor | sqm | 51.66 | 1038.70 | 53659.00 |
| 16 | Supplying fitting & fixing of Stainless steel of 304 grade in hand railing using 50mm. Dia of 2 mm. thick circlar pipe with balustrade of size 2mm @ 0.90 m.c/c and stinless square pipe bracing | | | | |

| Slno | Item of the work | Unit | Qty | Rate | Amount |
|------|---|------|-------|---------|------------|
| | of size 32mm.x32mm.x2mm. In 3 rows in case as per approved design and specification, buffing,polishing etc. with cost ,conveyance, taxes of all materials labour T & P etc. required for the completion in all aspect | Rmt | 23.20 | 3541.40 | 82160.00 |
| 17 | Add Labour Registration charges | | | | 500.00 |
| 18 | Contygency @1% | | | | 10369.00 |
| 19 | Display Board & Photograp | | | | 9000.00 |
| | | | | | 1036827.00 |