

Completion of Mukhya Mantri Sabha Ghar at Bhagitikra, GP- Bankipali

S/no	Item of the work	Unit	Qty	Rate	Amount
1	RCC M-20 work with 20mm down grade course aggregate including hoisting and laying. with cost, conveyance, royalty of all materials, T &				
a	Ground Floor	cum	53.11	5215.60	277001.00
2	Rigid and smooth centering & shuttering for RCC works including false works and dismantling then after casting including cost of materials complete in ground.				
a	Ground Floor				
	(i) Column,Beam	sqm	108.71	761.20	82750.00
	(ii) Wall beam	sqm	47.01	269.70	12679.00
	(iii) Roof Slab	sqm	253.70	442.50	112262.00
3	Supplying of H Y S D bar reinforcement in R.C.C. works with Labour charges for cutting, bending , binding of bars , including cost,conveyance & taxes of H Y S D bars and binding wire , T & P etc. complete.				
a		Qntl	53.00	10335.35	547774.00
4	20 mm thick grading plaster in C:M (1:4) over roof slab including cost,conveyance and royalty etc complete.				
		sqm	253.70	238.80	60584.00
5	6mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials etc.				
		sqm	268.22	166.90	44766.00
6	12mm (½") thick cement plaster (1:6) finishing smooth to outside smooth surface of brick walls including cost, conveyance, royalties and taxes of all materials and cost of all labour charges .				
a	Ground Floor	sqm	273.55	149.80	40978.00
7	16mm (¾") thick cement plaster (1:6) finished smooth to inside rough surface including cost and conveyance, royalties and taxes of all materials and labour charges .				
a	Ground Floor	sqm	184.42	213.00	39281.00
8	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.				

Slno	Item of the work	Unit	Qty	Rate	Amount
		sqm	991.19	74.70	74042.00
9	Priming one coat over the finished wall surface,including cost, conveyance & taxes etc complete				
a	Ground Floor	sqm	734.32	61.60	45234.00
10	Wall painting with 2 coats with plastic emulsion paint of approved shade on new wrk to give an even shade including cost and conveyance, royalties and taxes of all materials and labour charges . Etc complete				
a	Ground Floor	sqm	469.28	86.15	40428.00
11	Wall painting with 2 coats with weather coat of approved shade on new work to give an even shade including cost, taxes , conveyance etc complete.				
a	Ground Floor	sqm	288.55	83.50	24094.00
12	Supplying of M.S. Door & Window shutters including cost, conveyance & taxes of all labour & material etc complete.				
		Kg	946.75	147.40	139551.00
13	Painting two coats over one coat of primer on new steel work including cost ,conveyance of material & labour charges.				
		sqm	35.64	199.80	7121.00
14	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thickness of 10mm and filling joints with epoxy grout of approved .				
a	Ground Floor	sqm	256.85	989.50	254153.00
15	Supplying fitting & fixing of Stainless steel of 304 grade in hand railing using 50mm. Dia of 2 mm. thick circlar pipe with balustrade of size 2mm @ 0.90 m.c/c and stinless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in case as per approved design and specification, buffing,polishing etc. with cost ,conveyance, taxes of all materials labour T & P etc. required for the				
		Rmt	15.21	3541.40	53865.00
16	Add labour Registration charges				500.00
17	Contygency @1%				18850.00
18	Display Board & Photograp				9000.00
					1884913.00