

## Completion of Mukhya Mantri Sabha Ghara at Chhanchani, GP- Sargul

SR.NO	NAME OF WORK	QTY	UNIT	RATE IN RS	AMOUNT IN RS
1	Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.	19.180	cum	202.90	3892
2	Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.		cum	390.60	5941
3	P.C.C(1:3:6) with 4cm size CBG metal with lowering laying the concrete & curing etc., including supply of all materials labour T&P required for the work with cost ,conveyance & royalty,taxes etc all complete as per the direction of the engineer in charge.	3.770	cum	4955.20	18681
4	R.C.C. M20 with 20mm and 10mm size CBG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work with cost, conveyance, royalty,taxes but	44.690	cum	5411.90	241858
5	Rigid & smooth centering & shuttering for RCC works including false work and dismantling then after casting including all cost of materials .				
a	Beam & wall beam	118.730	cum	714.40	84821
b	SLAB	231.740	cum	461.30	106902
6	Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge	45.000	QNTL	9370.40	421668.00
7	Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm <sup>2</sup> with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C. F&P	4.240	cum	4475.30	18975
I	SUPERSTRUCTER	4.540	cum	4558.34	20695
8	20mm. thick grading plaster in cement mortar (1:4) over roof slab etc comp. (per sqm.)	228.866	sqm	237.90	54447
9	12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)	175.679	sqm	147.90	25983

SR.NO	NAME OF WORK	QTY	UNIT	RATE IN RS	AMOUNT IN RS
10	16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)	336.200	sqm	213.60	71812
11	Supplying fitting & fixing of vetrified tiles in floors of size 600X600 mm of approved make conforming to IS 13755 laid on 20 mm thick cement mortar(1:4) filling joints with white cement of approved quality including cost of all materials etc.	212.528	sqm	1,108.00	235480
12	Fixing tiles ceramic/Glazed in floor treads or steps and landing on 25mm thick bed of cement motar 1:1 joined with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing comp.	33.43	sqm	1,173.40	39230
13	Fixing the tiels in dados skirting risers of steps on the 12mm thick C.P(1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing the polishing landing	23.36	sqm	1,227.60	28677
14	Labour charges for fixing MS Grills,Door and Windows.	1400	KG	108.00	151200
15	Finishing wall surface of wall with Acylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding stagging charges with cost of all materials taxes labour T&P etc	510.691	sqm	82.50	42132
16	Priming one coat with cemenr primer( watwer bound) including all cost etc.	511.878	sqm	68.20	34910
17	Wall painting two coats with Plastic Emulsion painof approved shade on new work etc comp.	510.69	sqm	92.50	47239
18	Wall painting two coats with weather coat of approved shade on new work etc comp.	175.679	sqm	85.30	14985
19	Paining two coats over one coat of primer on new steel work including all cost etc comp.	140.000	sqm	193.00	27020
20	PVC Door	2.000	NOS	3,400.00	6800
21	DISPLY BOARD	1.000	NOS	5000.00	5000.00
<b>TOTAL</b>				<b>RS</b>	<b>1708348</b>