

OFFICE OF THE PANCHAYAT SAMITI, BIRMAHARAJPUR

No : 2457

Date : 30/8/2024

(SHORT TENDER CALL NOTICE)

Block Development Officer, Birmaharajpur on behalf of Government of Odisha invites sealed tender in single cover system from the intending Bidder for execution of works mentioned in the table below. The eligible contractors registered with the State Government and contractors of equivalent Grade/Class registered with Central Government/MES/Railways or other Licensing Authority for execution of Civil works on production of definite proof form the appropriate authority can participate in the BID.

Sl. No.	Name of Work	Estimated Cost put to tender (in Rs.)	EMD	Class of Contractor	Cost of tender paper in (Rs.)	Period of Completion
1	2	3	4	5	6	7
1	• Construction of addl Class Room at Nuapada PS,G.P. Subalaya	12,47,550/-	12,476/-	"C"	6000.00	6 Month

The tenderers are requested to submit valid & up to date photo copy of license, GST Certificate, copy of Pan Card along with tender documents. The tender bids complete in all respect must reach in the address of the **Block Development Officer, Birmaharajpur** through registered post/speed post **on or before 05.30 P.M of dt 13.09.2024** and will be opened **on dt 17.09.2024 at 11.00 A.M** in presence of the tenderers or their authorized representatives willing to be present. BID must be accompanied by EMD/BID security of the amount as specified for the work at Column No.4 of the above table, duly pledged in favour of Block Development Officer, Birmaharajpur. The tender document will be **sold from dt 31.08.2024 to dt. 13.09.2024 10.00 A.M. to 5.30 P.M.** on payment of tender paper cost as noted above to be deposited in the Cash Counter of Panchayat Samiti Office, Birmaharajpur. The tenderer must be mentioned the name of the work in capital letter on the top of the envelop of tender paper to be submitted.

The Authority will not be held responsible for any postal delay in respect of receipt of tender documents and reserves the right to accept or reject any or all tenders without assigning any reason thereof.


Block Development Officer
Birmaharajpur

(page-2)

Memo No. 2458 /Date. 30/8/2024

Copy to DIO,N.I.C, Subarnapur for uploading the detail tender call notice and the bid documents in the official website of Subarnapur i.e. www.subarnapur.nic.in


Block Development Officer
Birmaharajpur

Memo No. 2459 /Date. 30/8/2024

Copy to CDO-cum-EO, Zilla Parisad,Subarnapur/All BDOs of Subarnapur District/ Sub-Collector,Birmaharajpur/ Tahasildar,Birmaharajpur/ CDPO,Birmaharajpur for information and necessary action with request to display in their Notice board for wide circulation.


Block Development Officer
Birmaharajpur

Bill of Quantities

Tender Inviting Authority: Block Development Officer Birmaharajpur

Name of Work: Construction of Additional class room at

Nuapada P.S.

Contract No:

Name of the Bidder/ Bidding Firm / Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER	TEXT	NUMBER	TEXT	NUMBER	NUMBER #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P
1	2	4	5	6	53
1	Earthwork in excavation of foundation trenches in hard soil with initial lead and lift except sheet rock and boulders (requiring blasting) including dressing and levelling the bed upto the required depth and depositing the excavated materials away from the site with all leads and lifts. T and p shoring and shuttering if required etc. complete as directed by engineer-in-charge.	43.830	Cum	269.700	11821.000
2	Supplying and filling in foundation and ditches with sand well watered and rammed in layers not exceeding 23 cm in depth with all lead and lift including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all labour, sundries. T & P required for the work etc complete in all respect as per direction of Engineer incharge.	49.580	Cum	470.610	23333.000
3	Providing & laying plain cement concrete 1:4:8 (1 cement 4 coarse and 8 graded stone aggregate for 40 mm nominal size) in foundation and plinth including cost of hoisting, lowering laying concrete, ramming,	10.710	Cum	5959.400	63825.000
4	2.5 cm Damp proof coarse with cc:(2:4) using 2 mm size hard broken granite chips of approved quality from approved quarry including hoisting, compacting, curing, finishing the exposed surface smooth, dewatering shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty and taxes of all materials, cost of labour and T and P etc complete as per direction of engineer in charge	7.350	sqm	388.700	2857.000
5	Filling in foundation and plinth with excavated materials including watering and ramming as directed by the engineer in charge	43.830		179.800	7881.000

6	Providing , lifting hoisting laying Reinforced cement concrete of M20 grade in column footings , as per approved designs and drawings having a munimum compressive strength (in work test) 200 Kg./ Square cm in 15cm. Cubes at 28 days after mixing and tests conducted in accordance with I.S. 416 using 12mm to 20 mm size black hard crusher broken granite stone ships of approved quality from approved quarry washed and cleaned (20mm size not to exceeds 25%) to be mixed in concrete mixture with ordinary protland cement (OPC) including noisting, lowering lying an dcompacting concrete by susing vibrators, watering and curing for 28 days centering and shuttering and finishing the exposed surface smooth proving grooves or beads wherever necessary including cost conveyance, loading and unloading royalties and taxes of all materials and cost of all labours sunones , T & P required fo rthe work ect complete in all respect excluding cost and conveyance of HYS/MS steel and binding wires , and labour charges for straightaining, cutting , bending etc of M.S. rods of for steel and binding				
		11.240	Cum	7057.720	79329.000
7	Ground Floor Column base				
		2.780	Cum	7923.200	22026.000
8	Plinth Beam				
		7.190	Cum	16176.720	116311.000
9	Column up to Roof level				
		1.120	Cum	14660.640	16420.000
10	Lintel				
		0.590	sqm	14149.800	8348.000
11	Chajja				
		9.670	cum	14149.800	136829.000
12	Roof Slab				
		29.027	qntl	7177.740	208345.000
13	Providing HYS/MS reinforcement for RCC works including bending, binding & placing in position as per Drawing including cost, conveyance of all materials, all labour and T&P				
		7.690	Cum	5557.630	42738.000
14	Fly Ash brick masonay in cemnet mortar of (1.6) with portland slag cement, watering and curing etc. including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all lbaour sundries T& P required for the works etc complete in all respect as directed by the Enginner -in-charge.in F and P				
		19.000	Cum	5590.630	106222.000
15	Ground floor SUPERSTRUCTUR				
		144.000	kg	73.020	10515.000
16	Supplying fitting and fixing steel angle iron door and windows as per approved design and drawing				
		4.550	sqm	7000.000	31850.000
17	Supplying fitting and fixing G.I. pressed door assembly with ploymer powder coated including cost of all materials and fittings etc complete				
		7.900	sqm	23.430	185.000
18	Labour for fitting and fixing doors and windows etc complete				

19	6 mm thick cement plaster(1:4)finished smooth to RCC surface after cleaning the surface including watering,curing etc complete with cost,conveyance royalties and taxex of all materials labour and T and p etc complete as per direction of engineer in charge	95.810	sqm	210.800	20202.000
20	Providing and laying 16 mm cement plaster 1.6 to out side on surface after cleaning the surface taking out point including cost of all materials labour cuting taxes etc complete as per instruction fo architect/ Engineer incharge	140.520		269.140	37820.000
21	Providing and laying 12 mm cement plaster 1.6 to out side on surface after cleaning the surface taking out point including cost of all materials labour cuting taxes etc complete as per instruction fo architect/ Engineer incharge	132.0400		186.700	24652.000
22	20 mm grading plaster(1:4) finished smooth over roof slab after cleaning the surface including watering curing etc complete	75.5500		296.500	22401.000
23	Fixing Kota tiles in dadoes on 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete icluding cost of tile etc complete	8.3600		1036.620	8666.000
24	Fixing Kota tiles in floors on 25mm thick cement plaster(1:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete icluding cost of tile etc complete	76.0700		1330.190	101188.000
25	Distempering two coats to walls with distemper of approved shade on new work to give an even shade excluding cost of distemper.including cost of brushes and putty inlcuding cost of paint(per one Sq. Mtr)(for inside)	80.820	sqm	162.560	13138.000
26	Painting two coats with approved paint to doors and windows over a coat of primer including cost of all materials and labour etc complete	19.1400	sqm	254.040	4862.000
27	Finishign walls with water proofing weather coat of approved shade on new work 2 coats to give an even shade inlcuding cost of brushes and putty inlcuding cost of paint for out side.	160.2100		171.890	27538.000
28	Ramp railing	17.500	sqm	3014.480	52753.000
29	Provision of display board				
30	Provision of black board 12 ft *x 4 ft				3500.000
31	Fire fighting arrangement				5500.000
32	Electrification work				6500.000
	Total in Figures				30000.000
	Limited to		Total		1247555.000

Rs

1247550.000

GST 18%

224559.000

Thirty two items only

TOTAL

1472109.00

(Rupees fourteen lakhs Seventy Two thousand one hundred and nine)only

The Rate quoted by me is
for the above work

(% Excess/Less than the cost put to tender

CONTRACTOR


BLOCK DEVELOPMENT OFFICER
BIRMAHARAJPUR