

OFFICE OF THE PANCHAYAT SAMITI, BIRMAHARAJPUR

No : 2466

Date : 20/8/2024

(SHORT TENDER CALL NOTICE)

Block Development Officer, Birmaharajpur on behalf of Government of Odisha invites sealed tender in single cover system from the intending Bidder for execution of works mentioned in the table below. The eligible contractors registered with the State Government and contractors of equivalent Grade/Class registered with Central Government/MES/Railways or other Licensing Authority for execution of Civil works on production of definite proof from the appropriate authority can participate in the BID.

Sl. No.	Name of Work	Estimated Cost put to tender (in Rs.)	EMD	Class of Contractor	Cost of tender paper in (Rs.)	Period of Completion
1	2	3	4	5	6	7
1	Construction of market complex near Bus-Stand at Birmaharajpur	16,94,915/-	16949/-	"C"	6000.00	6 Month

The tenderers are requested to submit valid & up to date photo copy of license, GST Certificate, copy of Pan Card along with tender documents. The tender bids complete in all respect must reach in the address of the **Block Development Officer, Birmaharajpur** through registered post/speed post **on or before 05.30 P.M of dt 13.09.2024** and will be opened **on dt 17.09.2024 at 11.00 A.M** in presence of the tenderers or their authorized representatives willing to be present. BID must be accompanied by EMD/BID security of the amount as specified for the work at Column No.4 of the above table, duly pledged in favour of Block Development Officer, Birmaharajpur. The tender document will be **sold from dt 31.08.2024 to dt. 13.09.2024 10.00 A.M. to 5.30 P.M.** on payment of tender paper cost as noted above to be deposited in the Cash Counter of Panchayat Samiti Office, Birmaharajpur. The tenderer must be mentioned the name of the work in capital letter on the top of the envelop of tender paper to be submitted.

The Authority will not be held responsible for any postal delay in respect of receipt of tender documents and reserves the right to accept or reject any or all tenders without assigning any reason thereof.


Block Development Officer
Birmaharajpur

(page-2)

Memo No. 2467 /Date. 30/8/2024

Copy to DIO,N.I.C, Subarnapur for uploading the detail tender call notice and the bid documents in the official website of Subarnapur i.e. www.subarnapur.nic.in


**Block Development Officer
Birmaharajpur**

Memo No. 2468 /Date. 30/8/2024

Copy to CDO-cum-EO, Zilla Parisad,Subarnapur/All BDOs of Subarnapur District/ Sub-Collector,Birmaharajpur/ Tahasildar,Birmarajpur/ CDPO,Birmaharajpur for information and necessary action with request to display in their Notice board for wide circulation.


**Block Development Officer
Birmaharajpur**

CONSTRUCTION OF MARKET COMPLEX NEAR BUS STAND B.M PUR .

Sl Nn	Description	Unit	Qty	Rate	Amount
1.	Excavation of foundation trench in hard soil including dressing of sides and leveling of bed etc. complete	cum	60.76	Rs.210.96	Rs.12818.00
2.	Filling sand in foundation and plinth well watered and rammed including cost.	Cum	64.58	Rs.584.82	Rs.37768.00
3.	Cement concrete (1:3:6) using 40mm size h.g. metal including cost ,conveyance and royalty etc. complete.	Cum	18.8	5881.63	110575.00
4.	R.C.C. work of m-20 grade with 20mm and down grade black hard granite (crusher royalty of all materials etc . complete	Cum	42.85	Rs.6474.24	Rs.277421.00
5.	Supplying , fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification .	Qtl	42.85	RS.8693.02	Rs.372496.00
6.	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantlingthem after casting including cost of materials complete in ground floor-roof slab and chajja	Sqm	158.65	Rs.676.54	Rs.107333.00
7.	Rigid and smooth centering and shuttering for R.C.C. work including falseworks ground floor-footings and plinth bend	Sqm	28.05	Rs.240.06	Rs.6722.00
8.	Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cust of materials complete in ground floor-beams and columns.	Sqm	84.0	Rs.1021.65	Rs.85819.00
9.	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling thm after casting including cost of materials complete in ground	Sqm	27.48	Rs.529.09	Rs.14539.00
10.	Brick works with fly ash bricks 25cm x 12cmx8cm size having crushing strength (1:6) in foundation & plinth.	Cum	15.2	Rs.5145.75	Rs.78215.00
11	Brick works with fly ash bricks 25cm x 12cmx8cm size having crushing strength not less then 75kg/cm2 with dimensional tolerance + 8 peercent cement mortar (1:6) in super structure	Cum	41.7	Rs.5184.07	Rs216176.00
12.	2.5cm thick A.S.flooring using c.c. (1:2:4)with 12mm size c.b.g. chips including cost conveyance and royalty etc.complete.	Sqm	36.46	Rs.358.95	Rs13087.00
13.	2 coats of painting over new M.S.doors and windows including 1 cost of priming T&P and labour charges etc complete .	Sqm	108.05	Rs.59.71	Rs.6452.00
14	2 coats of painting over new M.S.doors and windows including 1 cost of priming T&P and labour charges etc complete	Sqm	108.05	Rs.156.59	Rs16920.00
15.	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	Sqm	178.28	Rs.85.97	Rs.15327.00
16.	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	Sqm	294.97	Rs.93.89	Rs.27695.00
17.	12mm thick cement mortar plaster(1:6)on brik masonry walls including cost conveyance & royalty etc.complete.	Sqm	197.93	Rs.157.88	Rs.31249.00
18.	6mm thick cement plastar (1:4)on R.C.C. works including	Sqm	42.86	Rs.175.41	Rs.7518.00

	closely deep chipping and slurry treatment plaster including copst, conveyance and royalty etc. complete.				
19.	16mm thick cement mortar plaster (1:6) on briks masonry walls including coast ,conveyance and royalty etc.complete.	Sqm	199.62	Rs224.63	Rs.44841.00
20.	20mm thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost , conveyance and royalty etc.complete.	Sqm	131.76	Rs.251.55	Rs.33144.00
21.	Finicing wall surface of wall with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes , labour T&P etc. complete .	Sqm	294.97	Rs.77.04	Rs.22724.00
22.	Priming 1 coat with any approved primer on newly plastered wall surface	Sqm	473.25	Rs.65.11	Rs.30813.00

23. Provisional cost for M.S.rolling shutters at door opening 1000/Q @ 125/Kg = 1,25,000.00

24. Display board and photograph Rs.265.00

Total Amount Rs.1694915.00

(Rupees sixteen lakhs nintyfour thousand nine hundred fifteen only)


J.E.

B.M.PUR


AEE.

B.M.PUR


BDG

B.M.PUR