

OFFICE OF THE PANCHAYAT SAMITI, BIRMAHARAJPUR

No: 2472

Date: 30/8/2024

(SHORT TENDER CALL NOTICE)

Block Development Officer, Birmaharajpur on behalf of Government of Odisha invites sealed tender in single cover system from the intending Bidder for execution of works mentioned in the table below. The eligible contractors registered with the State Government and contractors of equivalent Grade/Class registered with Central Government/MES/Railways or other Licensing Authority for execution of Civil works on production of definite proof from the appropriate authority can participate in the BID.

Sl. No.	Name of Work	Estimated Cost put to tender (in Rs.)	EMD	Class of Contractor	Cost of tender paper in (Rs.)	Period of Completion
1	2	3	4	5	6	7
1	Construction of Kalyan Mandap Champamal G.P.	17,64,587/-	17646/-	"C"	6000.00	6 Month

The tenderers are requested to submit valid & up to date photo copy of licence, GST Certificate, copy of Pan Card along with tender documents. The tender bids complete in all respect must reach in the address of the **Block Development Officer, Birmaharajpur** through registered post/speed post **on or before 05.30 P.M of 13.09.2024** and will be opened **on dt 17.09.2024 at 11.00 A.M** in presence of the tenderers or their authorized representatives willing to be present. BID must be accompanied by EMD/BID security of the amount as specified for the work at Column No.4 of the above table, duly pledged in favour of Block Development Officer, Birmaharajpur. The tender document will be **sold from dt 31.08.2024 to dt. 13.09.2024 10.00 A.M. to 5.30 P.M.** on payment of tender paper cost as noted above to be deposited in the Cash Counter of Panchayat Samiti Office, Birmaharajpur. The tenderer must be mentioned the name of the work in capital letter on the top of the envelop of tender paper to be submitted.

The Authority will not be held responsible for any postal delay in respect of receipt of tender documents and reserves the right to accept or reject any or all tenders without assigning any reason thereof.


**Block Development Officer
Birmaharajpur**

(page-2)

Memo No. 2473

/Date. 30/8/2024

Copy to DIO,N.I.C, Subarnapur for uploading the detail tender call notice and the bid documents in the official website of Subarnapur i.e. www.subarnapur.nic.in


**Block Development Officer
Birmaharajpur**

Memo No. 2474

/Date. 30/8/2024

Copy to CDO-cum-EO, Zilla Parisad,Subarnapur/All BDOs of Subarnapur District/ Sub-Collector,Birmaharajpur/ Tahasildar,Birmaharajpur/ CDPO,Birmaharajpur for information and necessary action with request to display in their Notice board for wide circulation.


**Block Development Officer
Birmaharajpur**

CONSTRUCION OF KALYAN MANDAP B.M PUR .

SI Nn	Description	Unit	Qty	Rate	Amount
1.	Earth work excavation in hard soil with initial lead and initial lift including dressing and leveling the foundation bed and depositing the excavated earth away from worksite etc complete	Cum	37.958	208.14	7900.62
2.	Supplying filling in foundation and plinth with sand ,watered and rammed including cost conveyance & royailty and all taxes of matarials cost of all labour with T&P etc complete.	Cum	41.511	600.20	24914.91
3.	Cement concrete (1:4:8) with 40mm size H.G.C.B. metal including cost conveyance and .	Cum	14.739	5027.40	74100.00
4.	Briks works with 1 st class fly ass Briks 25cmx12cmx8cmhaving crushing strength not less than 75kg/cm2 with dimensional tolerance ± 8 % in cm (1:6) in superstructure .	Cum Cum	7.719 29.359	4882.60 4920.50	37691.00 144460.00
5.	RCC M-20 work with 20mm down gradecourse aggragate including hoisting and laying .	Cum	34.799	5744.90	199920.00
6.	HYSO steel (Fe-415) cutting bending cracking hooking welding or jointing (if rrequired) the M.S. rod or HYSO steel and binding tying the qrills hoisting lowering and placing in proper position	Qntl	31.320	8725.70	273285.00
7.	Rigid and smooth centering & suttering for RCC works including false works and dismantaling than after coasting including cost of mataraials	Sqm Sqm Sqm Sqm	77.565 25.957 86.390 109.121	107.80 279.20 760.70 490.20	8362.00 7247.00 65717.00 53736.00
8.	20mm thick grading plaster in C:M (1:4) to RCC over roof slab including cost conveyance and royalty	Sqm	109.621	225.03	24668.00
9.	6mm thiock cement plastar in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost conveyance & royality of room	Sqm	58.527	130.20	7620.22
10.	12mm(1/2)thick cement plastar (1:6)finising smooth to outside smooth surface of brick wallsafter racking out the joint including watering out side	Sqm	118.721	147.50	17511.00
11	16mm(1/2)thick cement plastar (1:6)finising smooth to intside rough surface of 9"/10" thick brick walls after racking out the joint including inside	Sqm	71.101	211.10	15009.00
12.	Priming 1 coat with wall cement primer (water bound) including cost conveyance etc complete	Sqm	819.822	69.80	57224.00
13.	Wall painting with 2 coats with water cost of approved shade on new work to give an even shade including cost convyanc etc complete	Sqm	118.721	87.00	10329.00
14	Wall paiting with 2 coat with plastic emulation paints of approved shade on new work to give an even shade including cost conveyance etc	Sqm	748.721	93.80	70230.00
15.	Add cost of iron shutter	Kg	1262.50	90.00	113625

16.	Supplying fitting and fixing vitrified floor tile 600mm*600mm	Sqm	91.042	1060.90	96586.00
17.	Supplying fitting and fixing ceramic tiles toilet	Sqm	4.65	874.30	4061.00
18.	Painting 2 coat over 1 coat of primer on new steel work including labour and material charges including cost ,conveyance etc complete	Sqm	807.125	221.00	38896.00
19.	Supplying fitting and fixing UPVC window	Sft Sft	198.00 56.00	500.00 720.00	99000.00 40320.00
20.	Add cost of display Board	Ls			3000.00

TOTAL- 1495412.75
ADD SGST+CGST -18% 269174.29

G total 1,764,587.00

(Seventeen lakhs sixty four thousand five hundredeightyseven only)



Junior Engineer
Birmaharajpur Block



Asst Ex Engineer
Birmaharajpur Block



BDO
Birmaharajpur Block