

OFFICE OF THE PANCHAYAT SAMITI, BIRMAHARAJPUR

No: 2980

Date: 23/09/2024

(SHORT TENDER CALL NOTICE)

Block Development Officer, Birmaharajpur on behalf of Government of Odisha invites sealed tender in single cover system from the intending Bidder for execution of works mentioned in the table below. The eligible contractors registered with the State Government and contractors of equivalent Grade/Class registered with Central Government/MES/Railways or other Licensing Authority for execution of Civil works on production of definite proof form the appropriate authority can participate in the BID.

Sl. No.	Name of Work	Estimated Cost put to tender (in Rs.)	EMD	Class of Contract or	Cost of tender paper in (Rs.)	Period of Completion
1	2	3	4	5	6	7
1	• Construction of 100 MT Godown for storage of seeds and Fertilizer at PACs/Lamps at Jatesingha .	Rs. 25,66,102.00	Rs. 25,661.00	"C"	6000.00	6 Month
2	• Construction of Kalyan Mandap at Kamalpur.	Rs. 29,53,949.00	Rs. 29539.00	"C"	6000.00	6 Month

The tenderers are requested to submit valid & up to date photo copy of license, GST Certificate, copy of Pan Card along with tender documents. The tender bids complete in all respect must reach in the address of the Block Development Officer, Birmaharajpur through registered post/speed post on or before **2.00 P.M** of dt **06.10.2024** and will be opened on dt **07.10..2024** at **3.00 P.M** in presence of the tenderers or their authorized representatives willing to be present. BID must be accompanied by EMD/BID security of the amount as specified for the work at Column No.4 of the above table, duly pledged in favour of Block Development Officer, Birmaharajpur. The tender document will be sold from dt 25.09.2024 to dt. 06.10.2024 10.00 A.M. to 5.30 P.M. on payment of tender paper cost as noted above to be deposited in the Cash Counter of Panchayat Samiti Office, Birmaharajpur. The tenderer must be mentioned the name of the work in capital letter on the top of the envelop of tender paper to be submitted.

The Authority will not be held responsible for any postal delay in respect of receipt of tender documents and reserves the right to accept or reject any or all tenders without assigning any reason thereof.


Block Development Officer
Birmaharajpur

(page-2)

Memo No. 2781

/Date. 23/09/2024

Copy to DIO, N.I.C, Subarnapur for uploading the detail tender call notice and the bid documents in the official website of Subarnapur i.e. www.subarnapur.nic.in for information of the public/prospective bidders.


Block Development Officer
Birmaharajpur

Memo No. 2782

/Date. 23/09/2024

Copy submitted to CDO-cum-EO, Zilla Parishad, Subarnapur/D.I.P.R.O., Subarnapur for wide publication All BDOs of Subarnapur District/ Sub-Collector, Birmaharajpur/ Tahasildar, Birmaharajpur/ CDPO, Birmaharajpur for information and necessary action with request to display in their Notice board for wide circulation.


Block Development Officer
Birmaharajpur

Memo No. 2783

/Date. 23/09/2024

Copy to Cashier, of this Office for information. Copy to Notice Board.


Block Development Officer
Birmaharajpur

Memo No. 2784

/Date. 23/09/2024

Copy forwarded to the Joint Director (Advertisement) I & P.R. Deptt. Govt. of Odisha, Bhubaneswar with a request to publish the Tender Call Notice in two Odia daily widely circulated news paper in all Odisha edition in minimum space for one day and the complementary copies of the News Paper may be sent to this Office for reference and record.


Block Development Officer
Birmaharajpur


ABSTRACT OF ESTIMATE

Construction of 100 MT godown for storage of seeds and fertilizer at Pacs/Lamps at Jatesingha

Sl	Description of items	Qty	Unit	Rate	Amount
1	Earthwork excavation in hard soil with initial lead and initial lift including dressing and levelling the foundation bed and depositing the excavated earth away from worksite etc complete.	101.57	cum	₹ 212.36	₹ 21,569.00
2	Supplying, filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty and all taxes of materials cost of all labour with T&P etc. complete.	109.11	cum	₹ 601.20	₹ 65,597.00
3	Filling F & P with excavated materials including cost of all labour, T &P etc. complete.	101.57	cum	₹ 207.00	₹ 21,025.00
4	Cement concrete (1:3:6) with 40 mm size H.G.C.B metal including cost, conveyance and royalty etc.	20.99	cum	₹ 5,403.40	₹ 1,13,417.00
5	Brick work with 1st class FLY ASS Bricks 25cmx12cmx8cm having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% in cm(1:6) in foundation and plinth	43	cum	₹ 4,917.70	₹ 2,11,461.00
6	R.C.C. M-20 grade concrete using 20mm and down grade c.b.g. chips including cost, conveyance and royalty etc. complete				
	A. plinth bend	6.55	cum	₹ 6,300.40	₹ 41,268.00
	B. column base	10.79	cum	₹ 5,919.95	₹ 63,876.00
	C. column & beam upto 5.0m height	12.04	cum	₹ 11,927.30	₹ 1,43,605.00
	D. Lintel bend	3.45	cum	₹ 9,702.10	₹ 33,472.00
	E. column & beam above 5.0m height	1.85	cum	₹ 12,258.96	₹ 22,679.00
	F. Wall bend	5.24	cum	₹ 9,914.15	₹ 51,950.00
7	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and	45.33	qntl	₹ 8,734.90	₹ 3,95,953.00
8	Cement concrete (1:2:4) using 12mm c.b.g. chips including cost, conveyance & royalty etc. complete	10.73	cum	₹ 6,758.10	₹ 72,514.00
9	Brick work with 1st class FLY ASS Bricks 25cmx12cmx8cm having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% in cm(1:6) in superstructure.				
	upto 3.0m height	37.56	cum	₹ 4,955.60	₹ 1,86,132.00
	above 3.0 m height	59.71	cum	₹ 4,988.60	₹ 2,97,869.00
10	12mm (½") thick cement plaster (1:6) finishing smooth to outside smooth surface of brick walls after racking out the joint including watering and curing with cost, conveyance, royalties etc complete.				
	upto 3.0 m height	196.5	sqm	₹ 149.60	₹ 29,396.00
	above 3.0m height	252.23	sqm	₹ 155.80	₹ 39,297.00
11	16mm (¾") thick cement plaster (1:6) finished smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost and conveyance, royalties etc				
	upto 3.0 m height	262.83	sqm	₹ 214.30	₹ 56,324.00
	above 3.0m height	91.01	sqm	₹ 219.70	₹ 19,995.00
12	Supplying , fitting and fixing of M.S. rolling shutters of approved specification and size	474	kg	₹ 100.00	₹ 47,400.00
13	Supplying , fabricating, fitting and fixing of M.S. Angular trusses & purlins approved specification and size	500	kg	₹ 132.17	₹ 66,085.00
14	Painting 2 coat on new iron works including cost, conveyance and royalty etc. complete	149.5	sqm	₹ 224.00	₹ 33,488.00
15	Supplying fitting and fixing of PGCL sheets in roof including fixing of ridgres , J hooks, washers windties etc. complete	187.96	sqm	₹ 836.55	₹ 1,57,238.00
16	Supplying fitting and fixing of holding down bolts (600mm x 200mm) & base plate of 8mm thick ness including all cost labour etc. complete.	90	kg	₹ 100.00	₹ 9,000.00
17	Cost of J hooks & nuts etc, 5/8" x 21/2" nut & bolt for trusses & purlins	75	kg	₹ 100.00	₹ 7,500.00

18	Distemping 2 coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper upto 3.0m height above 3.0m height	196.5 sqm	₹	76.80 ₹	15,091.00
19	Weather coat two coats on newly plastered wall surfaces including cost, conveyance and royalty etc. complete upto 3.0m height above 3.0m height	252.2 sqm	₹	80.64 ₹	20,337.00
20	Antitermite treatment in foundation trenches in foundation trenches , flooring sub grade, including all cost labour etc. complete	262.83 sqm	₹	88.00 ₹	23,129.00
21	Labour charges for fixing glass strips of depth 0.075m in joints in floor per 1m including cost of glasses	91.01 sqm	₹	88.00 ₹	8,009.00
22	cement punning with red oxide mix using 3.5kg of red oxide per 50 kg of cement 1:3 polishing with carborandum stone	55.84 sqm	₹	88.63 ₹	4,949.00
23	Supplying and fixing of steel ventilation (600mm x 600mm) glazed composite with M.S. Grills out side iron frame with glass pairs including suppling & fixing of putty & wire clips screw & nails & cost of materials	69.5 rmt	₹	50.82 ₹	3,532.00
24	Supplying & fitting,fixing of steel ventilator glazed composite with M.S. Grill outside iron frame welded with wire netting or mesh with glass pairs including supplying & fixing of putty & wire clips, screw & nails & cost of materials.	112.5 sqm	₹	64.48 ₹	7,254.00
25	Supply of fittings and fixing chlorinated poly vinyl chloride (CPVC) pipes with all fittings	0.36 sqm	₹	2,568.67 ₹	925.00
	15mm nominal outer dia pipes	5.76 sqm	₹	2,568.67 ₹	14,796.00
	20mm nominal outer dia pipes	10 mtr	₹	27.94 ₹	279.00
	35mm nominal outer dia pipes	10 mtr	₹	28.94 ₹	289.00
	32mm nominal outer dia pipes	15 mtr	₹	29.94 ₹	449.00
26	15mm dia CP bib cock	30 mtr	₹	30.94 ₹	928.00
27	15mm dia cp stop cock	2 no	₹	637.30 ₹	1,275.00
28	25 mm dia pvc full way valve	2 no	₹	600.00 ₹	1,200.00
29	32mm dia full way valve	2 no	₹	588.40 ₹	1,177.00
30	providing fitting and fixing first quality Hindware parryware basin	2 no	₹	703.20 ₹	1,406.00
31	providing fitting and fixing first quality Hindaware, parryware odisha type pan	1 no	₹	1,486.90 ₹	1,487.00
32	Recessing wiring to light point in 1.5mm sqmm FR PVC insulated single core multistrand copper conductor of ISI marked in:-	1 no	₹	3,896.60 ₹	3,897.00
	Light point	6 no	₹	672.20 ₹	4,033.00
	Ceiling fan point	1 no	₹	672.20 ₹	672.00
	Exhaust fan point	1 no	₹	672.20 ₹	672.00
33	MCB distribution board	2 no	₹	3,248.90 ₹	6,498.00
34	Earthing	1 no	₹	2,340.20 ₹	2,340.00
35	External elctricity supply/installation ,Installation of a Bore well with submersible pump (as per direction of engineer-in-charge)	1 no	₹	2,05,461.00 ₹	2,05,461.00
37	Cess for welfare of labourers				₹ 25,407.00
38	Display board and photograph				₹ 2,500.00
					₹ 25,66,102.00
					₹ 4,61,898.00
					₹ 30,28,000.00

(Rupees thirty lakh twenty eight thousar


 Junior Engineer
 Birmaharajpur Block Office


 Assistant Executive Engineer
 Birmaharajpur Block Office


 B.D.O.
 B.M. Pur

Name of the work:- Construction of Kalyan Mandapa at Kamalpur
 Estimated Cost:- ₹ 39,29,000.00 Head of Account:- W.O.D.C.(2023-24)

Sl. No.	Description	Quantity	Unit	Rate	Amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	67.036	m ³	₹ 208.14	₹ 13,953.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	155.729	m ³	₹ 600.20	₹ 93,469.00
3	Cement concrete (1:4:8) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	29.64	m ³	₹ 5,048.60	₹ 1,49,641.00
4	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth	26.292	m ³	₹ 4,890.90	₹ 1,28,592.00
5	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure(in ground floor)	51.569	m ³	₹ 4,928.80	₹ 2,54,173.00
6	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure(in first floor)	10.429	m ³	₹ 5,289.80	₹ 55,167.00
7	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	75.666	m ³	₹ 5,787.90	₹ 4,37,947.00
8	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	64.316	qtl	₹ 8,725.70	₹ 5,61,202.00
9	2.5cm thick grading concrete (1:2:2) on roof slab top with 4.7mm size c.b.g. chips including cost, conveyance and royalty. Etc. complete	198.6	m ²	₹ 317.30	₹ 63,016.00
10	Rigid & smooth centering and shuttering of R.C.C. works including all false works, and dismantling after casting etc. complete.				
	a) plinth bend footing etc.	107.487	m ²	₹ 107.80	₹ 11,587.00
	b) lintel bend	27.222	m ²	₹ 279.20	₹ 7,600.00
	c) roof slab and chajjas	268.559	m ²	₹ 490.20	₹ 1,31,648.00
	d) columns and beams	162.471	m ²	₹ 760.70	₹ 1,23,592.00
	e) R.C.C. stairs including railing excluding landing	9.216	m ²	₹ 631.50	₹ 5,820.00
11	Supplying, fitting and fixing vitrified tile in floors of size 600mm x 600mm of approved make with application of cement mortar bed of required thickness and filling joints with white cement of approved quality including cost of all materials, labour T&P etc required for the work.	165.091	m ²	₹ 1,062.30	₹ 1,75,376.00
12	Fixing vitrified tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	11.859	m ²	₹ 1,501.60	₹ 17,807.00
	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	12.715	m ²	₹ 1,146.80	₹ 14,582.00
	Fixing ceramic glazed tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles				
14	including rubbing and polishing complete including cost of precast tiles	29.008	m ²	₹ 1,270.40	₹ 36,852.00
	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. co				
15	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	198.602	m ²	₹ 130.50	₹ 25,918.00
16	16mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	208.457	m ²	₹ 148.00	₹ 30,852.00
17	20mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete	378.165	m ²	₹ 211.70	₹ 80,058.00
18		52.668	m ²	₹ 221.93	₹ 11,689.00

