

Panchayati Raj & Drinking Water Department
PANCHAYAT SAMITI OFFICE, DUNGURIPALI, DIST.SUBARNAPUR
INVITATION FOR BIDS

Tender Notice No. **01/2024-25** Date: 08.10.2024

TENDER CALL NOTICE

A. Block Development Officer Dunguripali on behalf of Government of Odisha invites Sealed tenders in single cover system from the intending Bidders for execution of works mentioned in the table below. The eligible contractors registered with the State Government and contractors of equivalent Grade / Class registered with Central Government / M.E.S. / Railways or other Licensing Authorities for execution of Civil works on production of definite proof from the appropriate authority can participate in the BID.

(TABLE)

Sl. No	Name of the work	Name of Schemes	Value of Work (Rs.)	Amount of Security (EMD) (Rs.)	Amount of Tender Paper cost (Rs.)	Period of Completion	Class of Contract or
1	2	3	4	5	6	7	8
1	Construction of Additional Class Room at Majhimunda Upper Primary School, GP-Bandhpali	RMSA	9,92,140	9,921	6,000	(04) Four Calendar months	"C & D"
2	Construction of Library at Anchalik High School, Bhimtikra, GP-Bhimtikra	RMSA	11,78,882	11,789	6,000	(04) Four Calendar months	"C & D"
3	Construction of Additional Class Room at Badkarley Upper Primary School, GP-Badkarley	RMSA	12,47,689	12,477	6,000	(04) Four Calendar months	"C & D"
4	Construction of Additional Class Room at Thenganal Primary School, GP-Samaleichuan	RMSA	12,47,689	12,477	6,000	(04) Four Calendar months	"C & D"
5	Construction of Additional Class Room at Pankel Upper Primary School, GP-Samaleichuan	RMSA	12,47,689	12,477	6,000	(04) Four Calendar months	"C & D"
6	Completion of Mandap near Tank at Khuntpali, GP-Chinajuri	WODC	7,78,022	7780	6000	(04) Four Calendar months	"C & D"

7	Completion of Kalyan Mandap at Talipada, VIII/ GP- Lingamarni	WODC	13,89,494	13,895	6000	(04) Four Calendar months	"C & D"
8	Construction of KGBV Hostel Building at Mayabarha Nodal UPS, Mayabarha, GP- Mayabarha	RMSA	84,46,224	84,462	10000	(12) Twelve Calendar Months	" B "

- B. The Tender Call Notice, DTCN with tender document can be down loaded from the District Portal www.subarnapur.nic.in.
- C. The tender document will be available in the website from dt. **09.10.2024 to dt. 27.10.2024**. The Bidder for participation in the BID will have to pay the cost of tender paper as mentioned in column-6 only in shape of Demand Draft (Nonrefundable) from any nationalized bank drawn in favour of Block Development Officer, Dunguripali payable at Dunguripali.
- D. BID must be accompanied by EMD/BID security of the amount as specified for the work Column No-5 of the above table, duly pledged in favour of Block Development Officer, Dunguripali. BID security will have to be in any one of forms as specified in the Bidding documents i.e. Demand draft / T.D.R from any Nationalized Bank. BID must be accompanied with valid PAN card, valid GSTIN registration certificate & Contractors Registration Certificate.
- E. The tender document completing in all respect will be received in the office of the Block Development Officer, Dunguripali from **14.10.2024 to 28.10.2024 up to 5.00 PM** through Registered /Speed Post only. The documents must be superscripted as "Name of the work with location". Tender document received after **5.00 pm of 28.10.2024** will not be considered. In case of any postal delay the authority shall not be held responsible. The Tender will be opened on **Dt. 29.10.2024 at 11.00 AM** in the office chamber of Block Development Officer, Dunguripali in presence of the Bidders or his authorized representatives.
- F. Additional performance security shall be obtained from the Bidder when the BID amount is less than the estimated cost put to tender. In such an event, only the successful Bidder who has quoted less BID price/rates than the estimated cost put to tender shall have to furnish the exact amount on the basis of differential cost i.e. estimated cost put to tender minus the quoted amount as Additional Performance Security (APS) in shape of Demand Draft / Term Deposit Receipt pledged in favour of the Block Development Officer, Dunguripali within seven days, otherwise the BID shall be cancelled and the security deposit shall be forfeited.

APS amount to be submitted by the Bidders.

SL. No	Range of Difference between the Estimated cost put to Tender and Bid amount	Additional Performance Security to be deposited by the successful Bidder
I	Below 5%	No Additional Performance Security
II	From 5% and above and below 10%	50% of (Difference between work value cost put to Tender and Bid amount
II	From 10% and above	150% of (Difference between estimated cost put to Tender and Bid amount

- G. The intending tenderer(s) should have-not abandoned any work nor their contract should have been rescinded during the last five years.
- H. The Block Development Officer, Dunguripali reserves the right to reject any or all the tenders without assigning any reasons. Other details can be seen in the BID document.


Block Development Officer,
Dunguripali

Memo No. 5085

//Date. 08.10.2024

Copy to N.I.C. Subarnapur for uploading the detail tender call notice and the bid documents in the official website of Subarnapur i.e. www.subarnapur.nic.in


Block Development Officer
Dunguripali

Memo No. 5086

//Date. 08.10.2024

Copy submitted to the Collector & District Magistrate, Subarnapur for favour of kind information.


Block Development Officer
Dunguripali

Memo No. 5087

//Date. 08.10.2024

Copy submitted to the CDO-cum-EO, ZP, Subarnapur/ Sub- Collector Sonepur/ Birmaharajpur for favour of kind information.


Block Development Officer
Dunguripali

Memo No. 5088

//Date. 08.10.2024

Copy forwarded to All District Level Officers, Subarnapur/All BDOs of Subarnapur District/ All Tahasildars of Subarnapur District/CDMO, Subarnapur /IIC, Dunguripali Police Station/ Notice Board Dunguripali Block/ Case record for information and wide circulation.


Block Development Officer
Dunguripali

TERMS & CONDITIONS

1. BID must be accompanied by BID security (EMD-1%) of the amount specified for the work in the table above in any one of the forms as specified in the Bidding document, TDR of any Nationalized Bank Payable at Dunguripali duly pledged in favour of the Block Development Officer, Dunguripali. BIDs must also be accompanied by self-attested Xerox copies of GSTIN registration certificate, PAN card and valid contract registration certificate, and all others up to date.
2. BIDs must be accompanied with cost of tender document as per Col.No.6 as specified, in shape of demand draft towards BID cost issued from any Nationalized Bank, in favour of The Block Development Officer, Dunguripali payable at Dunguripali.
3. The Tender should be submitted in 1 no. of BID and the BID document should be communicated to the Block Development Officer, Dunguripali At-PO Dunguripali Dist. Subarnapur, Odisha PIN-767023 in single sealed cover of A4 size Paper as per check List, by Regd. Post/ Speed Post on or before the schedule date and time.
4. The BID will be opened on **Dt. 29.10.2024 at 11.00 AM** in the Office of the undersigned, in presence of the members of tender committee of Block Development Officer, Dunguripali and the Bidders or their authorized agent who wish to attend at the meeting hall of Panchayat Samiti Office, Dunguripali. During the time of opening & verification, the original documents must be produced for verification, failing which the tender will be rejected. If the Office happens to be closed on the date of receipt of the BIDs as specified the BIDs will be received on the next working day at the same time and venue respectively.
5. In case of Engineer contractors seeking exemption of E.M.D. in this work are instructed to produce an affidavit regarding his list of works awarded during current financial year **2024-25** with exemption of E.M.D.
6. Schedule Caste & Scheduled Tribe Tenderers will be given price preference where their tenders are within 10% of the rate quoted by the lowest tenderer, for any work, the work may be considered for award to him / them at the lowest tendered rate. (To avail of this benefit Bidder must submit an affidavit along with the cast certificate while submitting the tender paper).
7. No relation certificate in shape of affidavit in original shall be produced along with the tender paper without which the tender will be liable for rejection.
8. The tenderers while submitting tender shall furnish an affidavit along with the tender about the authenticity of the tender documents including E.M.D. The conditional tender will not be accepted on any circumstances by the authority.
9. The Block Development Officer, Dunguripali reserves the right to reject any or all the tenders without assigning any reason thereof.
10. The Bidders shall carefully study the tentative drawings and specifications applicable to the contract and all documents which will form a part of the agreement to be entered into by the accepted Bidder and detailed specification for Odisha and other relevant specifications and drawings which are available at www.subarnapur.nic.in . Complaint at a future date that plans and specifications have not been seen by the Bidders cannot be entertained.
11. The drawings furnished with the BID are tentative and subject to revision or modification during the execution as per actual necessity. But the tendered rates quoted by the Bidder will hold well in case of such modification and shall in no way invalidate the contract and no extra monetary compensation will be entertained. The work shall however be executed as per final approved

drawing to be issued by the Engineer-in-charge as and when required.

12. All rates should be for finished item of works mentioned in the tender schedules.
13. The Bidder should quote the (%) percentage rates over the amount put to tender both in figure and words for the work.
14. Every Bidder is expected before quoting his/her rates to inspect the proposed work site and should also inspect the quarries and approach roads to quarries and satisfies him/her about the quality and availability of materials. Complaints at future date that the availability of materials at quarries has been misjudged cannot be entertained.
15. The Bidder may at his option quote reasonable % percentage rate for the work carefully during fill up so that it should not be unworkable during execution.
16. The BID containing the extraneous conditions not covered by the DTCN are liable for rejection and quotations should be strictly in accordance with the tender call notice. Any change in the wording will not be accepted.
17. The authority reserves the right to reject any or all the BIDs received without assigning any reasons thereof what so ever.
18. As per Works Department Memorandum No.12366 dt.08/11/2013, if the rate quoted by the Bidder is more than 15% of the tender amount, then such a BID shall be rejected and tender shall be finalized basing on the merits of rest BIDs. But if more than one BID is quoted at 14 .99% (Decimals up to two numbers will be taken for all practical purpose) less than the estimated cost, the tender accepting authority will finalize the tender through the transparent lottery system, where all Bidders/their authorized representatives, the Block Development Officer Dunguripali with the members of Tender Committee will present.
19. BIDs not accompanied by required amount of Tender paper cost, E.M.D, A.P.S. or exemption order as per Works Department Memorandum No.288838, dt.18.12.95 will be summarily rejected.
20. The earnest money will be retained in the case of successful Bidder and will be dealt with as per the terms and conditions of the O.P.W.D. Code and will not carry any interest. The earnest money of the un-successful Bidders will be refunded on application after the BID is finally accepted.
21. The BID documents received after due date and time will not be entertained.
22. NO RELATION CERTIFICATE: -
The Bidder shall furnish a certificate along with the tender to the effect that he/she is not related to any Officer in the rank of Asst. Engineer, B.D.O., Under Secretary and above in Panchayati Raj Department. If the fact subsequently proved to be false, the contract is liable to be rescinded. The earnest money and total security will be forfeited.
23. WORK EXPERIENCE: -
(i) Each tenderer is to submit along with tender a note regarding his experience on construction of similar nature of work. The above information should be certified by the concerned authority not below the rank of Executive Engineer.
(ii) The prospective applicant in its name should furnish list of similar nature of works executed in Schedule-D-I satisfactorily completed and list of works in progress in Schedule-D-II. The certificate to be furnished by the employer not below the rank of BDO Dunguripali
24. No Bidder will be permitted to furnish their BID in their own manuscript paper.
25. The Bidder whose BID is selected for acceptance and who has no fixed deposit with the Govt. of Odisha, shall within a period of seven days upon written intimation being given to him/her BID make an initial security deposit (ISD) @ 1% of the tendered amount in the form of Demand Draft

of any nationalized bank and in no other form so that the EMD and ISD will be 2% (two percent) of the tendered amount and sign the agreement in the P.W.D form F2 (Schedule XLV No.61) for the fulfillment of the contract in the "Office of the BDO Dunguripali" The security deposit together with the earnest money and the amount withheld according to the provision of F2 agreement shall be retained as security for the due fulfillment of this contract. Failure to enter into the required agreement and to make the security deposits as above shall entail forfeiture of the E.M.D. No BID shall be finally accepted until the required amount of security money is deposited. The written agreement to be entered into between the contractor and the Govt. shall be the foundation of the rights of both the parties and the contract shall be deemed to be incomplete until the agreement has first been signed by the Contractor and then by the proper Officer authorized to enter into the contract on behalf of the Govt. As concurred by Law Department and Finance Department in their U.O.R. No.848, Dt. 21.05.97, J.O.R. No.202, W.F.D., dated.6.03.98 respectively the E.M.D. will be forfeited in the case, where the Bidders back out from the offer before acceptance of the BID by the competent authority.

26. The security will be refunded six months after completion of the work and payment of the final bill and will not carry any interest.
27. The Contractor shall be liable to fully indemnify the department of any compensation under Workmen Compensation Act VIII of 1993 on account of the Workmen employed by the Contractor and full amount of compensation paid will be recovered from the Contractor.
28. The Bidders are required to abide by the fair wages clause as introduced by the Govt. of Odisha and will not pay less than the fair wages fixed by the Govt. to the labourer engaged by him/her for the work.
29. The contractors are quote there % percentage both in words and figures and put their signature on every over writing.
(a)When there is discrepancy between the rates in figures and in words, the rate quoted in words will be taken as correct.
30. The length and sizes of the M.S. or Tor steel are to be procured by the contractor and should be TATA TISCON / SAIL or any rod approved by the Zilla Parishad, Subarnapur.
31. No part of the contract shall sublet without writing permission of the BDO and C.D.O cum E.O Zila Parishad, Subarnapur or transfer be made by power of attorney authorizing other to receive payment on the contractor's behalf.
32. Steel shuttering & centering shall be used which shall be lined with suitable sheeting and made leak proof and water tight.
33. The Department will have the right to inspect the scaffolding, centering and shuttering made for the work and can reject partly or fully such structures if found defective in their opinion.
34. Concrete should be machine mixed unless otherwise ordered in writing by the Additional Project Director (Tech) Zilla Parishad, Subarnapur. The contractor should arrange his own concrete mixer, vibrator, and pumps etc., for this purpose at his own cost.
35. Only ACC/Konark/ Ultratech cement (OPC & PPC) are to be used and weight of each cement bag being taken as 50 Kg. and Cost of empty cement Bag will be recovered @ Rs 3.50/bag or as per S.R. (P.W.D).
36. In case of any complaint by the laborers working about the non-payment of his/her wages as per latest minimum wages Act, the B.D.O., will have the right to investigate and if the contractor is found to be in default, he/she may recover such amount due from the Contractor and pay such

amount to the laborers directly under intimation to the local labour Officer of the Govt. The contractor shall not employ child labour. The decision of the B.D.O. is final and binding on the contractor.

37. No compensation will be paid by the Department for any damage done by rain, flood, cyclone, and tide or by any other natural calamities during the execution of the work.
38. It should be understood clearly that no claim whatsoever will be entertained in regard to extra items of work or extra quantity of any item besides estimated amount, unless written order is obtained from the BDO and rates settled before the extra items of work or extra quantity of any item of work is taken up.
39. The Bidder shall have to abide by the C.P.W.D. safety Code Rules introduced by the Govt. of India, Ministry of Works Housing and Supply in their standing order No.44150 dt. 25.11.1957.
40. The Contractor shall bear various incidentals, sundries and contingencies necessitated by the work in full within the following or similar category.
 - (a) Rent, Royalties and other charges of materials, Octroi duty, all other taxes including GSTIN, ferry tolls, conveyance charges and other cost on account of land and building including temporary building and construction of service road and diversion road and its' maintenance till completion of the work as required by the Contractor for collection of materials, storage, housing of staff or other purpose of the work. No Bidder will however be liable to pay Govt. for temporary occupation of land owned by Govt. at the site of work.
 - (b) Labour Camps or huts necessary to a suitable scale including conservancy and sanitary arrangements there into the satisfaction of the local health authorities.
 - (c) Suitable water supply including pipe water supply wherever available for the staff and labour as well as for the work.
 - (d) Fees and duties levied by the Municipal Canal or water supply authorities.
 - (e) Suitable equipment and watering apparatus for the labour engaged in risky operation and medical aid to the labourer engaged for the work.
 - (f) Suitable fencing, barriers, signals including electric signals where necessary at work and approaches in order to protect public and employees from accident.
 - (g) Compensation including cost of any suit for injury to persons or property due to neglect of any major precautions also becomes payable due to operation of the workmen compensation Act.
 - (h) The Contractor has to arrange adequate lighting arrangement for the work wherever necessary at his own cost.
41. No payment will be made for bench marks, level pillars profiles and benching and leveling the ground where required. The rates to be quoted should be for the finished items of work inclusive of carriage of all materials and incidental item of works.
42. All preliminary works such as Vats, mixing platform etc. are to be done by the Contractor at his own cost.
43. The Contractor should arrange the materials like steel, cement, paint, shutters, bitumen etc. of approved quality and specification at his own cost for completion of the work with the time schedule. No extension of time will be granted to the Contractor due to delay in procurement of materials. The materials can be supplied by the BDO on recommendation of the J.E. and A.E. to the contractor on Payment basis.
44. The department will have the right to supply at any time in the interest of the work any departmental materials to be used in the work and the contractor shall use such materials without any controversy

- or dispute on that account. The rate of issue of such materials will be at the stock issue rate inclusive of storage charges or rates fixed by the Department or current market rate whichever is higher.
45. The Contractor will be responsible for the loss or damage of any departmental materials during transit and in the execution of the work due to reason what-so-ever and the cost of such materials will be recovered from the bills at stock issue rates or market rates whichever is higher.
 46. If the Contractor removes Govt. materials supplied to him/her from the work site with a view to dispose of the same dishonestly, he shall be in addition to any other liability Civil or criminal arising out of his contract be liable to pay a penalty equivalent to five times of the price of the materials according to the stock issue rate or market rate whichever is higher. The penalty so imposed shall be recovered at any time from any sum that may then or at any time thereafter become due to the Contractor or from his/her security deposit or from the proceeds of sale thereof.
 47. The selected Contractor may take delivery of departmental supply according to his need for the work issued by the Department subject to the availability of the materials. The Contractor shall make all arrangement for proper storage of materials but no cost for raising shed for storage, pay of watchman etc. will be borne by the Department. The department is not responsible for considering the theft of materials at site. It is contractor's risk. Under any such plea if the Contractor stops the work, he/she shall have to pay the full penalty as per Clause of F2 agreement.
 48. After the work is finished all surplus materials and debris's should be removed 100 meters clear ways from work site. Preliminary works such as Vats, mixing platform etc. should be dismantled and all materials removed from the work site and premises left neat and clean and this should be inclusive of the rates.
 49. The contractor should at his/her own cost arrange necessary tools and plants required for the efficient execution of work and the rates quoted should be inclusive of the running charges of each plant and cost of conveyance. The machineries, if available, with the department may be supplied on hire as per charges fixed by the Department.
 50. The depth of foundation indicated on the drawing are provisional but these may be altered, if necessary, in the light of the nature of strata indicated by boring which must be taken in advance of actual execution of the foundation. .
 51. Items of works not covered by the tender notice shall be paid at the current schedule of rates of the State and those not covered by the said schedule of rates will be paid on actual analysis approved by the Competent Authority.
 52. On no account, the contract work should be sublet to anybody without the prior approval of the Department. In such an event the Contract may be rescinded.
 53. Dewatering from the foundation of bridges, culverts, buildings worksites etc. and watering for consolidation in roads embankments when and where necessary during execution will have to be done by the contractor and no extra payment will be made..
 54. Number of tests as specified in I.R.C./MORT & H/I.S.I. specification required for the construction of road/bridges/buildings or any other structural works will be conducted in any Govt. laboratories or reputed material testing laboratory as to be decided by the Engineer in-charge. Testing charges including expenditure for collection/transportation of samples/specimens etc. will be borne by the Contractor. The collection of samples and testing are to be conducted for both prior to execution as may be directed by the Engineer in-charge and on both the accounts the cost shall be borne by the Contractor.
 55. Any damages caused by natural calamities should be repaired by the Contractor at his own cost. The Department will not be any way responsible for the same and will not pay any cost towards the repair done by the Contractor.

56. Over and above these conditions, the terms and conditions and rules and regulations and specifications as laid down in Odisha Detailed Standard Specification, Odisha P.W.D. Code, Bridge Code and MORT & H specifications with latest revision/ amendment are also binding on the part of the Contractor.
57. The contractor shall supply sample of all materials before procurement for the work for testing and acceptance as may be required by the Engineer in-charge.
58. The contractor has to arrange the land required for borrowing earth if necessary for the road work at his/her cost. No extra payment by the Department will be made on this account and no claim what so ever will be entertained on this ground. The rates quoted by the Contractor should be inclusive of all such charges.
59. The information furnished must be sufficient to show that the applicant is capable in all respects to successfully complete the envisaged work.
60. TIME CONTROL:-
- A. Progress of work and Re-scheduling programme.
- (i). The BDO Dunguripali shall issue the letter of Acceptance to the successful contractor. The issue of the letter of acceptance shall be treated as closure of the BID process and commencement of the contract.
- (ii) Within 15 days of issue of the letter of acceptance, the contractor shall submit to the BDO Dunguripali for approval a Programme commensurate to Clause no. B showing the general methods, arrangements, and timing for all the activities in the Works along with monthly cash flow forecast.
- B. The Contractor shall submit a Bar Chart of the work before commencement of the Work.
- (i). An update of the Programme shall be a programme showing the actual progress achieved on each activity and the effect of the progress achieved on the timing of the remaining work including any changes to the sequence of the activities
- (ii). The BDO Dunguripali, on approval of the Programme shall not alter the Contractor's obligations. The Contractor may revise the Programme and submit it to the BDO Dunguripali again at any time. A revised Programme is to show the effect of Variation and Compensation Events.
- C. Extension of the Completion Date.
- (i). The time allowed for execution of the works as specified in the Contract data shall be the essence of the Contract. The execution of the works shall commence from the 15th day or such time period as mentioned in letter of Award after the date on which the Authority shall issues written orders to commence the work or from the date of handing over of the site whichever is later. If the Contractor commits default in commencing the execution of the work as aforesaid, Authority shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the earnest money & performance guarantee / Security deposit absolutely.
- (ii). As soon as possible after the Agreement is executed the Contractor shall submit the Time & Progress Chart for each milestone and get it approved by the Block Development Officer. The Chart shall be prepared in direct relation to the time stated in the Contract documents for completion of items of the works. It shall indicate the forecast of the dates of commencement and completion of various trades of sections of the work and may be amended as necessary by agreement between the Block Development Officer, Dunguripali and the Contractor within the limitations of time imposed in the contract documents, and further to ensure good progress during the execution of the work, the contractor shall in all cases in which the time allowed for any work, exceeds one month (save for special jobs for which a separate programme has been agreed upon) complete the work as per milestone given in contract data.

(iii). In case of delay occurred due to any of the reasons mentioned below, the Contractor shall immediately give notice thereof in writing to the BDO Dunguripali but shall nevertheless use constantly his best endeavors to prevent or make good the delay and shall do all that may be reasonably required to the satisfaction of the Engineer-in-Charge to proceed with the works.

- a. Force major, or
- b. Abnormally bad weather, or
- c. Serious loss or damage by fire, or
- d. Civil commotion, local commotion of workmen, strike or lockout affecting any of the trades employed on the work, or.
- e. Delay on the part of other contractors or tradesmen engaged by BDO Dunguripali in executing work not forming part of the Contract.
- f. In case a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date without the Contractor taking steps to accelerate the remaining work and which would cause the Contractor to incur additional cost, or
- g. Any other cause, which, in the absolute discretion of the authority mentioned, in Contract data is beyond the Contractors control.

(iv). Request for reschedule and extension of time, to be eligible for consideration, shall be made by the Contractor in writing within fourteen days of the happening of the event causing delay. The Contractor may also, if practicable, indicate in such a request the period for which extension is desired.

(v). In any such case a fair and reasonable extension of time for completion of work may be given. Such extension shall be communicated to the Contractor by the BDO Dunguripali in writing, within 3 months of the date of receipt of such request. Non-application by the contractor for extension of time shall not be a bar for giving a fair and reasonable extension by the Engineer-in-Charge and this shall be binding on the contractor.

D. Compensation for Delay. Compensation @ 1% per month of for delay of work, delay to be computed on per Day basis. Provided always that the total amount of compensation for delay to be paid under this condition shall not exceed 10% of the Tendered Value of work.

E. Management Meetings.

(i). Either the Engineer or the Contractor may require the other to attend a management meeting. The business of management meetings shall be to review the plans for remaining work and to deal with matters raised in accordance with the early warning procedure.

(ii). The Engineer shall record the business of management meetings and is to provide copies of his record to those attending the meeting and to the Employer. The responsibility of the parties for actions to be taken to be decided by the Engineer either at the management meeting or after the management meeting and stated in writing to all who attended the meeting.

61. Even qualified criteria are met; the Bidders can be disqualified for the following reasons, if enquired by the Department.

- (a) Making a false statement or declaration
- (b) Past record of poor performance
- (c) Past record of abandoning the work half way/ resignation of contract.
- (d) Past record of in-ordinate delay in completion of the work.
- (e) Past history of litigation.

In case of the 1st lowest tendered or even the next lowest tendered withdraw in series one by one, thereby facilitating a particular tender for award, and then they shall be penalized with adequate

disincentives with forfeiture of E.M.D. unless adequate justification for such back out is furnished. Appropriate action for black listing the renderers shall also be taken apart from disincentivizing the tender.

62. The authority reserves the right for payment subject to availability of funds in concerned Head of account.

63. PROVIDING FACILITIES TO THE ENGINEER CONTRACTOR :

(a) As per works Department No.FR 11/2001/10003/00 BBSR, dt.24.05.01, 5% price preference allowed to the Engineer Contractor in the tender rates has been withdrawn.

(b) Exemption of E.M.D. to the Engineer Contractor will be allowed for a maximum of three works in a financial year for participating in the tender and the fact of participating with exemption of E.M.D. should be entered in the original Registration Certificate of the Engineer Contractor.

64. Income Tax will be deducted from the Contractor's bill @ prevailing percentage fixed by I.T. Department.

65. Prevailing rate of GST on the gross amount of the bill will be deducted from Contractor's bill.

66. Under no circumstances interest is chargeable for the dues or additional dues if any payable for the work.

67. The Contractors are required to pay royalty to Govt. as fixed from time to time and produced such authenticated documents in support of their payment as royalty, along with their bills. Failing which, the amount of royalties of different materials as utilized by them in the work will be recovered from their bills.

68. The contractor shall be responsible for the defect liability period for one year from the date of completion of the Project.

Compensation for Delay.

69. If the contractor fails to maintain the required progress in terms of clause-2 of P-1 Contract or to complete the work and clear the site on or before the contract or extended date of completion, he shall, without prejudice to any other right or remedy available under the law to the Government on account of such breach, pay as agreed compensation the amount calculated at the rates stipulated below as the B.D.O Dunguripali (whose decision in writing shall be final and binding) may decide on the amount of tendered value of the work for every completed day / month (as applicable) that the progress remains below that specified in Clause-2 of P-1 Contract or that the work remains incomplete. This will also apply to items or group of items for which a separate period of completion has been specified. Compensation @ **1.5%** per month of for delay of work, delay to be completed on per Day basis. Provided always that the total amount of **compensation** for delay to be paid under this condition shall not exceed 10% of the Tendered Value of work or to the Tendered Value of the item or group of items of work for which a separate period of completion is originally given. The amount of compensation may be adjusted or set-off against any sum payable to the Contractor under this or any other contract with the Government. In case, the contractor does not achieve a particular milestone mentioned in contract data, or the rescheduled milestone(s) in terms of Clause-2.5, the amount shown against that milestone shall be withheld, to be adjusted against the compensation levied at the final grant of extension of time. Withholding of this amount on failure to achieve a milestone shall be automatic without any notice to the contractor. However, if the contractor catches up with the progress of work on the subsequent milestone(s), the withheld amount shall be released. In case the contractor fails to make up for the delay in subsequent milestone(s), amount mentioned against each milestone missed subsequently also shall be withheld. However, no interest whatsoever shall be payable on such withheld amount.

70. The quantity mentioned can be increased or reduced to the extent of **10% for individual** items subject to a maximum of **5% over the estimated cost**. If it exceeds the limit stated above prior **approval of competent authority** is mandatory before making any payment. The period of completion is fixed and cannot be altered except in case of exceptional circumstances with due approval of next higher authority. Bills for percentage rate tenders shall be prepared at the estimated rates for individual items only and the percentage excess or less shall be added or subtracted from the gross amount of the bill.

71. **Additional performance Security:**

Amendment to para 3.5.5 (v) Note – ii of OPWD Code Vol.-I by modification.

Additional performance security shall be obtained from the Bidder when the BID amount is less than the estimated cost put to tender. In such an event, only the successful Bidder who has quoted less BID price/rates than the estimated cost put to tender shall have to furnish the exact amount of differential cost i.e. estimated cost put to tender minus the quoted amount as Additional Performance Security (APS) in shape of Demand Draft / Term Deposit Receipt pledged in favour of the B.D.O Dunguripali within seven days, otherwise the BID shall be cancelled and the security deposit shall be forfeited.

The BIDs of the technically qualified Bidders will be opened for evaluation of the price BID. In case of the Bidders quoting less BID price/rate than the estimated cost put to tender and have not furnished the exact amount of differential cost (i.e. estimated cost put to tender minus the quoted amount) as Additional Performance Security in shape of Demand Draft/Term Deposit Receipt, their price BID will not be taken into consideration for evaluation even if they have qualified in the technical BID evaluation.

72. **ELIGIBILITY CRITERIA :**

- (a) Required E.M.D. as per clause NO.19.
- (b) Furnishing of additional performance security, if any as per clause No. 23
- (c) Self-Attested copy of valid Registration Certificate, IT PAN Card, Valid GSTIN Certificate along with the BID and furnish the originals of the above said documents on the same day of the opening of the tender before the tendering authority.

73. The terms and conditions stipulated are comprehensive but not exhaustive. All other terms and conditions as laid down in OPWD Code Vol. I, II and. Circular in force shall also be applied for selecting a tender for award of work.

74. S.C/S.T contractors should pay Earnest Money 50 % along with the attested copies of the caste certificate and an undertaking in shape of affidavit that he has not avail the concessions for more than three times in the current financial year 2023-24. If the tender of the S.C./S.T. contractor is within 10% of the rate quoted by the lowest tenderer for the work, the same will be considered for awarded to him/her at the lowest tender rate. Any amendment order noticed by the Government may be enclosed by the contractor to get the facilities in the tender.

Signature of the Contractor.

Block Development Officer, Dunguripali.

PERMANENT ADDRESS of the Contractor

PHONE /CELL NUMBER:

e-Mail Address:

TO BE FILLED UP BY THE OFFICE AT THE TIME OF OPENING OF THE TENDER

CHECK LIST

Sl No.	Documents	Submitted		Page No.	Issuing authority
		Yes	No		
1	2	3	4	5	6
I.	Cost of tender paper in shape of DD.				
II.	Copy of valid license				
III.	Copy of valid I.T/ Pan Card				
IV.	Copy of GSTIN Registration certificate				
V.	Required EMD in approved form				
VI.	No relation certificate				
VII.	Affidavit of no litigation				
VIII.	Affidavit for authenticities of true document attached				
IX.	Additional performance Security (if required)				
X.	BID Document				
XI.	Experience Certificate				

Certified that all the information mention above has been attached with the tender paper & are true and correct to the best of my knowledge & belief.

CONTRACTOR

DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT MAJIMUNDA UPPER PRY.SCHOOL OF DUNGURIPALI BLOCK					
Sl	Description	QTY	UNIT	RATE	Amount
1	Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.	18.895	cum	730.2	13797.13
2	P.C.C(1:3:6) with 4cm size hard granite metal with lowering laying the concrete & curing etc., including supply of all materials labour T&P required for the work with cost ,conveyance & royalty,taxes etc all complete as per the direction of the engineer in charge.	6.65	cum	5680.93	37778.18
3	R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work with cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.		cum		0.00
a)	Column s/s	0.336	cum	15661.5	5262.26
b)	Lintel FF	0.663	cum	13673	9065.20
c	G. BEAM	3.115	cum	15661.5	48785.57
d	chhaja	0.577	cum	13178	7603.71
e	STAIR CASE	0.948		11937.5	11316.75
f	Slab	13.687	cum	11937.5	163388.56
4	Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.	18.985	QTL	8736.5	165862.45
5	Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm ² with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.		cum		0.00
a)	gf	2.912	cum	5629.95	16394.41
b)	ff	23.31	cum	5995.6	139757.44
6	12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)	157.027	SQM	176.5	27715.27
7	16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)	117.209	SQM	268.9	31517.50

DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT MAJIMUNDA UPPER PRY.SCHOOL OF DUNGURIPALI BLOCK

Sl	Description	QTY	UNIT	RATE	Amount
8	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thickness of 10mm and filling joints with epoxy grout of approved quality including cost of all materials, labour T&P etc required for the work.	77.74	SQM	1449.2	112660.81
9	Fixing tiles in daddos,skatting & risers of steps on 12mm thick bed of cement mortar (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing etc complete. (Data for 10 sqm)	23.004	SQM	1418.8	32638.08
	With Ceramic Tiles(20cmx30cm)		SQM		0.00
10	Wt of MS Grills,Door & Windows made out of structural steel pati.	370.5	KGM	145	53722.50
11	Painting with synthetic paint of approved quality and shad over surface with 2 coats over 1 coat of primer etc.	23.23	SQM	264.4	6142.01
12	Priming one coat over wall surface	336.327	SQM	84.5	28419.63
13	plastic emusuion paint	137.867	SQM	107.5	14820.70
14	Wall Painting two coats with Weather coat Paint over a coat Primer of approved shade on new work to give an even shade including cost of paint.	123.93	SQM	100.8	12492.14
15	ADD FOR PROVISION FOR PHTOGRAPHS (PRI/MIDDLE/COMPLITION)	1		1000	1000.00
16	PROVISION FOR ELECTRIFICATION & black board		LS	Rs	52000.00
		TOTAL			992140.31

2

DETAIL ESTIMATE FOR CONSTRUCTION OF LIBRARY AT BHIMTIKIRA ANCHALIKA HIGH SCHOOL OF DUNGURIPALI BLOCK

Sl	Description	QTY	UNIT	RATE	Amount
1	Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.	31.394	cum	267	8382.20
2	Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.	42.007	cum	730.2	30673.51
3	P.C.C(1:3:6) with 4cm size hard granite metal with lowering laying the concrete & curing etc., including supply of all materials labour T&P required for the work with cost ,conveyance & royalty,taxes etc all complete as per the direction of the engineer in charge.	14.983	cum	5680.93	85117.37
4	R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work with cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.		cum		0.00
a)	Column Base	4.883	cum	5763.15	28141.46
b)	Column GL TO PL	0.273	cum	5763.15	1573.34
c)	Plinth bend	3.002	cum	6509	19540.02
D)	Column s/s	3.359	cum	15661.5	52606.98
E)	Lintel	2.2	cum	12314.7	27092.34
F)	G. BEAM	3.359	cum	15661.5	52606.98
G)	chhaja	0.44	cum	11937.5	5252.50
H)	Slab	12.441	cum	11937.5	148514.44
5	Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.	26.96	QTL	8736.5	235536.04
6	Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm ² with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.		cum		0.00
a)	Foundation & plinth	8.97	cum	5592	50160.24
b)	Superstructure	23.291	cum	5629.95	131127.17
7	12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)	165.291	SQM	176.5	29173.86

DETAIL ESTIMATE FOR CONSTRUCTION OF LIBRARY AT BHIMTIKIRA ANCHALIKA HIGH SCHOOL OF DUNGURIPALI BLOCK

SI	Description	QTY	UNIT	RATE	Amount
8	16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)	156.798	SQM	268.9	42162.98
9	Supplying, fitting and fixing vetrified tile in floors of size 600mm x 600mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thickness of 10mm and filling joints with epoxy grout of approved quality including cost of all materials, labour T&P etc required for the work.	61.38	SQM	1449.2	88951.90
10	Fixing tiles in daddos,skating & risers of steps on 12mm thick bed of cement mortar (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing etc complete. (Data for 10 sqm)	5.208	SQM	1418.8	7389.11
	With Ceramic Tiles(20cmx30cm)		SQM		0.00
11	Wt of MS Grills,Door & Windows made out of structural steel pati.	467	KGM	145	67715.00
12	Painting with synthetic paint of approved quality and shad over surface with 2 coats over 1 coat of primer etc.	28.46	SQM	264.4	7524.82
13	Priming one coat over wall surface	308.697	SQM	84.5	26084.90
14	plastic emusuion paint	156.798	SQM	107.5	16855.79
15	Wall Painting two coats with Weather coat Paint over a coat Primer of approved shade on new work to give an even shade including cost of paint.	135.903	SQM	100.8	13699.02
17	ADD FOR PROVISION FOR PHTOGRAPHS (PRI/MIDDLE/ COMPLITION)	1		1000	1000.00
18	PROVISION FOR ELECTRIFICATION & black board		LS	Rs	2000.00
		TOTAL		Rs	1178881.961

3					
DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT BADAKERLEY UPPER PRY. SCHOOL OF DUNGURIPALI BLOCK					
Sl	Description	QTY	UNIT	RATE	Amount
1	Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.	43.83	cum	267	11702.61
2	Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.	49.58	cum	730.2	36203.32
3	P.C.C(1:4:8) with 4cm size hard granite metal with lowering laying the concrete & curing etc., including supply of all materials labour T&P required for the work with cost ,conveyance & royalty,taxes etc all complete as per the direction of the engineer in charge.	10.71	cum	5680.93	60842.76
4	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size hard broken granite Chips of approved quality from approved quarry incl. hoisting, compacting curing,finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials,cost of labour and T&p etc. all complete as per the direction of E.I.C.	7.35	SQM	377.9	2777.57
5	Filling in foundation and plinth with excavated materials including water and ramming as directed by the Engineer-in -charge.	43.83	cum	178	7801.74
6	R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work wirh cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.				
a)	Column Base	11.24	cum	5763.15	64777.81
b)	Plinth bend	2.78	cum	5763.15	16021.56
c	Column s/s & BEAM	7.19	cum	15661.5	112606.19
d	Lintel	1.12	cum	12314.7	13792.46
e	chhaja	0.59	cum	11937.5	7043.13
f	Slab	9.67	cum	11937.5	115435.63
7	Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.	25.88	QTL	8736.5	226100.62

3					
DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT BADAKEYLEY UPPER PRY. SCHOOL OF DUNGURIPALI BLOCK					
SI	Description	QTY	UNIT	RATE	Amount
8	Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm ² with lowering & curing including cost, conveyance, royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.		cum		0.00
a)	Foundation & plinth	7.69	cum	5592	43002.48
b)	Superstructure	19	cum	5629.95	106969.05
9	Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	144	kg	110	15840.00
10	Supplying and fixing of G.I Pressed G.I Door assembly with polymer powder coated including the cost of all materials and fittings etc. complete.	4.55	sqm	7000	31850.00
11	Labour for fitting and fixing doors and windows etc.all complete.	7.9	SQM	23.43	185.10
12	6mm thick cement plaster (1:4),finished smooth to R.C.C. surfaces after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	95.81	SQM	172.2	16498.48
13	12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)	132.04	SQM	176.5	23305.06
14	16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)	140.52	SQM	268.9	37785.83
15	20mm thick grading plaster (1:4),finished smooth over roof slab after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	75.55	SQM	284.7	21509.09
16	Fixing Kota tiles in Dados on 12 mm thick cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	8.36	SQM	1037.6	8674.34
17	Fixing Kota tiles in floor on 25 mm thick cement plaster (1:1) joined with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	76.07	SQM	1304.5	99233.32
18	Distempering two coats with approved shade over a coat of oil bound primer incl. cost of all material, labour and T&P etc. complete.	80.82	SQM	175.9	14216.24
19	Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material, T&P and labour etc complete. (for iron work)	108	SQM	264.4	28555.20
20	Weather coat painting two coats with approved shade over a coat of oil bound primer incl. cost of all material, T&P and labour etc complete.	160.21	SQM	185.3	29686.91

3					
DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT BADAKERLEY UPPER PRY. SCHOOL OF DUNGURIPALI BLOCK					
SI	Description	QTY	UNIT	RATE	Amount
21	STEEL RAILING FOR RAMPS	14	RMT	3555.2	49772.80
		TOTAL		RS	1,202,189.26
				Provision for Display Board =	RS 3500.00
				Provision for Black Board of size 12.0 x 4.0 ft size	RS 5500.00
				Fire fighting arrengement =	RS 6500.00
				Electrification Works	RS 30000.00
				TOTAL CIVIL WORK	Rs 1247689.26

4 DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT THENGANAL PRY. SCHOOL OF DUNGURIPALI BLOCK					
Sl	Description	QTY	UNIT	RATE	Amount
1	Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer - in - charge.	43.83	cum	267	11702.61
2	Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.	49.58	cum	730.2	36203.32
3	P.C.C(1:4:8) with 4cm size hard granite metal with lowering laying the concrete & curing etc., including supply of all materials labour T&P required for the work with cost ,conveyance & royalty,taxes etc all complete as per the direction of the engineer in charge.	10.71	cum	5680.93	60842.76
4	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size hard broken granite Chips of approved quality from approved quarry incl. hoisting, compacting curing,finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials,cost of labour and T&p etc. all complete as per the direction of E.I.C.	7.35	SQM	377.9	2777.57
5	Filling in foundation and plinth with excavated materials including water and ramming as directed by the Engineer-in -charge.	43.83	cum	178	7801.74
6	R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work with cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.				
a)	Column Base	11.24	cum	5763.15	64777.81
b)	Plinth bend	2.78	cum	5763.15	16021.56
c	Column s/s &BEAM	7.19	cum	15661.5	112606.19
d	Lintel	1.12	cum	12314.7	13792.46
e	chhaja	0.59	cum	11937.5	7043.13
f	Slab	9.67	cum	11937.5	115435.63
7	Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.	25.88	QTL	8736.5	226100.62

4 DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT THE GANAL PRY. SCHOOL OF DUNGURIPALI BLOCK					
Sl	Description	QTY	UNIT	RATE	Amount
8	Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm ² with lowering & curing including cost, conveyance, royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.		cum		0.00
a)	Foundation & plinth	7.69	cum	5592	43002.48
b)	Superstructure	19	cum	5629.95	106969.05
9	Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	144	kg	110	15840.00
10	Supplying and fixing of G.I Pressed G.I Door assembly with polymer powder coated including the cost of all materials and fittings etc. complete.	4.55	sqm	7000	31850.00
11	Labour for fitting and fixing doors and windows etc.all complete.	7.9	SQM	23.43	185.10
12	6mm thick cement plaster (1:4), finished smooth to R.C.C. surfaces after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	95.81	SQM	172.2	16498.48
13	12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)	132.04	SQM	176.5	23305.06
14	16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)	140.52	SQM	268.9	37785.83
15	20mm thick grading plaster (1:4), finished smooth over roof slab after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	75.55	SQM	284.7	21509.09
16	Fixing Kota tiles in Dados on 12 mm thick cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	8.36	SQM	1037.6	8674.34
17	Fixing Kota tiles in floor on 25 mm thick cement plaster (1:1) joined with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	76.07	SQM	1304.5	99233.32
18	Distemping two coats with approved shade over a coat of oil bound primer incl. cost of all material, labour and T&P etc. complete.	80.82	SQM	175.9	14216.24
19	Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material, T&P and labour etc complete. (for Iron work)	108	SQM	264.4	28555.20

DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT THE NGANAL PRY. SCHOOL OF DUNGURIPALI BLOCK					
SI	Description	QTY	UNIT	RATE	Amount
20	Weather coat painting two coats with approved shade over a coat of oil bound primer incl. cost of all material, T&P and labour etc complete.	160.21	SQM	185.3	29686.91
21	STEEL RAILING FOR RAMPS	14	RMT	3555.2	49772.80
		TOTAL		RS	1,202,189.26
				Provision for Display Board =	RS 3500.00
				Provision for Black Board of size 12.0 x 4.0 ft size.	RS 5500.00
				Fire fighting arrangement =	RS 6500.00
				Electrification Works	RS 30000.00
				TOTAL CIVIL WORK	RS 1247689.26

5 DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT PANKEL PRY. SCHOOL OF DUNGURIPALI BLOCK					
Sl	Description	QTY	UNIT	RATE	Amount
1	Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.	43.83	cum	267	11702.61
2	Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.	49.58	cum	730.2	36203.32
3	P.C.C(1:4:8) with 4cm size hard granite metal with lowering laying the concrete & curing etc., including supply of all materials labour T&P required for the work with cost ,conveyance & royalty,taxes etc all complete as per the direction of the engineer in charge.	10.71	cum	5680.9	60842.76
4	2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size hard broken granite Chips of approved quality from approved quarry incl. hoisting, compacting curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials, cost of labour and T&p etc. all complete as per the direction of E.I.C.	7.35	SQM	377.9	2777.57
5	Filling in foundation and plinth with excavated materials including water and ramming as directed by the Engineer-in - charge.	43.83	cum	178	7801.74
6	R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work with cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.				
a)	Column Base	11.24	cum	5763.2	64777.81
b)	Plinth bend	2.78	cum	5763.2	16021.56
c)	Column s/s & BEAM	7.19	cum	15662	112606.19
d)	Lintel	1.12	cum	12315	13792.46
e)	chhaja	0.59	cum	11938	7043.13
f)	Slab	9.67	cum	11938	115435.63
7	Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.	25.88	QTL	8736.5	226100.62
8	Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm ² with lowering & curing including cost, conveyance, royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.		cum		0.00
a)	Foundation & plinth	7.69	cum	5592	43002.48
b)	Superstructure	19	cum	5630	106969.05

5 DETAIL ESTIMATE FOR CONSTRUCTION OF ACR AT PANKEL PRY. SCHOOL OF DUNGURIPALI BLOCK					
Sl	Description	QTY	UNIT	RATE	Amount
9	Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	144	kg	110	15840.00
10	Supplying and fixing of G.I Pressed G.I Door assembly with polymer powder coated including the cost of all materials and fittings etc. complete.	4.55	sqm	7000	31850.00
11	Labour for fitting and fixing doors and windows etc.all complete.	7.9	SQM	23.43	185.10
12	6mm thick cement plaster (1:4),finished smooth to R.C.C. surfaces after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	95.81	SQM	172.2	16498.48
13	12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)	132.04	SQM	176.5	23305.06
14	16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)	140.52	SQM	268.9	37785.83
15	20mm thick grading plaster (1:4),finished smooth over roof slab after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	75.55	SQM	284.7	21509.09
16	Fixing Kota tiles in Dados on 12 mm thick cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	8.36	SQM	1037.6	8674.34
17	Fixing Kota tiles in floor on 25 mm thick cement plaster (1:1) joined with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	76.07	SQM	1304.5	99233.32
18	Distempering two coats with approved shade over a coat of oil bound primer incl. cost of all material, labour and T&P etc. complete.	80.82	SQM	175.9	14216.24
19	Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material,T&P and labour etc complete. (for Iron work)	108	SQM	264.4	28555.20
20	Weather coat painting two coats with approved shade over a coat of oil bound primer incl. cost of all material,T&P and labour etc complete.	160.21	SQM	185.3	29686.91
21	STEEL RAILING FOR RAMPS	14	RMT	3555.2	49772.80
		TOTAL		RS	1,202,189.26
				Provision for Display Board =	RS 3500.00
				Provision for Black Board of size 12.0 x 4.0 ft size.	RS 5500.00
				Fire fighting arrangement =	RS 6500.00
				Electrification Works	RS 30000.00
				TOTAL CIVIL WORK	Rs 1247689.26

6. NAME OF THE WORK:-COMPLETION OF MANDAP near Tank AT KHUNTPALI, CHINAJURI GP.

Sl.	DESCRIPTION	QTY	UNIT	RATE IN RS	AMOUNT IN RS
1	Foundation excavation in hard soil including leveling and dressing the bed and sides depositing muck within initial lead and lift etc.complete.as per direction of Engg-in-Charge.	2.02	Cum	214.50	433.00
2	Filling Foundation and plinth with sand watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg-in-charge	1.01	Cum	916.60	926.00
3	Cement concrete (1:3:6) with 40mm size CBHG metal including cost, conveyance and royalty etc.complete as per direction of Engg-in-Charge.	1.01	Cum	6000.80	6,061.00
4	Fly Ash Bricks Masonary in C.M. 1:6 in F & P including cost, conveyance and royalty of material curing etc. complete as per the direction of the Engg-in-Charge.	5.35	Cum	5344.60	28,594.00
5	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg-in- Charge.				
	(i) Ground Floor	202.97	Sqm	162.90	33,064.00
6	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg-in-Charge.				
	(i) Ground Floor	215.04	Sqm	230.70	49,610.00
7	6mm thick cement plaster with C.M (1:4) to RCC Surface including closed deep chipping and slury treatment etc. complete as per direction of Engg-in- Charge.				
	(i) Ground Floor	28.43	Sqm	169.80	4,827.00
8	Fixing vitrified tiles in dados skirting and risers of stepson 12mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matched shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.				
	(i) Ground Floor	3.54	Sqm	1612.10	5,707.00
9	Fixing of Ceramic Glazed tiles in dados, on 12mm thick bed of cement plaster 1:3(1 cement : 3 sand) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of tiles etc.				
	(i) Ground Floor	56.97	Sqm	1274.60	72,614.00
10	Fixing floor tiles in floors, treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shade including cost for rubbing, polishing & cost of tiles etc complete. as per director of Engg-in-charge.				
	(i) Ground Floor	144.43	Sqm	1156.90	167,091.00
11	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.				
	(i) Ground Floor	418.01	Sqm	78.60	32,856.00

6. NAME OF THE WORK:-COMPLETION OF MANDAP near Tank AT KHUNTPALI, CHINAJURI GP.

Sl.	DESCRIPTION	QTY	UNIT	RATE IN RS	AMOUNT IN RS
12	wall priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge.				
	(i) Ground Floor	418.01	Sqm	70.90	29,637.00
13	Wall painting with 2 coats with plastic emulsion paint of approved shade on new wrk to give an even shade.				
	(i) Ground Floor	243.47	Sqm	94.90	23,105.00
14	wall painting two coats on new work with weather coat paint of approved shade as per direction of Engg-in-Charge.				
	(i) Ground Floor	202.97	Sqm	88.10	17,882.00
15	Supplying and fixing of steel M.S Door & Windows with all fitting and fixtures including cost of cutting holes in the brick masonry and R.C.C column and making good to damage etc,as per direction of Engineer-in-charge.				
	(i) Ground Floor	648.00	kg	133.50	86,508.00
16	Painting two coats with Synthetic Enamel paint over one coat primer to grill etc complete as per direction of Engg-in-Charge.				
	(i) Ground Floor	50.19	Sqm	223.30	11,207.00
17	Providing,Fitting and fixing up Al Door with anodized aluminium door section no 9202 ,9201 as top member and 9200 as bottom member and middle member and 6mm plain glass in top portion 12mm thick prelaminated board(Nova pan make) in bottom portion fixed on door frame by means of tapered clip No 4660 and frame to be completed by means of jointing angle No 1855 etc.including cost of all materials , hire charges of drilling machine, labour T&P etc. complete.				
	(i) Ground Floor	20.05	Sqm	6405.20	128,424.00
18	Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778, as windows frame section No. 4095,4096and 9777,3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour, T&P etc. complete as per direction of the Engineer-incharge.				
	(i) Ground Floor	17.84	Sqm	4118.60	73,476.00
19	Provision for Transparency Pillar			Rs.	6,000.00
		Grand Total		Rs.	778,022.00

7. NAME OF THE WORK:-COMPLETION OF KALYAN MANDAP AT TALIPADA,LINGAMARNI GP.

Sl.	DESCRIPTION	QTY	UNIT	RATE IN RS	AMOUNT IN RS
1	Foundation excavation in hard soil including leveling and dressing the bed and sides depositing muck within initial lead and lift etc.complete.as per direction of Engg-in-Charge.	8.91	Cum	214.50	1,911.00
2	Filling Foundation and plinth with sand watered and rammed including cost, conveyance and royalty etc complete as per direction of Engg-in-charge	1.47	Cum	1048.10	1,541.00
3	Cement concrete (1:3:6) with 40mm size CBHG metal including cost, conveyance and royalty etc.complete as per direction of Engg-in-Charge.	17.66	Cum	6063.90	107,088.00
4	KB Bricks Masonary in C.M. 1:6 in F & P including cost, conveyance and royalty of material curing etc. complete as per the direction of the Engg-in-Charge.	6.95	Cum	5757.20	40,013.00
5	1St class KB brick masonry work in superstructure thoroughly soaked in water,with cement mortar (1:6) including Scaffoldings,racking out joints,curing etc. complete as per the direction of the Engg-in-charge.				
	(i) Ground Floor	22.84	Cum	5795.50	132,369.00
6	R.C.C work of (M20) grade with 20 mm and down graded chips including hosting and laying etc. complete as per direction of Engg-in-charge.				
	(i) Ground Floor	5.64	Cum	6648.30	37,496.00
7	Rigid and smooth centering & shuttering for RCC works including false works and dismantling then after casting including cost of materials complete in ground.				
	(b) Plinth Beam				
	(i) Ground Floor	16.45	Sqm	234.90	3,864.00
	(G) lintel				
	(i) Ground Floor	9.24	Sqm	529.80	4,895.00
	Slab	30.00	Sqm	677.60	20,328.00
8	Supplying , fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge asper direction of Engg-in -Charge.				
	(i) Ground Floor	5.64	Qntl	8686.80	48,994.00
9	12mm cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg-in- Charge.				
	(i) Ground Floor	361.79	Sqm	164.90	59,659.00
10	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg-in-Charge.				
	(i) Ground Floor	393.28	Sqm	233.10	91,674.00
11	6mm thick cement plaster with C.M (1:4) to RCC Surface including closed deep chipping and slury treatment etc. complete as per direction of Engg-in- Charge.				
	(i) Ground Floor	289.51	Sqm	170.80	49,448.00
12	Fixing vitrified tiles in dados skirting and risers of stepson 12mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matched shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.				
	(i) Ground Floor	3.76	Sqm	1614.00	6,069.00

7. NAME OF THE WORK:-COMPLETION OF KALYAN MANDAP AT TALIPADA,LINGAMARNI GP.

Sl.	DESCRIPTION	QTY	UNIT	RATE IN RS	AMOUNT IN RS
13	Fixing of Ceramic Glazed tiles in dados, on 12mm thick bed of cement plaster 1:3(1 cement : 3 sand) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of tiles etc.				
	(i) Ground Floor	104.99	Sqm	1276.60	134,030.00
14	Fixing floor tiles in floors, treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shade including cost for rubbing, polishing & cost of tiles etc complete. as per director of Engg-in-charge.				
	(i) Ground Floor	187.80	Sqm	1159.60	217,773.00
15	Supplying fitting & fixing of ceramic floor tiles in floors, treads or steps and landing on 25 mm thick bed of C.M(1:4) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing .				
	(i) Ground Floor	15.03	Sqm	1264.90	19,011.00
16	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.				
	(i) Ground Floor	682.79	Sqm	78.60	53,667.00
17	wall priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge.				
	(i) Ground Floor	910.34	Sqm	70.90	64,543.00
18	Wall painting with 2 coats with plastic emulsion paint of approved shade on new wrk to give an even shade.				
	(i) Ground Floor	682.79	Sqm	94.90	64,797.00
19	wall painting two coats on new work with weather coat paint of approved shade as per direction of Engg-in-Charge.				
	(i) Ground Floor	361.79	Sqm	88.10	31,874.00
20	Supplying and fixing of steel M.S Door & Windows with all fitting and fixtures including cost of cutting holes in the brick masonry and R.C.C column and making good to damage etc,as per direction of Engineer-in-charge.				
	(i) Ground Floor	1334.47	kg	133.50	178,152.00
21	Painting two coats with Synthetic Enamel paint over one coat primer to grill etc complete as per direction of Engg-in-Charge.				
	(i) Ground Floor	64.03	Sqm	223.30	14,298.00
22	Provision for Transparency Pillar			Rs.	6,000.00
		Grand Total		Rs.	1,389,494.00

**8. Detailed Estimate of Proposed Hostel for Kasturba Gandhi Balika Vidyalaya at
Mayabarha NODAL UPS under Dunguripali block**

Particulars	Qty	Unit	RATE	Amount
1				
Earth work in excavation of foundation trenches in hard soil with initial load and lift except sheet rock and boulders (requiring blasting) including dressing and leveling the bed upto the required depth and depositing the excavated materials away from the site with all loads and lifts. T & P shoring and shuttering if required etc. complete as directed by engineer-in-charge.	202.727	CUM	267.00	54128.11
2 Supplying and filling in foundation and ditches with sand well watered and rammed in layers not exceeding 23 cm in depth with all load and lift including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all labour, sundries. T & P required for the work etc complete in all respect as per direction of Engineer in-charge.	153.526	CUM	665.10	102110.14
3 Providing & laying plain cement concrete 1:3:6 (1 cement 3 coarse and 6 graded stone aggregate of 40 mm nominal size) in foundation and plinth including cost of hoisting, lowering laying concrete, ramming, watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundries. T & P required.	22.124	CUM	5680.93	125684.90
4 Plain Cement Concrete (1:4:8) using 40 mm size H.G. metal (crusher broken) well rammed including cost, conveyance, royalty taxes of all materials, etc completed as per the direction of the Engineer-in-charge.	28.81	CUM	5595.43	161204.34
5 Providing, lifting hoisting laying Reinforced cement concrete of M20 grade in column footings, as per approved designs and drawings having a minimum compressive strength (in work test) 200 Kg / Square cm in 15cm. Cubes at 28 days after mixing and tests conducted in accordance with IS 416 using 12mm to 20 mm size black hard crusher broken granite stone chips of approved quality from approved quarry washed and cleaned (20mm size dust exceeds 25%) to be mixed in concrete mixture with ordinary portland cement (OPC) without fog roasting, low water/cement and compacting concrete by using vibrators, waterline.				
A Ground Floor				
(i) Column Base	47.538	CUM	5635.85	267917.04
II Plinth Beam	10.675	CUM	6381.70	68124.65
III Column up to Roof level	9.21	CUM	15534.20	141563.16
IV Window Sill & LL	9.600	CUM	12187.40	116999.04
V Chajja	1.79	CUM	11810.20	21140.26
VI Roof Beam	12.625	CUM	15534.20	196119.28
VII Roof Slab	38.01	CUM	11810.20	448917.51
VIII Stair case	2.92	CUM	12309.20	35918.25
B 1st floor				
I Column up to Roof level	9.11	CUM	17336.80	157950.26
II Window Sill	9.354	CUM	13545.80	126707.41
III Chajja	1.99	CUM	13050.80	25971.09
IV Roof Beam	10.63	CUM	17336.80	184220.84
V Roof Slab	37.57	CUM	13050.80	490292.45
VI Stair case	2.92	CUM	13408.10	39124.84
C 2nd Floor				
I Column up to Roof level	3.80	CUM	17336.80	65827.83
II Chajja	0.05	CUM	13050.80	652.54
III Roof Beam	1.047	CUM	17336.80	18151.63
IV Roof Slab	1.708	CUM	13050.80	22290.77
6 Fly Ash brick masonry in cement mortar of (1:6) with portland slag cement, watering and curing etc. including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all labour sundries. T & P required for the works etc complete in all respect as directed by the Engineer-in-charge.				
I In F & P	23.911	CUM	5552.60	132768.22
II Ground floor Superstructure	77.859	CUM	5590.52	435272.30
III 1st floor	59.243	CUM	5956.10	352857.23
IV 2nd floor	28.21	CUM	5956.10	168021.58
7 Providing HYSD reinforcement for RCC works including bending, binding & placing in position as per Drawing including cost, conveyance of all materials, all labour and T&P etc complete.				
I Foundation & Plinth	42.884	QTL	8730.20	374385.90
II Ground floor	73.220	QTL	8730.20	639225.24
III 1st floor	69.977	QTL	8762.50	613173.46
IV 2nd floor	7.409	QTL	8762.50	64921.36

	Particulars	Qty	Unit	RATE	Amount
8	Providing and laying 12 mm cement plaster 1.6 to outside on surface after cleaning the surface taking out point including cost of all materials labour curing taxes etc complete as per instruction to architect/				
i	Ground floor	476.656	SQM	174.40	83128.81
ii	1st Floor	477.601	SQM	181.40	86636.82
iii	2nd floor	177.35	SQM	181.40	32170.93
9	Providing and laying 16 mm cement plaster 1.6 to outside on surface after cleaning the surface taking out point including cost of all materials labour curing taxes etc complete as per instruction to architect/ Engineer in charge				
i	Ground floor	496.956	SQM	266.40	132389.08
ii	1st Floor	503.521	SQM	273.10	137511.59
iii	2nd floor	151.30	SQM	273.10	41320.58
10	Providing and laying 6 mm cement plaster 1.4 to outside on surface after cleaning the surface taking out point including cost of all materials labour curing taxes etc complete as per instruction to architect/ Engineer in charge				
i	Ground floor	263.106	SQM	163.80	43096.76
ii	1st floor	263.11	SQM	170.80	44938.50
iii	2nd floor	44.69	SQM	170.80	7632.20
11	Finishign walls with water proofing weather coat of approved shade on new work 2 coats to give an even shade including cost of brushes and putty including cost of paint for out side.				
i	Ground Floor	405.58	SQM	183.40	74383.37
ii	1st Floor	393.27	SQM	188.90	74288.70
iii	2nd floor	328.65	SQM	188.90	62081.99
12	Distemping two coats to walls with distemper of approved shade on new work to give an even shade excluding cost of distemper including cost of brushes and putty including cost of paint (per sq. Mtr)(for				
i	Ground Floor	693.309	SQM	89.40	61981.82
ii	1st floor	726.157	SQM	91.40	66370.75
iii	2nd floor	44.685	SQM	91.40	4084.21
13	Providing and painting two coats of synthetic enamel paints over a coat of primer to steel work including sand papering, scaffolding, cost of conveyance, taxes of all materials, T & P labour required to complete the work as per design/ drawing & instruction of Architects/ engineer in charge				
i	Ground Floor	203.805	SQM	264.40	53886.04
ii	1st floor	199.553	SQM	264.40	52761.81
iii	2nd floor	5.67	SQM	264.40	1499.15
14	Providing and fixing of FRP (PVC) door including frame and all necessary accessories such as tower bolt, handles, hinges, etc complete in all respects.	20	SQM	2000.00	40000.00
15	Doors /Window frame made out of M.S. angle I.S.A 40mm x 40 mm x 6 mm with integrated grill of M.S. Flat 6mm x 18 mm @ 100 mm c/c spacing horizontally. The frame will be embedded to the wall with M.S clamps including shutter made out of 18 gauge sheet or plyer welded & embedded with ISA 25mm x 75 mm x 6 mm & provided with 25 mm x 6 mm flat pating diagonally completed in all respect as per the direction of I.C.The item is inclusive of all fitting fixtures such as handle tower bolt stay, hinges, knob, screws, etc with all materials labou. T & P etc.				
i	Ground Floor	3865.65	KG	90.00	347908.50
ii	1st floor	4417.5	KG	90.00	397575.00
iii	2nd floor	88.2	KG	90.00	7938.00
16	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.4mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in stair/case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect Data for 3.26 sqm	17	SMT	3000.00	51000.00
17	2.5cm thick A.S flooring with C.C.(1:2:4) including punning using 12mm size b.h.g. c.b.chips & watering, curing with cost, conveyance, royalty of all materials and labour charges etc. complete.				
i	Ground Floor	184.97	SQM	400.60	74098.98
ii	1st Floor	201.953	SQM	451.27	91135.33
18	2.5cm thick A.S flooring with C.C.(1:2:4) including punning using 12mm size b.h.g. c.b.chips & watering, curing with cost, conveyance, royalty of all materials and labour charges etc. complete.				
i	Ground Floor	21.092	SQM	400.60	8449.46
ii	1st Floor	20.771	SQM	451.27	9373.33

	Particulars	Qty	Unit	RATE	Amount
19	Fixing Ceramic tiles (300 mm x 300 mm) in floors, treads or steps and landing on 25mm thick bed of cement mortar 1:1 (cement : sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of				
i	Ground Floor	53.609	SQM	980.20	52547.54
ii	1st Floor	53.609	SQM	993.30	53249.82
iii	KADDAP TILES IN KITCHEN	15.372	SQM	867.00	13327.52
iv	Ground Floor				
A	Stair case portion Chequered Tile	30.458	SQM	755.60	23014.06
B	1st Floor	30.458	SQM	768.70	23413.06
20	Supplying fixing of ceramics wall tile of premium grade (20cmx30cm / 40cm x 40cm special plain / printed series) 25mm thick bed of cm (1:1) with net cement slurry mixing including fixing tiles etc complete.				
i	Ground Floor	110.736	SQM	976.50	113992.70
ii	1st Floor	97.464	SQM	996.20	97093.64
21	Fixing of Granite tiles for kitchen platform on 25mm thick bed of cement mortar 1:1 (cement : sand) jointed with neat cement slurry mixed with pigment of match the shades of the tiles including rubbing and polishing complete excluding cost of pre-cast Granite	6.597	SQM	967.00	6379.30
24	Plinth Protection				
a	Earth work in excavation in foundation	12.675	CUM	267.00	3384.23
b	sand filling	8.775	CUM	665.10	5836.25
c	Cement concrete (1:3:6)	0.98	CUM	5595.43	5483.52
d	c.c.(1:2:4)	6.337	CUM	7717.80	48907.70
25	Septic Tank			Rs	260271.48
	Grand Total of Civil Work	Total:-		Rs	8446224.15

The Rate quoted by me is _____ % (excess/less) than the estimated cost
put to tender for the above work.

CONTRACTOR

**BLOCK DEVELOPMENT OFFICER
DUNGURIPALI**

Tender inviting authority	Block Development Officer, Dunguripali
Name of the work	
Bidder's name	
Total estimated cost	

Percentage of Less

In figure	In words

Percentage of Excess

In figure	In words

My / our quoted rate is _____ % (both in figure and
words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write anything excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable. Government of Odisha
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

Signature of Contractor

WORKING EXPERIENCE

LIST OF PROJECTS EXECUTED

Name of Employer	Name of location and name of work	Contract price in Indian Rupees	Items of works	Date of starting the work as per Agreement	Stipulated date of completion of the work as per Agreement	Actual date of completion of the work	Reasons for delay in starting/ completion, if any
1	2	3	4	5	6	7	8

Signature of the Tenderer

WORKING EXPERIENCE

Name of Employer	Name of location and name of work	Contract price in Indian Rupees	Items of works	Date of starting the work as per Agreement	Stipulated date of completion of the work as per Agreement	Revised target date of completion of the work, if any	Reasons for slow progress, if any, with the updated billing amount
1	2	3	4	5	6	7	8

Signature of the Tenderer

Executive Engineer

CERTIFICATE OF TOOLS AND PLANTS

I/We hereby certify that the following tools and plants, machineries and vehicles are in my /our possession in working orders.

(i)

(ii)

(iii)

(iv)

(v)

I/We also note that, non-submission of this certificate will render my/our tender liable for rejection.

Signature of the Tenderer
Date.

INFORMATION REGARDING CURRENT LITIGATION, DEBARRING EXPELLING OF
TENDERER OR ABANDONMENT OF WORK BY THE TENDERER

1. a) Is the tenderer currently involved in any litigation relating to the works. Yes / No
b) If yes: give details:

2. a) Has the tenderer or any of its constituent partners been debarred/ expelled by any agency in India during the last 5 years. Yes / No

3. a) Has the tenderer or any of its constituent partners failed to perform on any contract work in India during the last 5 years. Yes / No
b) If yes, give details:

Note:

If any information in this schedule is found to be incorrect or concealed, qualification application will summarily be rejected.

Signature of Tenderer

AFFIDAVIT

1. The undersigned do hereby certify that all the statements made in the required attachments are true and correct.

2. The undersigned also hereby certifies that neither my / our firm / company / individuals _____ nor any of its constituent partners have abandoned any road/ bridge/Irrigation /Buildings or other project work in India nor any contract awarded to us for such works have been rescinded during the last five years prior to the date of this bid.

3. The undersigned hereby authorise(s) and request(s) any bank, person, firm or Corporation to furnish pertinent information as deemed necessary and as requested by the Department to verify this statement or regarding my (our) competency and general reputation.

4. The undersigned understands and agrees that further qualifying information may be requested and agree to furnish any such information at the request of the Department.

5. The undersigned undertake that in case of any information furnished by me found to be incorrect, the Government has right to reject the Bid.

(Signature of Tenderer)

Title of Officer

Name of Firm

Date

SAMPLE FORMATS

UNDER TAKING

This is to certify that

1. My firm has neither been associated, directly or indirectly, with the Consultant or with any other entity that has prepared the design, specifications, and other documents for the Project nor has any person associated with been proposed as Project Manager for the Contract.
2. My firm has not engaged any agency and any of its affiliates engaged by the Engineer-in-Charge to provide consulting services for the preparation or supervision of this work.
3. My firm has not engaged any Engineer of gazetted rank employed in Engineering or Administrative duties in an Engineering Department of the Government of Orissa or other gazetted officer retired from Government service during last two years without prior permission of the Government of Orissa in writing on or before submission of this tender. I am aware that my contract is liable to be cancelled if either I or any of my employees is found any time to be such a person who had not obtained the permission of the Government of Orissa as aforesaid.

Signature of the Tenderer.

Date:-

Note: i. Strike out whichever is not applicable

ii. In case any person is under his employment with due permission from Government, the same may be cited in a separate letter.

RELATIONSHIP DECLARATION

To,

The Block Development Officer, Dunguripali

Subject: (Name of the Work).....

Reference : (BID reference number).....

Sir,

It is to inform that I have relative(s) employed as an Officer in the rank of an Assistant Engineer/Under Secretary under the _____ Department. His (Their) details are as follows.

Relationship:

Name:

Designation

Office

Address

, I am to submit herewith the names of persons who are working under my firm having near relatives to any gazetted officer in the rank of an Assistant Engineer/Under Secretary in the _____ Department.

Sl no	Name of the my employee and his designation in the firm	Presently working at	Details of his relatives working in the Department
			Relationship Name: Designation Office Address
			Relationship Name: Designation Office Address

I am also duty bound to inform the relationship of any subsequent employment with any gazette officer in the rank of an Assistant Engineer/Under Secretary in the _____ Department. I am aware that any breach of this condition would render my firm liable for penal action for suppression of facts.

Yours Sincerely

Signature of the Tenderer.
Date: