



## OFFICE OF THE ASSISTANT DIRECTOR OF HORTICULTURE, SONEPUR

Email ID- [snp.hort@gmail.com](mailto:snp.hort@gmail.com)

### SHORT TENDER CALL NOTICE

Order No. 151...../ADH

Dated the, 07/02/2025

1. Short Tender Call Notice is invited on behalf of Governor of Odisha from Registered and Eligible Civil Contractors of the State PWD/Water Resources / Rural Work/ CPWD for the following work. The details of the work are given below.

SI. No.	Name of the Work	Approximate Estimated cost putto Tender (excluding GST & CESS) (Rs.)	EMD/Bid Security (Rs.)	Cost of Tender Paper (Rs.)	Class of Contractor	Time of Completion
1	2	3	4	5		6
1.	Concrete Overhead Tank BLT&EC,Binika	4,20,478/-	1% of the Tender Amount	2000/-	D or C	45 Days
2.	Stone Patching and Renovation of Existing Farm Pond, BLT&EC,Binika	4,20,828/-	1% of the Tender Amount	2000/-	D or C	45 Days
3	Land Development, BLT&EC,Binika	1,77,056/-	1% of the Tender Amount	600/-	D or C	15 Days
4	Dug Well BLT&EC,Binika	4,20,315/-	1% of the Tender Amount	2000/-	D or C	45 Days
5	CC Road,BLT & EC,Binika	4,19,030/-	1% of the Tender Amount	2000/-	D or C	20 Days
6	Flooring and Installation of Electricity and PH Sanitary Work,BLT & EC,Tarava	4,18,920/-	1% of the Tender Amount	2000/-	D or C	45 Days
7	Plinth Protection,ADH Office,Sonepur	3,35,235/-	1% of the Tender Amount	2000/-	D or C	20 Days
8	Installation of Blade Wire on Top of Boundary walln South Side,ADH Office,Sonepur	4,19,521/-	1% of the Tender Amount	2000/-	D or C	45 Days

2. Bid documents consisting of detailed schedule of quantities and set of terms and conditions of contract and other necessary documents can be obtained & deposited in the office of the undersigned as per following:

1.	Date & Time availability of sale of bid documents	<b>Dt 10.02.2025 to Dt 19.02.2025 upto 1 P.M</b>
2.	Last Date of Receipt of Tender Paper and other required documents in tender box at O/o ADH, Sonepur.	<b>Dt. 19.02.2025 upto 5.30 P.M</b>
3.	Date of opening of Tender Paper	<b>Dt. 20.02.2025 at 11 A.M</b>

3. The bids shall be opened in the presence of the bidders of his authorized representatives who wish to attend.

4. The cost of Bid documents in shape of demand draft issued from any nationalized scheduled bank should be prepared in the name of the **Assistant Director of Horticulture,Sonepur** and payable at Sonepur the place as mentioned in the Contract Data as mentioned in the notice towards cost of bid.The

Bid cost shall be deposited in shape of Bank Draft or Money Receipt from **O/o ADH, Sonepur (Account Section)** prepared on or before the last date of receipt along with the Bid.

5. The earnest money deposit / bid security (1%) in shape of any one of the from i.e. Deposit receipt of Nationalized Bank / Kissan Vikash Patra / Post Office Savings Bank account / National Savings Certificate / Postal Office Time Deposit. Account duly pledged in favour of the **Assistant Director of Horticulture, Sonepur** payable at **O/o ADH, Sonepur**.

7. The Successful bidder is required to submit the Annual Performance Security (as per the latest circular of Govt. of Odisha) in shape of T.D.R, NSC, KVP Pledge in favour of **ADH, Sonepur**

8. As per the Rule -13 of Appendix-VIII OPWD Code Vol-II, the contractor has to deposit 1% bid amount at the time of drawl of Agreement as Initial Security Deposit.


9. Besides, Contractors of Super Class, A & B will be required to furnish security deposit by way of deduction from their bill at the rate of 5% of the gross amount of each bill where as in case C&D Class contractors such deduction will be made at the rate of 3% of the gross amount of each bill. This will be refunded to the contractor after 6 month completion of the work.

10. The Contractors are required to provide IT 1% of the gross amount, CGST and SGST 1% each of estimated cost, and Labour CESS 1% of the estimated cost as a deduction from their bill.

11. The authority reserves the right to reject any or all the tenders so received without assigning any reason thereof.

**12. Bidders shall have to submit photo copies of:**


- i. Contractor Registration Certificate
- ii. PAN Card
- iii. GST registration certificate
- iv. Correspondence Address of the bidder (Aadhar Card)
- v. Affidavit for SC/ST and Engineering contractor, for avail benefits as per the latest circular of Govt. of Odisha.

  
**Assistant Director of Horticulture  
Sonepur**

Memo No. 152 /ADH

Dated 07/02/2025


Copy forwarded to DIO, NIC, Subarnapur for information and necessary action. He is requested to web hosting the tender notice in the district website <https://subarnapur.odisha.gov.in/>

  
**Assistant Director of Horticulture  
Sonepur**

Memo No. 153 /ADH

Dated 07/02/2025

Copy forwarded to the AHO (all)/AAE (O/o ADH, Sonepur)/SA (O/o ADH, Sonepur) for information and necessary action. They are directed to display in their notice board for wide publication and to attend the opening of the tender at scheduled date and time as specified in the tender notice.

  
**Assistant Director of Horticulture  
Sonepur**

Memo No. 154 /ADH Dated 07/02/2025

Copy submitted to the AEE(Agril.),Subarnapur for information and necessary action. They are requested to display in their notice board for wide publication.

Assistant Director of Horticulture  
Sonepur

Memo No. 155 /ADH Dated 07/02/2025

Copy submitted to the Head,KVK,Subarnapur/PD Watershed,Sonepur/Executive Engineer (Hort.) NZ, Sambalpur/CDAO,Sonepur for information and necessary action. They are requested to display in their notice board for wide publication.

Assistant Director of Horticulture  
Sonepur

Memo No. 156 /ADH Dated 07/02/2025

Copy submitted to the Director of Horticulture, Odisha, Bhubaneswar for information and necessary action.


Assistant Director of Horticulture  
Sonepur


## Tender Schedule / Bill of Quantity (1)

<b>Tender Inviting Authority:</b> Assistant Director of Horticulture, Sonepur					
<b>Name of the Work:</b> Concrete Over Head Tank, BLT & EC, Binika					
<b>Name of the Bidder:</b>					
<b>Address/Mobile No:</b>					
<b>Email Id:</b>					
Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Earth work Excavation of foundation in hard soil within 50 m initial lead and 1.5 m initial lift including rough dressing and levelling as per the direction of engineer in charge	13.50	cum	223.51	3017.00
2	Filling foundation and plinth with sand well watered and rammed including cost and conveyance of materials.	1.350	cum	632.30	854.00
3	C.C.(1:4:8) with 40 mm. size h.g. ( C.B ) metal in F&P including watering & curing etc.	1.800	cum	5399.79	9720.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite (C.B.) stone chips including hoisting and laying in ground floor, per cum				
	( I ) - RCC Column Base, Plinth	2.770	cum	6379.61	17672.00
	(II) -RCC Column and Beam	7.490	cum	17778.91	133164.00
	(III) -RCC Roof	3.760	cum	13477.51	50675.00
5	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification in ground floor	20.250	Qntl	8549.71	173132.00
6	6 mm thick cement plaster in C.M.(1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment complete	108.460	sqm	208.29	22591.00
7	Cement Washing One Coats to walls with cement complete including rubbing and polishing etc.	81.460	sqm	18.38	1497.00
8	Finishing walls with water proofing cement paint of approved shade on new work two coats to give even an shade including watering and curing complete	81.460	sqm	45.69	3722.00
9	20mm thick cement plaster (1:4) smooth grading to roof slab including watering and curing complete	11.560	sqm	291.39	3368.00
10	Priming 1 Coat to surface with red oxide primer on new iron work completely	4.050	sqm	78.97	320.00
11	Wall painting 2 coats with approved paint on new iron work complete	4.050	sqm	184.10	746.00
<b>Grand Total</b>					<b>420478</b>
(Rupees Four Lakh Twenty Thousand Four Hundred Seventy Eight)only					
<b>Quoted Percentage (%)</b>		<b>LESS/EXCESS</b>			
<b>Amount Quoted (In Figure)</b>					
<b>Amount Quoted (In Words)</b>					
<b>Signature of the Bidder With Date &amp; Seal</b>					

NB:-Amount Quoted above are excluding of CGST 9% & SGST 9% and CESS 1% , which will be paid extra on the value of work executed as applicable.

Prepared By


  
 Assistant Agriculture Engineer  
 O/o ADH, Sonepur 06/02/2025


  
 Assistant Director of Horticulture  
 Sonepur

## Tender Schedule / Bill of Quantity (2)

<b>Tender Inviting Authority: Assistant Director of Horticulture, Sonepur</b>					
<b>Name of the Work: Stone Patching and Renovation of Existing Farm Pond, BLT &amp; EC, Binika</b>					
<b>Name of the Bidder:</b>					
<b>Address/Mobile:-</b>					
<b>Email Id:-</b>					
Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Excavation in all kinds of soil including moorum, stoney earth, gravel etc. excepting all kinds of rock & boulders exceeding 0.014cum in volume for dam base stripping, cut-off trenches, outfall drains and stripping in borrow areas including rough dressing and dumping the excavated materials away from work site manually within 50m initial lead and 1.5m initial lift as per the direction of Engineer-in-charge including stacking of useful materials as directed by Engineer	160.650	cum	246.38	39581
2	Rough stone dry packing in aprons and revetments with hard granite stones (30cm and above)	108.675	cum	1968.71	213950
3	Flush pointing to stone masonry in cement mortar 1:3 including racking out joints 5mm deep, cleaning, pressing cement mortar finishing and curing including cost of materials, labour, scaffolding with initial lead and lift upto 10m etc. complete as per the direction of Engineer-in-charge.	531.000	Sqm	315.06	167297
<b>Grand Total</b>					<b>420828</b>
(Rupees Four Lakh Twenty Thousand Eight Hundred Twenty Eight )only					
<b>Quoted Percentage (%): LESS/EXCESS</b>					
<b>Amount Quoted (In Figure):</b>					
<b>Amount Quoted (In Words):</b>					
<b>Signature of the Bidder :</b>					

NB:-Amount Quoted above are excluding of CGST 9% & SGST 9% and CESS 1% , which will be paid extra on the value of work executed as applicable.

Prepared By  
  
Assistant Agriculture Engineer  
O/o ADH, Sonepur

  
Assistant Director of Horticulture  
Sonepur  
Aset. Director of Horticulture  
Sonepur

## Tender Schedule / Bill of Quantity (3)

**Tender Inviting Authority:** Assistant Director of Horticulture, Sonepur

**Name of the Work:** Land Development, BLT & EC, Binika

**Name of the Bidder:**

**Address/Mobile:-**

**Email Id:-**

Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Cleaning and grubbing road including uprooting rank vegetation, grass bushes, shrubs, sapling and trees girth upto 300mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned upto lead 1000m including removal and disposal of top organic soil not exceeding 150mm in thickness	1100	Sqm	10.89	11979
2	Excavation, loading, unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravels and moorum etc interspread with boulders up to .5cum size with all lifts and delifts including trimming of the slopes and bed to design section and depositing the excavated materials away from the work site as per specification and as directed by the E-I-C within an initial lead of 1 km from the place of excavation complete	297.500	cum	81.57	24267
3	Transportation of Earth From 15km lead including royalty of Earth	297.500	cum	450.46	134012
4	Ramming or rolling earth work with light HRR in embankment in layers not exceeding 0.3m	297.500	cum	22.85	6798
<b>Grand Total</b>					<b>177056</b>

(Rupees One Lakh Seventy Seven Thousand Fifty Six) only


**Quoted Percentage (%):**    **LESS/EXCESS**


**Amount Quoted (In Figure):**

**Amount Quoted (In Words):**

**Signature of the Bidder :**

NB:-Amount Quoted above are excluding of CGST 6% & SGST 6% and CESS 1% , which will be paid extra on the value of work executed as applicable.

*Prepared By*  
  
 Assistant Agriculture Engineer  
 O/o ADH, Sonepur

  
 Assistant Director of Horticulture  
 Sonepur  
 Asst. Director of Horticulture  
 Sonepur

## Tender Schedule / Bill of Quantity (4)

**Tender Inviting Authority: Assistant Director of Horticulture, Sonepur**

**Name of the Work: Dug Well, BLT & EC, Binika**

**Name of the Bidder:**

**Address/Mobile:-**

**Email Id:-**

Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	<b>Earthwork in excavation of foundation in hard and gravelly soil etc</b>				
	1st depth of 1.5m-Initial rate of foundation same nature of soil	30.655	cum	268.22	8222
	2nd depth of 1.5m-1.5 times initial rate + 1.5 times lift	30.655	cum	434.3	13313
	3rd depth of 1.5m-2 times initial rate + 2.5 times lift	30.655	cum	642.99	19711
	4th depth of 1.5m-2.5 times initial rate + 3.5 times lift	30.655	cum	894.31	27415
2	<b>Excavation in all kinds of soil including moorum, stoney earth, gravel etc.</b>				
	5th depth of 1.5m-3 times initial rate + 4.5 times lift	30.655	cum	1638.48	50228
	6th depth of 1.5m-3.5 times initial rate + 5.5 times lift	30.655	cum	2050.08	62845
3	<b>Dry stone masonry or rough stone dry masonry for guard walls and retaining walls with hard granite stones</b>				
	For Ground Level beyond 4.5m	49.640	cum	2571.59	127654
	For Ground Level beyond 1.5m upto 4.5m	26.520	cum	2322.61	61596
4	<b>Random rubble H.G. stone Masonry in cement mortar (1:6) in foundation and plinth.</b>	9.190	cum	4652.07	42753
5	<b>Filling in foundation and plinth with excavated materials including watering and ramming as directed by the EIC.</b>	36.786	cum	178.81	6578
<b>Grand Total</b>					<b>420315</b>
<b>(Rupees Four Lakh Twenty Thousand Three Hundred Fifteen) only</b>					

**Quoted Percentage (%): LESS/EXCESS**


**Amount Quoted (In Figure):**


**Amount Quoted (In Words):**

**Signature of the Bidder :**

**NB:-Amount Quoted above are excluding of CGST 9% & SGST 9% and CESS 1% , which will be paid extra on the value of work executed as applicable.**

Prepared By

  
Assistant Agriculture Engineer  
O/o ADH, Sonepur

  
Assistant Director of Horticulture  
Sonepur


Assistant Director of Horticulture


## Tender Schedule / Bill of Quantity (5)

<b>Tender Inviting Authority:</b> Assistant Director of Horticulture, Sonapur					
<b>Name of the Work:</b> CC Road ,BLT & EC, Binika					
<b>Name of the Bidder:</b>					
<b>Address/Mobile No:</b>					
<b>Email Id:</b>					
Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Earth work Excavation of foundation in hard soil within 50 m initial lead and 1.5 m initial lift including rough dressing and levelling as per the direction of engineer in charge	33.29	cum	222.53	7408.00
2	Filling foundation and plinth with sand well watered and rammed including cost and conveyance of materials.	23.427	cum	632.01	14806.00
3	C.C.(1:4:8) with 40 mm. size h.g. ( C.B ) metal in F&P including watering & curing etc.	46.854	cum	5390.41	252562.00
4	Cement Concrete (1:2:4) using 12mm size hard granite crusher broken chips of approved quality including lowering laying concrete, watering and curing etc	16.769	cum	7416.33	124364.00
5	Filling Foundation and Plinth with excavated materials including watering and ramming as directed by EIC	33.291	cum	178.02	5926.00
6	Centering and shuttering of CC Road in F&P	57.095	sqm	244.57	13964.00
<b>Grand Total</b>					<b>419030</b>
(Rupees Four Lakh Nineteen Thousand Thirty)only					
<b>Quoted Percentage (%)      LESS/EXCESS</b>					
<b>Amount Quoted (In Figure)</b>					
<b>Amount Quoted (In Words)</b>					
<b>Signature of the Bidder With Date &amp; Seal</b>					

NB:-Amount Quoted above are excluding of CGST 9% & SGST 9% and CESS 1% , which will be paid extra on the value of work executed as applicable.

Prepared By

  
Assistant Agriculture Engineer  
O/o ADH, Sonapur

  
Assistant Director of Horticulture  
Sonapur  
Asst. Director of Horticulture  
Sonapur

## Tender Schedule / Bill of Quantity (6)

<b>Tender Inviting Authority:</b> Assistant Director of Horticulture, Sonepur					
<b>Name of the Work:</b> Flooring and Installation of Electricity & PH Sanitary Work, BLT & EC, Tarava					
<b>Name of the Bidder:</b>					
<b>Address/Mobile:</b>					
<b>Email Id:</b>					
Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Dismantling and removing old tiled flooring including removing the base coarse and stacking the useful materials for reuse and removing the debris within 50 m lead	68.338	Sqm	139.73	9549.00
2	Dismantling and removing old tiled cladding from walls including racking out joints 12mm deep stacking the useful materials for reuse and removing the debris within 50 m lead	33.454	Sqm	72.66	2431.00
3	Dismantling and removing cement concrete including stacking the useful materials for reuse and removing the debris within 50m lead	9.746	cum	831.68	8106.00
4	Earthwork in excavation of foundation in all kinds of soil within 50M initial lead and 1.5M initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3 m in depth including cost and conveyance, royalty & taxes of all materials and cost of all labour T&P required for the work etc. complete as per the direction of the EIC.	71.458	cum	268.220	19166.00
5	Supplying, Filling sand in foundation & plinth well watered and rammed including cost, conveyance, taxes, royalty of sand, labour & T&P etc. complete as per specification and direction of the EIC.	71.458	cum	632.300	45183.00
6	Cement Concrete (1:4:8) by using 40 mm size hard granite crusher broken stone metal of approved quality and from approved quarry including lowering laying concrete, watering and curing etc. complete for required levels laid in layers including cost and conveyance, royalty & taxes of all materials and cost of all labour T&P required for the work etc. complete as per the direction of the EIC.	9.746	cum	5399.790	52626.00

7	Supplying, fitting & fixing of Vitrified tiles in floors of size 600mmx 600mm of approved make confirming to IS:13755 laid on 20 mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of the Engineer-in-charge (for New Work only )	42.291	Sqm	1126.920	47659.00
8	Fixing of Vitrified tiles 60 cm x 60 cm (Ivory) series in dado, skirting and risers of steps on 12mm thick cement plaster in mortar (1:3) joined with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles in ground floor.	4.271	Sqm	1259.210	5378.00
9	Fixing Ceramic tiles size 30 cm x 30 cm / 40 cm x 40 cm in Floors, Treads on steps & landing on 25 mm thick bed of cement mortar [1:1] joined with neat cement slurry mixed with pigment to match the shade of the Tiles including rubbing and polishing complete including cost, conveyance, royalty and taxes of all materials and cost of all labour with T&P required for the work , etc. complete as per the direction for the EIC.	26.047	Sqm	992.860	25861.00
10	Fixing Ceramic tiles 20 cm x 30 cm / 20 cm x 20 cm in Dado, Skirting and rises of steps on 12 mm thick cement mortar [1:3] joined with neat cement slurry mixed with pigment to match the shade of the Tiles including rubbing and polishing complete including rubbing and polishing etc. complete including cost, conveyance, royalty and taxes of all materials and cost of all labour with T&P required for the work etc. complete as per the direction of the EIC.	29.183	Sqm	976.450	28496.00
11	Dismantling and removing doors, windows and ventilator including removal of frame, hinges, fastening and stacking the same for reuse and removing the debris within 50m lead	3.870	Sqm	441.950	1710.00
12	Cutting grooves in pucca floors and walls for taking GI/PVC pipes and making good the damages as per specification complete.	20.000	m	218.560	4371.00
13	Supplying all materials, labours, taxes and tools and plants for fittings and fixing of PVC pipes, class-confirming to ASTM-D-1785/89(Sch-80) and pipe fittings of the following nominal bore with clamps fittings including making good the wall, ceiling and floor, testing all complete as per specification and direction of the Engineer -in-charge.	80.000	m	246.770	19742.00

14	Fixing Wash Down Water Closet (European type W.C pan) with integral 'S' or 'P' trap conforming to IS 2556 : Part 8-2004, to the floor with wooden plug and chromium plated screws including jointing the trap with soil pipe in cement mortar (1:1) etc all complete as per specification.(Seat and cover to be measured and paid for separately)	2	no	3109.51	6219.00
15	Fixing plastic seat and cover for wash down water closet with chromium plated brass hinges and rubber buffers all complete as per specification.	2	no	783.22	1566.00
16	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete.	2	no	2202.49	4405.00
17	Fixing 15mm dia PVC inlet connection pipe and making connection with pillar cocks/Angular cocks and supply mains for wash basin complete as per specification	4	no	115.03	460.00
18	Fixing Chromium Plated Revolving Shower rose(bend type) with 15mm or 20mm inlet including polishing all complete as per specification	2	no	848.25	1697.00
19	Supplying all materials,labour, T&P fitting,fixing of Virtuous China flat Wash basin over sizes 550 mm x 400 mm with hole for pillar taps conforming to IS 2556 : Part 4-2004 with cast iron or M.S Brackets painted white cement including cutting holes in walls and making good the damages etc. All complete as per specification and direction of the Engineer-in-charge.	2	no	3028.26	6057.00
20	Fixing pedestal for wash basin complete recessed at the back for the reception of pipes and fittings	2	no	2595.96	5192.00
21	Fixing pillar taps capstan head screw down high pressure lettered 'Hot' and 'Cold' with long screws, shanks and back nuts of the following nominal bore as per specification	2	no	1422.44	2845.00
22	Fixing of CP Brass Angular Stop Cocks conforming to IS:781-1995 of the following nominal sizes as per specification complete.	5	no	928.88	4644.00
23	15mm dia CP Brass Concealed Stop Cock	2	no	1113.47	2227.00
24	Fixing towel rail complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws, complete as per specification	4	no	1073.19	4293.00
25	Fixing CP Soap holder in Bathroom.	6	no	424.81	2549.00

26	Supplying all materials, labour, T&P fitting, fixing of bevelled type plate glass mirror with wooden plugs CP screw and cement etc. All complete as per specification and direction of the Engineer-in-charge.	2	no	915.41	1831.00
27	Supplying all materials, labour, T&P fitting, fixing of plate glass shelf with CP brass brackets wooden plugs CP screw and cement etc. All complete as per specification and direction of the Engineer-in-charge.	2	no	797.87	1596.00
28	Fixing of CP Health Faucet with 1.01RM PVC Tube	2	no	806.44	1613.00
29	Fixing of Bib Cocks (Taps) polished bright conforming to IS:781-1995 of the following nominal sizes as per specification				0.00
	Short Body Bib Cock	4	no	906.87	3627.00
	15mm CP 2 in 1 Bib cock	2	no	1295.71	2591.00
30	Providing fitting fixing of Al door with OEL anodized Al door section of 9202 as vertical member, 9201 as top member and 9200 as bottom and middle member and 12 mm thick pre-laminated board fixed on door frame by means of tapered clip no 4660 and the frame to be completed by means of joining angle no. 1855 including all cost of labour T&P, hire charges of drilling machine, labour charges etc complete	3.87	Sqm	7667.4	29673.00
31	Supplying all materials, labour, T&P fitting, fixing of PVC waste pipe for wash basin or sink i.e Flexible (Coil shaped) PVC Waste pipe 32mm dia with length not less than 1150 mm with PVC waste fittings etc. All complete as per specification and direction of the Engineer-in-charge.	2	no	98.38	197.00
32	Supplying all materials, labour, T&P and fitting, fixing PVC, Soil, waste and rain water pipes and filling of the following outside diameter conforming to IS 13592 Type A, to walls with seal ring conforming to IS:5382, leaving 10 mm gap for 10mm thermal expansion, (1) single socket pipes as per manufacturer's specification testing, all complete as per specification and direction of the Engineer in charge.				0.00
	75mm dia PVC SWR pipes	15.000	m	238.330	3575.00
	110mm dia PVC SWR pipes	20.000	m	386.370	7727.00
33	Finishing surface of walls with cement based wall putty of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials labour T & P etc. as per direction of Engineer -In -charge.	175.370	Sqm	91.730	16087.00

34	Finishing walls with Distemper of approved shade on new work two coats to give an even shade including watering and curing complete including cost, conveyance and taxes of all materials and cost of all labour with T&P required for the work etc. complete as per the direction of the EIC.	175.370	Sqm	88.450	15511.00
35	Wall painting 2 coat with Plastic emulsion paint of approved shade on new work to give an even shade including cost of paint.	150.530	Sqm	106.530	16036.00
36	Other Accessories	1	no	6424.13	6424.00
<b>Grand Total</b>					<b>418920.00</b>
(Rupees Four Lakh Eighteen Thousand Nine Hundred Twenty)only					
<b>Quoted Percentage (%) LESS/EXCESS</b>					
<b>Amount Quoted (In Figure)</b>					
<b>Amount Quoted (In Words)</b>					
<b>Signature of the Bidder With Date &amp; Seal</b>					

NB:-Amount Quoted above are excluding of CGST 9% & SGST 9% and CESS 1% , which will be paid extra on the value of work executed as applicable.

Prepared By

*B. Bhanja*  
Assistant Agriculture Engineer  
O/o ADH, Sonapur


*B. Bhanja*  
Assistant Director of Horticulture  
Sonapur  
Asst. Director of Horticulture  
Sonapur


## Tender Schedule / Bill of Quantity (7)

<b>Tender Inviting Authority: Assistant Director of Horticulture, Sonepur</b>					
<b>Name of the Work: Plinth Protection, ADH Office, Sonepur</b>					
<b>Name of the Bidder:</b>					
<b>Address/Mobile:-</b>					
<b>Email Id:-</b>					
Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Earth work Excavation of foundation in hard soil within 50 m initial lead and 1.5 m initial lift including rough dressing and levelling as per the direction of engineer in charge	45.360	cum	222.53	10094
2	Filling foundation and plinth with sand well watered and rammed including cost and conveyance of materials.	37.380	cum	632.01	23625
3	C.C.(1:4:8) with 40 mm. size h.g. ( C.B ) metal in F&P including watering & curing etc.	25.620	cum	5700.85	146056
4	Brick work with Fly Ash brick (23x11x8 cm) having crushing strength not less than 75 Kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8 percent in cement mortar (1:6) in Foundation & Plinth	12.600	cum	5532.82	69714
5	C.C.(1:2:4) with 12 mm. size h.g. chips in wall top with watering, curing completely	10.080	cum	7705.44	77671
6	Add towards the cost for filling the foundation and plinth with excavated materials	45.36	cum	178.02	8075
<b>Grand Total</b>					<b>335235</b>
(Rupees Three Lakh Thirty Five Thousand Two hundred Thirty Five) only					
<b>Quoted Percentage (%): LESS/EXCESS</b>					
<b>Amount Quoted (In Figure):</b>					
<b>Amount Quoted (In Words):</b>					
<b>Signature of the Bidder :</b>					

NB:-Amount Quoted above are excluding of CGST 9% & SGST 9% and CESS 1% , which will be paid extra on the value of work executed as applicable.

Prepared By

  
Assistant Agriculture Engineer  
O/o ADH, Sonepur

  
Assistant Director of Horticulture  
Sonepur  
Asst. Director of Horticulture,  
Sonepur

**Tender Schedule / Bill of Quantity** (8)

**Tender Inviting Authority: Assistant Director of Horticulture, Sonepur**

**Name of the Work: Installation of Blade Wire on Top of Boundary Wall South Side, ADH Office, Sonepur**

**Name of the Bidder:**

**Address/Mobile:-**

**Email Id:-**

Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Cutting holes of Size(0.08x0.08x0.30)m through existing brick work for fixing Angle Iron and making good the damages with cement mortar (1:6) and CC(1:2:4) and as per specification and direction of the Engineer -in-charge.	181	No	60	10860
2	Iron work wrought and put up in trusses and record racks	8.552	Qntl	14392.76	123087
3	Providing and fixing concertina coil fencing with punched tape concertina coil 600mm diameter 10m openable length(total length 90m), having 50 nos rounds per 6m length, upto 3m height of wall within existing angle iron (Y") shaped placed 2.4m or 3m apart and with 9 horizontal R.B.T reinforced barbed wire, studied with G.I staples and G.I clips to retain horizontal, including necessary bolts or GI barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T)/Spring core (2.5mm thick) wire of high tensile strength of 165kg/sq.mm with tape(0.52 mm thick) and weight 43.478 gm/m(Cost of MS Angle and CC Block Separately)	540	m	528.84	285574

**Grand Total** 419521  
 (Rupees Four Lakh Nineteen Thousand Five Hundred Twenty One)only


**Quoted Percentage (%): LESS/EXCESS**

**Amount Quoted (In Figure):**

**Amount Quoted (In Words):**

**Signature of the Bidder :**

**NB:-Amount Quoted above are excluding of CGST 9% & SGST 9% and CESS 1% , which will be paid extra on the value of work executed as applicable.**

Prepared By  
  
 Assistant Agriculture Engineer  
 O/o ADH, Sonepur  
 27.01.2025

  
 Assistant Director of Horticulture  
 Asst. Director of Horticulture  
 Sonepur  
 Sonepur