



PANCHAYAT SAMITI OFFICE, TARBHA

Tel.No-(06654)246055

Email: ori-tarava@nic.in

Letter No. 1345

Date 17/03/2025

ADDENDUM

The addendum is hereby made against this Tender Call Notice No-03/2024-25, Dated- 10.03.2025 as follows.

1. The Tender Schedule for the Project Construction of KGBV Hostel Building at Atasingha is added from Sl.No 6,7 & 8.
2. The estimates for Electrification of the 16 nos. of works.

All other terms and conditions remain same.


Block Development Officer
Tarbha

Memo No. 1346 /Date. 17/03/2025

Copy to N.I.C, Subarnapur for uploading of the same again in the official website of Subarnapur i.e. www.subarnapur.nic.in.

Copy to CDO-cum-EO, Zilla Parisad, Subarnapur for information and necessary action with request to display in their Notice board for wide circulation.


Block Development Officer
Tarbha

TENDER SCHEDULED

Name of the Work- Const. of KGBV Hostel at Atasingha

Estimated Cost – Rs.99,68,000 /-

Tender Scheduled – Rs.83,02,841 /-

Head of Account – SSD

Item No.	Description	Unit	Qty	Rate	Amount
	Civil				
1	Earth work in excavation of foundation trenches in hard soil with initial lead and lift except sheet rock and boulders (requiring blasting) including dressing and leveling the bed upto the required depth and depositing the excavated materials away form the site with all leads and lifts. T & P shoring and shuttering if required etc. complete as directed by engineer- in charge.	Cum	177.02	₹ 274.20	₹ 48,539.65
2	Supplying and filling in foundation and ditches with sand well watered and rammed in layers not exceeding 23 cm in depth with all lead and lift including cost, conveyance, loading and unloading , royalties and taxes of all materials and cost of all labour, sundries. T & P required for the work etc complete in all respect as per direction of Engineer incharge.	Cum	162.50	₹ 702.70	₹ 1,14,189.45
3	Cement concrete (1:3:6) with 40 mm size H.b.g. metal including cost,conveyance and royalty etc.complete.	Cum	17.66	₹5,574.04	₹ 98,416.37
4	Plain Cement Concrete (1:4:8) using 40 mm size H.G. metal (crusser brocken) well rammed including cost, conveyance, royalty taxes of all meterials, etc completed as per the direction of the Engineer-in-charge.	Cum	28.81	₹ 5,574.04	₹ 1,60,575.94
5	RCC work M-20 grade using 20mm and down grade course aggregate including hoisting and laying,cost , conveyance & royalty etc. complete. (GROUND FLOOR)	Cum	135.59	₹ 6,241.20	₹ 8,46,264.93
	1st Floor	Cum	114.56	₹ 6,360.30	₹ 7,28,642.33
	2nd Floor	Cum	7.04	₹ 6,479.40	₹ 45,601.21
6	Rigid and smooth centering & shuttering for RCC works including false works and dismantling then after casting including cost of materials complete in ground.				
	a) Column Base	sqm	74.88	₹ 247.50	₹ 18,532.80
	b) Plinth Beam	sqm	125.37	₹ 247.50	₹ 31,030.00
	C) column up to RL	sqm	138.38	₹ 1,186.80	₹ 1,64,223.00
	d) Window sill	sqm	9.08	₹ 247.50	₹ 2,246.00

	e) Lintel	sqm	68.49	₹ 570.00	₹ 39,037.59
	f) chajja	sqm	41.98	₹ 754.30	₹ 31,668.53
	g) Roof Band	sqm	88.58	₹ 1,186.80	₹ 1,05,130.30
	h) Roof Slab	sqm	326.40	₹ 754.30	₹ 2,46,202.39
	i) Staircase	sqm	23.26	₹ 1,041.10	₹ 24,213.38
	1st floor				
	j) column up to rl	sqm	138.38	₹ 1,384.30	₹ 1,91,552.51
	k) window sill and Lintel	sqm	63.33	₹ 674.30	₹ 42,701.40
	l) Chajja	sqm	39.30	₹ 886.50	₹ 34,836.35
	m) Roof Beam	sqm	88.13	₹ 1,384.30	₹ 1,21,996.97
	n) Roof slab	sqm	319.61	₹ 886.50	₹ 2,83,337.37
	o) Stair Case	sqm	20.458	₹ 1,215.80	₹ 24,872.23
	2nd Floor				
	p) column up to rl	sqm	3.80	₹ 6,479.40	₹ 24,601.47
	q) Chajja	sqm	0.90	₹ 1,018.70	₹ 916.83
	r) Roof Beam	sqm	8.38	₹ 1,557.20	₹ 13,049.34
	s) slab	sqm	17.08	₹ 1,018.70	₹ 17,399.40
	-				
7	Brick work with Fly Ash bricks of size 25cmx12cmx8cm and crushing strength not less than 75 kg/cm ² in C.M.(1:6) in foundation and plinth including all charges.	Cum	23.91	₹ 5,787.00	₹ 1,38,371.51
	ground floor	Cum	74.33	₹ 5,825.35	₹ 4,32,990.98
	1st floor	Cum	73.89	₹ 6,194.60	₹ 4,57,707.38
	2nd floor	Cum	33.61	₹ 6,563.90	₹ 2,20,611.04
8	Supplying and fixing uncoated HYSD bars in R.C.C. works including cutting, bending, binding including cost of binding wire and T & P etc. complete.				
	ground floor	qntl	48.47	₹ 8,728.90	₹ 4,23,127.24
		qntl	65.41	₹ 8,728.90	₹ 5,70,914.53
	1st floor	qntl	69.70	₹ 8,761.50	₹ 6,10,710.59
	2nd floor	qntl	7.32	₹ 8,794.20	₹ 64,334.43

9	16mm (5/8") thick cement plaster (1:6) finished smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost and conveyance, royalties etc complete.	sqm	464.48	₹ 270.50	₹ 1,25,640.89
	1st floor	sqm	460.92	₹ 277.30	₹ 1,27,813.53
	2nd floor	sqm	151.30	₹ 284.20	₹ 43,000.03
10	12mm (1/2") thick cement plaster (1:6) finishing smooth to outside smooth surface of brick walls after racking out the joint including watering and curing with cost, conveyance, royalties etc complete.	sqm	495.94	₹ 187.80	₹ 93,136.87
	1st Floor	sqm	497.33	₹ 195.50	₹ 97,228.31
	2nd floor	sqm	139.24	₹ 203.10	₹ 28,280.29
11	6mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	sqm	263.106	₹ 202.90	₹ 53,384.11
	1st floor	sqm	263.106	₹ 211.80	₹ 55,725.74
	2nd floor	sqm	44.685	₹ 220.70	₹ 9,861.87
12	White washing 2 coats with shell lime including cost, conveyance etc complete.				
	qty same as 16 mm Plastering (ground floor)	sqm	464.48	₹ 21.80	₹ 10,125.59
	qty same as 16 mm Plastering (1st floor)	sqm	460.92	₹ 22.30	₹ 10,278.55
	qty same as 16 mm Plastering (2nd floor)	sqm	151.30	₹ 23.00	₹ 3,479.95
	qty same as 6mm Plastering (Ground floor)	sqm	263.106	₹ 21.80	₹ 5,735.70
	qty same as 6mm Plastering (1st floor)	sqm	263.106	₹ 22.30	₹ 5,867.25
13	Distemping two coats to walls with distemper of approved shade on new work to give an even shade excluding cost of distemper. including cost of brushes and putty including cost of paint(per one Sq. Mtr)(for inside)	sqm	796.85	₹ 90.20	₹ 71,875.58
	1st floor	sqm	830.42	₹ 92.30	₹ 76,648.07
	2nd floor	sqm	44.68	₹ 94.30	₹ 4,213.75
14	Doors /Window frame made out of M.S. angle I.S.A 40mm x 40 mm x 6 mm with integrated frill of M.S. Flat 6mm x 18 mm @ 100 mm c/c spacing horizontally. The frame with be embedded to the wall with M.S. clamps including shutter made out of 18 gauge sheet property welded / embedded with ISA 25mm x 25 mm x 6 mm & provided with 25 mm x 6 mm flat placing diagonally completed in all respect as per the diraction of EIC.The item is inclusive of all fitting fixures such as handle tower bolt stay, hinges , knob , screws, etc with all	kg	3320.55	₹ 100.00	₹ 3,32,055.00

	materials labour T & P etc.				
	1st floor	kg	3881.85	₹ 100.00	₹ 3,88,185.00
	2nd floor	kg	75.60	₹ 100.00	₹ 7,560.00
15	Iron work wrought and put up in grated doors, windows and cage latrines including cost conveyance & taxes etc complete	kg	373.89	₹ 100.00	₹ 37,389.00
16	2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HGCB chips including punning including cost, conveyance & royalty of materials.	sqm	184.97	₹ 404.10	₹ 74,746.46
		sqm	53.61	₹ 404.10	₹ 21,663.30
	1st floor	sqm	201.95	₹ 404.10	₹ 81,609.05
17	12mm C.P.in C.M. (1:4) with cement punning for skirting including cost,conveyance and royalty etc.	sqm	21.09	₹ 210.00	₹ 4,429.22
	1st floor	sqm	20.77	₹ 210.00	₹ 4,361.81
18	Electrical Works				₹ 1,50,000.00
				Grand Total Rs.	₹ 83,02,841.00

(Rupees Eighty- Three Lakh Two Thousand Eight hundred Forty-One) Only

Budh
12.03.2015
Block Development Officer
Tarbha Block

NAME OF THE WORK- Construction of KGBP Hostel Building at Attasingha under Tarbha Block.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of				
a	-do- light point Group-A	12	Each	611.00	7332.00
b	-do- light point Group-B	18	Each	903.00	16254.00
c	-do- light point Group-C	5	Each	1,275.00	6375.00
d	-do- Fan point Group-B	10	Each	903.00	9030.00
e	Group-C	6	Each	1,245.00	7470.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anhor.)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	38	Mtr	157.00	5966.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	27	Mtr	188.00	5076.00
3	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	33	Each	75.00	2475.00
4	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	0	Each	660.00	0.00
5	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	12	Each	2191.00	26292.00
6	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	12	Each	294.00	3528.00
7	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	4	Each	1850.00	7400.00
8	S/F of 9W LED Bulb (Havells/Philips/Crompton)	0	Each	136.00	0.00
9	S/F of 45 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	4325.00	8650.00
10	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

3

11	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make- Havells/ Legrand /L&T/C&S.)				0.00
a	4 way Double door	2	Each	975.00	1950.00
12	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	Single pole	8	Each	142.00	1136.00
13	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
14	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existing surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				127370.00
	Add 9% CGST				11463.30
	Add 9% SGST				11463.30
	TOTAL				150296.60
	Or say				150297.00

Limited to Rs 1,50,000/-


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block, at Sibtura G.P.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havells).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

13	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make-Havells/ Legrand /L&T/C&S.)				0.00
a	8 way Double door	2	Each	1689.00	3378.00
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	40Amp DP MCB	2	Each	750.00	1500.00
b	Single pole	10	Each	142	1420.00
15	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
16	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existing surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				135459.00
	Add 9% CGST				12191.31
	Add 9% SGST				12191.31
	TOTAL				159841.62
	Or say				159842.00

Limited to Rs 1,52,909/2


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block, at Badbhainra gp.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havells).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

(Handwritten signature)

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block, at puæ Gp.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havels).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

13	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make-Havells/ Legrand /L&T/C&S.)				0.00
a	8 way Double door	2	Each	1689.00	3378.00
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	40Amp DP MCB	2	Each	750.00	1500.00
b	Single pole	10	Each	142	1420.00
15	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
16	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existing surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				135459.00
	Add 9% CGST				12191.31
	Add 9% SGST				12191.31
	TOTAL				159841.62
	Or say				159842.00

Limited to Rs 1,52,909/2


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block, at Maredogocha G.P.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havels).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

(Signature)

13	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make-Havells/ Legrand /L&T/C&S.)				0.00
a	8 way Double door	2	Each	1689.00	3378.00
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	40Amp DP MCB	2	Each	750.00	1500.00
b	Single pole	10	Each	142	1420.00
15	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
16	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existing surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				135459.00
	Add 9% CGST				12191.31
	Add 9% SGST				12191.31
	TOTAL				159841.62
	Or say				159842.00

Limited to Rs 1,52,909/-


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block. at Sargaj GP.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havells).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

13	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make-Havells/ Legrand /L&T/C&S.)				0.00
a	8 way Double door	2	Each	1689.00	3378.00
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	40Amp DP MCB	2	Each	750.00	1500.00
b	Single pole	10	Each	142	1420.00
15	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
16	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existing surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				135459.00
	Add 9% CGST				12191.31
	Add 9% SGST				12191.31
	TOTAL				159841.62
	Or say				159842.00

Limited to Rs 1,52,909/-


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block, at Kambara G.P.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havells).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

(Handwritten signature)

13	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make- Havells/ Legrand /L&T/C&S.)				0.00
a	8 way Double door	2	Each	1689.00	3378.00
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connctions testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	40Amp DP MCB	2	Each	750.00	1500.00
b	Single pole	10	Each	142	1420.00
15	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
16	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existling surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				135459.00
	Add 9% CGST				12191.31
	Add 9% SGST				12191.31
	TOTAL				159841.62
	Or say				159842.00

Limited to Rs 1,52,909/-


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block, at Tulunda GP.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in RS
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havels).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

B

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block. at Charvata Gp.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havells).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

[Handwritten Signature]

13	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make-Havells/ Legrand /L&T/C&S.)				0.00
a	8 way Double door	2	Each	1689.00	3378.00
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	40Amp DP MCB	2	Each	750.00	1500.00
b	Single pole	10	Each	142	1420.00
15	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
16	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existing surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				135459.00
	Add 9% CGST				12191.31
	Add 9% SGST				12191.31
	TOTAL				159841.62
	Or say				159842.00

Limited to Rs 1,52,909/-


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block. at Menda Gp.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection. (Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havells).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

(Handwritten mark)

13	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphalized and powder painted including earthing etc. as required (but with out MCB/ RCCB/ Isolator) make-Havells/ Legrand /L&T/C&S.)				0.00
a	8 way Double door	2	Each	1689.00	3378.00
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
a	40Amp DP MCB	2	Each	750.00	1500.00
b	Single pole	10	Each	142	1420.00
15	S/F of Standard Earthing with medium class 40mm 3Mtr. Long ISI marked GI Earth pipe including accessories such as funnel GI nut, Bolt, washer , hinged cover plate with locking arrangement, 40mm to 20GI rediusor 5nos 20mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per Direction of Engineer-in -Chage.	1	Each	2446.00	2446.00
16	proving and fixing of 8 SWG(4mm) dia copper wire on surface or in recess for loop earthing along with existing surface /recessed conduit /submain wiring /cable as required	10	mtr	59.00	590.00
	Sub total				135459.00
	Add 9% CGST				12191.31
	Add 9% SGST				12191.31
	TOTAL				159841.62
	Or say				159842.00

Limited to B 1,52,909/-


Block Development Officer
Taibha


Junior Engineer
G.E. Section Balangir

NAME OF THE WORK- Construction of GPLF Office Building with Market complex under Tarbha Block. at Paikbahal Gp.

Sl. No.	Description of Items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand /Roma)				
	-do- light point Group-A	9	Each	611.00	5499.00
	-do- light point Group-B	13	Each	903.00	11739.00
	-do- light point Group-C	6	Each	1,275.00	7650.00
	-do- Fan point Group-B	8	Each	903.00	7224.00
	Group-C	4	Each	1,245.00	4980.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	46	Mtr	157.00	7222.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	75	Mtr	171.00	12825.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	26	Mtr	188.00	4888.00
3	For Inverter wiring 1 X 1.5sqmm	38	Mtr	38.00	1444.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	14	Each	75.00	1050.00
5	S/F of 1x18 watt T5 fitting with all accessories in complete (Havells/Philips/Crompton) in direction of Engineer in charge	13	Each	660.00	8580.00
6	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	10	Each	2191.00	21910.00
7	S/F of step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	10	Each	294.00	2940.00
8	S/F of 12" Exhaust Fan(Bajaj/Usha/Khaitan)	2	Each	1850.00	3700.00
9	S/F of 18W. LED Surface square type ceiling light(Bajaj/Orient/Havells).	1	Each	1679.00	1679.00
10	S/F of computer board with 3 Nos. Switch & 3 Nos. Socket.	3	Each	1074.00	3222.00
11	S/F of 60 Watt LED Street Light New generation energy saving & environmental friendly long life versatile pressure die-cast aluminium IP66 roadway luminaire with high power LEDs as light source and electronic drive including G.I bracket ,M.S clamp ,Anchor fastner with all accessories and connection.(Make:Philips/Havells/Crompton/Panasonic or eq. model)	2	Each	8499.00	16998.00
12	S/F of 63A DP Main Switch(Anchor/Cona)	1	Each	2575.00	2575.00

Bu

The first part of the paper
 deals with the general
 principles of the
 subject. It is
 divided into two
 main sections.
 The first section
 deals with the
 general principles
 of the subject.
 The second section
 deals with the
 specific details
 of the subject.
 The first part of
 the paper deals
 with the general
 principles of the
 subject. It is
 divided into two
 main sections.
 The first section
 deals with the
 general principles
 of the subject.
 The second section
 deals with the
 specific details
 of the subject.
 The first part of
 the paper deals
 with the general
 principles of the
 subject. It is
 divided into two
 main sections.
 The first section
 deals with the
 general principles
 of the subject.
 The second section
 deals with the
 specific details
 of the subject.

NAME OF THE WORK- Construction of Additional Class room of Tarbha Block.

at Bhalu ~~Angli~~ P.S GP: - Badbhairva

Sl. No.	Description of items.	Qty	Unit	Rate (Including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Piano type switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection. (Make of wire-Anchor/Havells/Finolex) (Make of switch -Legrand /Roma)				
	-do- light point Group-A	5	Each	485.00	2425.00
	-do- light point Group-B	4	Each	777.00	3108.00
	-do- light point Group-C	3	Each	1,149.00	3447.00
	-do- Fan point Group-B	6	Each	777.00	4662.00
	Group-C	2	Each	1,149.00	2298.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	25	Mtr	157.00	3925.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	35	Mtr	171.00	5985.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	15	Mtr	188.00	2820.00
3	For Inverter wiring 1 X 1.5sqmm	0	Mtr	38.00	0.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	12	Each	75.00	900.00
5	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	8	Each	2191.00	17528.00
6	S/F of step type Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	8	Each	244.00	1952.00
	4 way Double door	1	Each	975.00	975.00
7	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required. (MAKE- Legrand/Seimens/schneider/L & T)				0.00
	Single pole	4	Each	142.00	568.00
	Sub total				50593.00
	Add 9% CGST				4553.37
	Add 9% SGST				4553.37
	TOTAL				59699.74
	Or say				59700.00

Limited to B 59506/1


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir
G.E. Section Balangir
Junior Engineer


NAME OF THE WORK- Construction of Additional Class room of Tarbha Block.

at pua PS GP:-pua

Sl. No.	Description of items.	Qty	Unit	Rate (Including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Piano type switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand (Roma))				
	-do- light point Group-A	5	Each	485.00	2425.00
	-do- light point Group-B	4	Each	777.00	3108.00
	-do- light point Group-C	3	Each	1,149.00	3447.00
	-do- Fan point Group-B	6	Each	777.00	4662.00
	Group-C	2	Each	1,149.00	2298.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	25	Mtr	157.00	3925.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	35	Mtr	171.00	5985.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	15	Mtr	188.00	2820.00
3	For Inverter wiring 1 X 1.5sqmm	0	Mtr	38.00	0.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	12	Each	75.00	900.00
5	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	8	Each	2191.00	17528.00
6	S/F of step type Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	8	Each	244.00	1952.00
	4 way Double door	1	Each	975.00	975.00
7	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connnections testing and commisioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
	Single pole	4	Each	142.00	568.00
	Sub total				50593.00
	Add 9% CGST				4553.37
	Add 9% SGST				4553.37
	TOTAL				59699.74
	Or say				59700.00

Limited to Rs 59,506/2


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir
G.E. Section Balangir
Junior Engineer

Handwritten header text, possibly a title or date, which is mostly illegible due to fading.

Date	Description	Amount	Balance
1890
1891
1892
1893
1894
1895
1896
1897
1898
1899
1900

NAME OF THE WORK- Construction of Additional Class room of Tarbha Block.

at Ghatkaintara UPS, GP:- Sibtura

Sl. No.	Description of items.	Qty	Unit	Rate (Including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Piano type switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection. (Make of wire-Anchor/Havells/Finolex) (Make of switch - Legrand/Romel)				
	-do- light point Group-A	5	Each	485.00	2425.00
	-do- light point Group-B	4	Each	777.00	3108.00
	-do- light point Group-C	3	Each	1,149.00	3447.00
	-do- Fan point Group-B	6	Each	777.00	4662.00
	Group-C	2	Each	1,149.00	2298.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	25	Mtr	157.00	3925.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	35	Mtr	171.00	5985.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	15	Mtr	188.00	2820.00
3	For Inverter wiring 1 X 1.5sqmm	0	Mtr	38.00	0.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	12	Each	75.00	900.00
5	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	8	Each	2191.00	17528.00
6	S/F of step type Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	8	Each	244.00	1952.00
	4 way Double door	1	Each	975.00	975.00
7	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connections testing and commissioning as required. (MAKE- Legrand/Seimens/schneider/L & T)				0.00
	Single pole	4	Each	142.00	568.00
	Sub total				50593.00
	Add 9% CGST				4553.37
	Add 9% SGST				4553.37
	TOTAL				59699.74
	Or say				59700.00

Limited to Rs 59,506/2

Block Development Officer
Tarbha

Junior Engineer
G.E. Section Balangir
G.E. Section Balangir
Junior Engineer

NAME OF THE WORK- Construction of Additional Class room of Tarbha Block.

at Dubwaps, GP:-Dubwala

Sl. No.	Description of items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Piano type switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection. (Make of wire-Anchor/Havells/Finolex) (Make of switch- Legrand/Roma)				
	-do- light point Group-A	5	Each	485.00	2425.00
	-do- light point Group-B	4	Each	777.00	3108.00
	-do- light point Group-C	3	Each	1,149.00	3447.00
	-do- Fan point Group-B	6	Each	777.00	4662.00
	Group-C	2	Each	1,149.00	2298.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finolex/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	25	Mtr	157.00	3925.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	35	Mtr	171.00	5985.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	15	Mtr	188.00	2820.00
3	For Inverter wiring 1 X 1.5sqmm	0	Mtr	38.00	0.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	12	Each	75.00	900.00
5	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	8	Each	2191.00	17528.00
6	S/F of step type Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	8	Each	244.00	1952.00
	4 way Double door	1	Each	975.00	975.00
7	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connections testing and commissioning as required. (MAKE- Legrand/Seimens/schneider/L & T)				0.00
	Single pole	4	Each	142.00	568.00
	Sub total				50593.00
	Add 9% CGST				4553.37
	Add 9% SGST				4553.37
	TOTAL				59699.74
	Or say				59700.00

Limited to Rs 59,506/2


Block Development Officer
Tarbha


Junior Engineer
G.E. Section Balangir
G.E. Section Balangir
Junior Engineer

NAME OF THE WORK- Construction of Additional Class room of Tarbha Block.

at Katapali UGHS, GP:- Katapali

Sl. No.	Description of items.	Qty	Unit	Rate (including 1% L.C)	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Plano type switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection.(Make of wire-Anchor/Havells/Finox) (Make of switch -Legrand/Romel)				
	-do- light point Group-A	9	Each	485.00	4365.00
	-do- light point Group-B	5	Each	777.00	3885.00
	-do- light point Group-C	3	Each	1,149.00	3447.00
	-do- Fan point Group-B	6	Each	777.00	4662.00
	Group-C	2	Each	1,149.00	2298.00
2	Recessed wiring to submain of the following FR PVC insulated single core multistrand copper conductor of ISI Marked confirming to IS-694/1990 in 20mm dia nonmetallic heavy duty flexible conduct 1.6 sqmm thick along with following sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required complete in all respect as per direction of Engineer in charge (Havells/Finox/Anchor)				0.00
a	2x1.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	33	Mtr	157.00	5181.00
b	2x2.5 sqmm +1x1.5 sqmm 1100 Volts confirming to IS 694/1990	41	Mtr	171.00	7011.00
c	2x4 sq mm+1x1.5 sqmm 1100 Volts confirming to IS 694/1990	15	Mtr	188.00	2820.00
3	For Inverter wiring 1 X 1.5sqmm	0	Mtr	38.00	0.00
4	S/F of Bakelite Angle holder/Batten Holder of ISI marked in place of ceiling Rose complete in all respect as per direction of Engineer in charge (Make : Cona / Anchor / Havells).	16	Each	75.00	1200.00
5	S/F of A.C Ceiling fan 48" size. (Make-Usha-Polycab Vital /crompton decora/ Crompton jura.)	8	Each	2191.00	17528.00
6	S/F of step type Fan Regulator with all connection complete in all respect as per direction of Engineer in charge(Make-Roma/Legrand)	8	Each	244.00	1952.00
	4 way Double door	1	Each	975.00	975.00
7	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connections testing and commissioning as required .(MAKE- Legrand/Seimens/schneider/L & T)				0.00
	Single pole	4	Each	142.00	568.00
	Sub total				55892.00
	Add 9% CGST				5030.28
	Add 9% SGST				5030.28
	TOTAL				65952.56
	Or say				65953.00

Limited to Rs 65,933/-

Block Development Officer
Tarbha

Junior Engineer
G.E. Section Balangir