

OFFICE OF THE PANCHAYAT SAMITI, BIRMAHARAJPUR

No: 2051

Date: 27/2/2025

(SHORT TENDER CALL NOTICE)

Block Development Officer, Birmaharajpur on behalf of Government of Odisha invites sealed tender in single cover system from the intending Bidder for execution of works mentioned in the table below. The eligible contractors registered with the State Government and contractors of equivalent Grade/Class registered with Central Government/MES/Railways or other Licensing Authority for execution of Civil works on production of definite proof from the appropriate authority can participate in the BID.

Sl. No.	Name of Work	Estimated Cost put to tender (in Rs.)	EMD	Class of Contractor	Cost of tender paper in (Rs.)	Period of Completion
1	2	3	4	5	6	7
1	Construction of Additional Class Room at Tentulimahada UPS, GP-Mursundhi	Rs. 14,96,446.00	Rs. 14964.00	"C"	6000.00	6 Month
2	Construction of Additional Class Room at Badbardakata UPS, GP-Khandahata	Rs. 14,96,446.00	Rs. 14964.00	"C"	6000.00	6 Month
3	Construction of Additional Class Room at Buthipadar UPS, GP-Khandahata	Rs. 14,96,446.00	Rs. 14964.00	"C"	6000.00	6 Month
4	Construction of Additional Class Room at Khairmal UPS, GP-Kenjriapali	Rs. 14,96,446.00	Rs. 14964.00	"C"	6000.00	6 Month
5	Construction of Additional Class Room at Kumursingha UPS, GP-Bagbar	Rs. 14,96,446.00	Rs. 14964.00	"C"	6000.00	6 Month
6	Construction of Additional Class Room at Buroghat PS, GP-Bagbar	Rs. 14,96,446.00	Rs. 14964.00	"C"	6000.00	6 Month
7	Construction of Additional Class Room at Kadalipali PS, GP-Kenjriapali	Rs. 14,96,446.00	Rs. 14964.00	"C"	6000.00	6 Month

The tenderers are requested to submit valid & up to date photo copy of license, GST Certificate, copy of Pan Card along with tender documents. The tender bids complete in all respect must reach in the address of the Block Development Officer, Birmaharajpur through registered post/speed post on or before 05.30 P.M of dt **13.03.2025** and will be opened on dt **17.03.2025** at 3.00 P.M in presence of the tenderers or their authorized representatives willing to be present. BID must be accompanied by EMD/BID security of the amount as specified for the work at Column No.4 of the above table, duly pledged in favour of Block Development Officer, Birmaharajpur. The tender document will be sold from dt

28.02.2025 to 12.03.2025 from 10.00 A.M. to 5.30 P.M. on payment of tender paper cost as noted above to be deposited in the Cash Counter of Panchayat Samiti Office, Birmaharajpur. The tenderer must be mentioned the name of the work in capital letter on the top of the envelop of tender paper to be submitted.

The Authority will not be held responsible for any postal delay in respect of receipt of tender documents and reserves the right to accept or reject any or all tenders without assigning any reason thereof.

  
Block Development Officer  
Birmaharajpur  
27/02/25

Memo No. 2052 /Date. 27/2/2025

Copy to DIO, N.I.C, Subarnapur for uploading the detail tender call notice and the bid documents in the official website of Subarnapur i.e. www.subarnapur.nic.in for information of the public/prospective bidders.

  
Block Development Officer  
Birmaharajpur  
27/02/25

Memo No. 2053 /Date. 27/2/2025

Copy submitted to CDO-cum-EO, Zilla Parishad, Subarnapur/D.I.P.R.O., Subarnapur for wide publication All BDOs of Subarnapur District/ Sub-Collector, Birmaharajpur/ Tahasildar, Birmaharajpur/ CDPO, Birmaharajpur for information and necessary action with request to display in their Notice board for wide circulation.

  
Block Development Officer  
Birmaharajpur  
27/02/25

Memo No. 2054 /Date. 27/2/2025

Copy to Cashier, of this Office for information. Copy to Notice Board.

  
Block Development Officer  
Birmaharajpur  
27/02/25

Memo No. 2055 /Date. 27/2/2025

Copy forwarded to the Joint Director (Advertisement) I & P.R. Deptt. Govt. of Odisha, Bhubaneswar with a request to publish the Tender Call Notice in two Odiya daily widely circulated news paper in all Odisha edition in minimum space for one day and the complementary copies of the News Paper may be sent to this Office for reference and record.

  
Block Development Officer  
Birmaharajpur  
27/02/25

Name of the work:- Construction of Additional Class Room at Tentulimahada Primary School, Murshundi G.P.					
Tender Value:- ₹ 14,96,446/-					
Head of Account:- Samagra Siksha Abhiyaan(2024-25)					
Sl.no.	Description	unit	quantity	rate	amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	m <sup>3</sup>	43.2	₹ 270.89	₹ 11,702.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	45.17	₹ 599.18	₹ 27,065.00
3	Cement concrete (1:3:6) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	12.8	₹ 6,173.77	₹ 79,024.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	m <sup>3</sup>	32.5	₹ 6,297.20	₹ 2,04,659.00
5	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	qtl	28.15	₹ 8,584.52	₹ 2,41,654.00
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- roof slab and chajja	m <sup>2</sup>	117.32	₹ 772.10	₹ 90,583.00
7	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- footings and plinth bend	m <sup>2</sup>	60.8	₹ 252.82	₹ 15,371.00
8	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- beams and columns	m <sup>2</sup>	67.5	₹ 1,188.95	₹ 80,254.00
9	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- lintel	m <sup>2</sup>	25.28	₹ 570.03	₹ 14,410.00
10	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth"	m <sup>3</sup>	12.66	₹ 5,520.33	₹ 69,887.00
11	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure	m <sup>3</sup>	29.07	₹ 5,558.67	₹ 1,61,591.00
12	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost of precast tiles	m <sup>2</sup>	4.32	₹ 957.90	₹ 4,138.00
13	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	m <sup>2</sup>	15.73	₹ 978.49	₹ 15,392.00
14	1 coat of priming over new M.S. doors and windows including , T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 72.20	₹ 2,781.00
15	2 coats of painting over new M.S. doors and windows including T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 185.92	₹ 7,162.00
16	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	m <sup>2</sup>	156.14	₹ 99.67	₹ 15,562.00
17	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	m <sup>2</sup>	714.46	₹ 107.61	₹ 76,883.00

18	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	159.62	₹ 184.86	₹ 29,507.00
19	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	114.49	₹ 207.99	₹ 23,813.00
20	16mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	175.77	₹ 267.13	₹ 46,953.00
21	20mm, thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	91.46	₹ 289.80	₹ 26,505.00
22	2.5cm thick A.S. flooring using c.c. (1:2:4) with 12 mm size c.b.g. chips including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	84.81	₹ 407.28	₹ 34,541.00
23	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	m <sup>2</sup>	714.46	₹ 90.05	₹ 64,337.00
24	Priming 1 coat with any approved Primer on newly plastered wall surface	m <sup>2</sup>	870.59	₹ 78.23	₹ 68,106.00
25	Supplying and fixing of M.S. doors and windows	qt1	6.8	₹ 12,000.00	₹ 81,600.00
26	Display board and photograph	no	1	₹ 2,966.10	₹ 2,966.00

Tender value = ₹ 14,96,446.00

  
Junior Engineer  
Birmaharajpur Block Office

  
Assistant Executive Engineer  
Birmaharajpur Block Office

  
B.D. and others  
Birmaharajpur

**Name of the work:-Construction of Additional Class Room at Kadalipalli Primary School, Kenjhariapalli G.P.**

**Tender Value:- ₹ 14,96,446/- Head of Account:-Samagra Siksha Abhiyaan(2024-25)**

Sl.no.	Description	unit	quantity	rate	amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	m <sup>3</sup>	43.2	₹ 270.89	₹ 11,702.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	45.17	₹ 599.18	₹ 27,065.00
3	Cement concrete (1:3:6) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	12.8	₹ 6,173.77	₹ 79,024.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	m <sup>3</sup>	32.5	₹ 6,297.20	₹ 2,04,659.00
5	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	qt1	28.15	₹ 8,584.52	₹ 2,41,654.00
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- roof slab and chajja	m <sup>2</sup>	117.32	₹ 772.10	₹ 90,583.00
7	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- footings and plinth bend	m <sup>2</sup>	60.8	₹ 252.82	₹ 15,371.00
8	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- beams and columns	m <sup>2</sup>	67.5	₹ 1,188.95	₹ 80,254.00
9	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- lintel	m <sup>2</sup>	25.28	₹ 570.03	₹ 14,410.00
10	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth"	m <sup>3</sup>	12.66	₹ 5,520.33	₹ 69,887.00
11	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure	m <sup>3</sup>	29.07	₹ 5,558.67	₹ 1,61,591.00
12	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	m <sup>2</sup>	4.32	₹ 957.90	₹ 4,138.00
13	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	m <sup>2</sup>	15.73	₹ 978.49	₹ 15,392.00
14	1 coat of priming over new M.S. doors and windows including , T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 72.20	₹ 2,781.00
15	2 coats of painting over new M.S. doors and windows including T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 185.92	₹ 7,162.00
16	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	m <sup>2</sup>	156.14	₹ 99.67	₹ 15,562.00
17	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	m <sup>2</sup>	714.46	₹ 107.61	₹ 76,883.00

18	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	159.62	₹ 184.86	₹ 29,507.00
19	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	114.49	₹ 207.99	₹ 23,813.00
20	16mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	175.77	₹ 267.13	₹ 46,953.00
21	20mm, thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	91.46	₹ 289.80	₹ 26,505.00
22	2.5cm thick A.S. flooring using c.c. (1:2:4) with 12 mm size c.b.g. chips including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	84.81	₹ 407.28	₹ 34,541.00
23	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	m <sup>2</sup>	714.46	₹ 90.05	₹ 64,337.00
24	Priming 1 coat with any approved Primer on newly plastered wall surface	m <sup>2</sup>	870.59	₹ 78.23	₹ 68,106.00
25	Supplying and fixing of M.S. doors and windows	qtl	6.8	₹ 12,000.00	₹ 81,600.00
26	Display board and photograph	no	1	₹ 2,966.10	₹ 2,966.00

Tender value = ₹ 14,96,446.00

  
Junior Engineer  
Birmaharajpur Block Office

  
Assistant Executive Engineer  
Birmaharajpur Block Office

  
S.D.O.  
Birmaharajpur

Name of the work:-Construction of Additional Class Room at Khairmal Primary School, Kenjhariapalli G.P.					
Tender Value:- ₹ 14,96,446/-		Head of Account:-Samagra Siksha Abhiyaan(2024-25)			
Sl.no.	Description	unit	quantity	rate	amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	m <sup>3</sup>	43.2	₹ 270.89	₹ 11,702.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	45.17	₹ 599.18	₹ 27,065.00
3	Cement concrete (1:3:6) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	12.8	₹ 6,173.77	₹ 79,024.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	m <sup>3</sup>	32.5	₹ 6,297.20	₹ 2,04,659.00
5	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	qt1	28.15	₹ 8,584.52	₹ 2,41,654.00
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- roof slab and chajja	m <sup>2</sup>	117.32	₹ 772.10	₹ 90,583.00
7	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- footings and plinth bend	m <sup>2</sup>	60.8	₹ 252.82	₹ 15,371.00
8	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- beams and columns	m <sup>2</sup>	67.5	₹ 1,188.95	₹ 80,254.00
9	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- lintel	m <sup>2</sup>	25.28	₹ 570.03	₹ 14,410.00
10	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth"	m <sup>3</sup>	12.66	₹ 5,520.33	₹ 69,887.00
11	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure	m <sup>3</sup>	29.07	₹ 5,558.67	₹ 1,61,591.00
12	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	m <sup>2</sup>	4.32	₹ 957.90	₹ 4,138.00
13	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	m <sup>2</sup>	15.73	₹ 978.49	₹ 15,392.00
14	1 coat of priming over new M.S. doors and windows including , T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 72.20	₹ 2,781.00
15	2 coats of painting over new M.S. doors and windows including T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 185.92	₹ 7,162.00
16	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	m <sup>2</sup>	156.14	₹ 99.67	₹ 15,562.00
17	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	m <sup>2</sup>	714.46	₹ 107.61	₹ 76,883.00

18	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	159.62	₹ 184.86	₹ 29,507.00
19	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	114.49	₹ 207.99	₹ 23,813.00
20	16mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	175.77	₹ 267.13	₹ 46,953.00
21	20mm, thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	91.46	₹ 289.80	₹ 26,505.00
22	2.5cm thick A.S. flooring using c.c. (1:2:4) with 12 mm size c.b.g. chips including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	84.81	₹ 407.28	₹ 34,541.00
23	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	m <sup>2</sup>	714.46	₹ 90.05	₹ 64,337.00
24	Priming 1 coat with any approved Primer on newly plastered wall surface	m <sup>2</sup>	870.59	₹ 78.23	₹ 68,106.00
25	Supplying and fixing of M.S. doors and windows	qtl	6.8	₹ 12,000.00	₹ 81,600.00
26	Display board and photograph	no	1	₹ 2,966.10	₹ 2,966.00

Tender value = ₹ 14,96,446.00

  
Junior Engineer  
Birmaharajpur Block Office

  
Assistant Executive Engineer  
Birmaharajpur Block Office

  
B.D.O.  
Birmaharajpur Block Office

**Name of the work:- Construction of Additional Class Room at Buthipadar Primary School, Khandahata G.P.**

Tender Value:- ₹ 14,96,446/-

Head of Account:- Samagra Siksha Abhiyaan(2024-25)

Sl.no.	Description	unit	quantity	rate	amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	m <sup>3</sup>	43.2	₹ 270.89	₹ 11,702.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	45.17	₹ 599.18	₹ 27,065.00
3	Cement concrete (1:3:6) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	12.8	₹ 6,173.77	₹ 79,024.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	m <sup>3</sup>	32.5	₹ 6,297.20	₹ 2,04,659.00
5	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	qtl	28.15	₹ 8,584.52	₹ 2,41,654.00
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- roof slab and chajja	m <sup>2</sup>	117.32	₹ 772.10	₹ 90,583.00
7	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- footings and plinth bend	m <sup>2</sup>	60.8	₹ 252.82	₹ 15,371.00
8	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- beams and columns	m <sup>2</sup>	67.5	₹ 1,188.95	₹ 80,254.00
9	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- lintel	m <sup>2</sup>	25.28	₹ 570.03	₹ 14,410.00
10	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth"	m <sup>3</sup>	12.66	₹ 5,520.33	₹ 69,887.00
11	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure	m <sup>3</sup>	29.07	₹ 5,558.67	₹ 1,61,591.00
12	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	m <sup>2</sup>	4.32	₹ 957.90	₹ 4,138.00
13	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	m <sup>2</sup>	15.73	₹ 978.49	₹ 15,392.00
14	1 coat of priming over new M.S. doors and windows including , T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 72.20	₹ 2,781.00
15	2 coats of painting over new M.S. doors and windows including T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 185.92	₹ 7,162.00
16	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	m <sup>2</sup>	156.14	₹ 99.67	₹ 15,562.00
17	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	m <sup>2</sup>	714.46	₹ 107.61	₹ 76,883.00

18	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	159.62	₹ 184.86	₹ 29,507.00
19	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	114.49	₹ 207.99	₹ 23,813.00
20	16mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	175.77	₹ 267.13	₹ 46,953.00
21	20mm, thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	91.46	₹ 289.80	₹ 26,505.00
22	2.5cm thick A.S. flooring using c.c. (1:2:4) with 12 mm size c.b.g. chips including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	84.81	₹ 407.28	₹ 34,541.00
23	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	m <sup>2</sup>	714.46	₹ 90.05	₹ 64,337.00
24	Priming 1 coat with any approved Primer on newly plastered wall surface	m <sup>2</sup>	870.59	₹ 78.23	₹ 68,106.00
25	Supplying and fixing of M.S. doors and windows	qt1	6.8	₹ 12,000.00	₹ 81,600.00
26	Display board and photograph	no	1	₹ 2,966.10	₹ 2,966.00
<b>Tender value =</b>					<b>₹ 14,96,446.00</b>

  
Junior Engineer  
Birmaharajpur Block Office

  
Assistant Executive Engineer  
Birmaharajpur Block Office

  
B.D.O.  
Birmaharajpur

## Name of the work:-Construction of Additional Class Room at Badbardakata Primary School, Khandahata G.P.

Tender Value:- ₹ 14,96,446/-

Head of Account:-Samagra Siksha Abhiyaan(2024-25)

Sl.no.	Description	unit	quantity	rate	amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	m <sup>3</sup>	43.2	₹ 270.89	₹ 11,702.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	45.17	₹ 599.18	₹ 27,065.00
3	Cement concrete (1:3:6) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	12.8	₹ 6,173.77	₹ 79,024.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	m <sup>3</sup>	32.5	₹ 6,297.20	₹ 2,04,659.00
5	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	qtl	28.15	₹ 8,584.52	₹ 2,41,654.00
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- roof slab and chajja	m <sup>2</sup>	117.32	₹ 772.10	₹ 90,583.00
7	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- footings and plinth bend	m <sup>2</sup>	60.8	₹ 252.82	₹ 15,371.00
8	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- beams and columns	m <sup>2</sup>	67.5	₹ 1,188.95	₹ 80,254.00
9	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- lintel	m <sup>2</sup>	25.28	₹ 570.03	₹ 14,410.00
10	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm <sup>2</sup> with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth"	m <sup>3</sup>	12.66	₹ 5,520.33	₹ 69,887.00
11	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm <sup>2</sup> with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure	m <sup>3</sup>	29.07	₹ 5,558.67	₹ 1,61,591.00
12	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	m <sup>2</sup>	4.32	₹ 957.90	₹ 4,138.00
13	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	m <sup>2</sup>	15.73	₹ 978.49	₹ 15,392.00
14	1 coat of priming over new M.S. doors and windows including , T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 72.20	₹ 2,781.00
15	2 coats of painting over new M.S. doors and windows including T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 185.92	₹ 7,162.00
16	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	m <sup>2</sup>	156.14	₹ 99.67	₹ 15,562.00
17	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	m <sup>2</sup>	714.46	₹ 107.61	₹ 76,883.00

18	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	159.62	₹ 184.86	₹ 29,507.00
19	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	114.49	₹ 207.99	₹ 23,813.00
20	16mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	175.77	₹ 267.13	₹ 46,953.00
21	20mm, thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	91.46	₹ 289.80	₹ 26,505.00
22	2.5cm thick A.S. flooring using c.c. (1:2:4) with 12 mm size c.b.g. chips including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	84.81	₹ 407.28	₹ 34,541.00
23	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	m <sup>2</sup>	714.46	₹ 90.05	₹ 64,337.00
24	Priming 1 coat with any approved Primer on newly plastered wall surface	m <sup>2</sup>	870.59	₹ 78.23	₹ 68,106.00
25	Supplying and fixing of M.S. doors and windows	qt1	6.8	₹ 12,000.00	₹ 81,600.00
26	Display board and photograph	no	1	₹ 2,966.10	₹ 2,966.00

Tender value = ₹ 14,96,446.00

  
Junior Engineer  
Birmaharajpur Block Office

  
Assistant Executive Engineer  
Birmaharajpur Block Office

  
B.D.O.  
Birmaharajpur

Name of the work:-Construction of Additional Class Room at Kumarsingha Primary School, Bagbar G.P.

Tender Value:- ₹ 14,96,446/-

Head of Account:-Samagra Siksha Abhiyaan(2024-25)

Sl.no.	Description	unit	quantity	rate	amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	m <sup>3</sup>	43.2	₹ 270.89	₹ 11,702.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	45.17	₹ 599.18	₹ 27,065.00
3	Cement concrete (1:3:6) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	12.8	₹ 6,173.77	₹ 79,024.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	m <sup>3</sup>	32.5	₹ 6,297.20	₹ 2,04,659.00
5	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	qtl	28.15	₹ 8,584.52	₹ 2,41,654.00
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- roof slab and chajja	m <sup>2</sup>	117.32	₹ 772.10	₹ 90,583.00
7	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- footings and plinth bend	m <sup>2</sup>	60.8	₹ 252.82	₹ 15,371.00
8	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- beams and columns	m <sup>2</sup>	67.5	₹ 1,188.95	₹ 80,254.00
9	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- lintel	m <sup>2</sup>	25.28	₹ 570.03	₹ 14,410.00
10	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth"	m <sup>3</sup>	12.66	₹ 5,520.33	₹ 69,887.00
11	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure	m <sup>3</sup>	29.07	₹ 5,558.67	₹ 1,61,591.00
12	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	m <sup>2</sup>	4.32	₹ 957.90	₹ 4,138.00
13	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	m <sup>2</sup>	15.73	₹ 978.49	₹ 15,392.00
14	1 coat of priming over new M.S. doors and windows including , T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 72.20	₹ 2,781.00
15	2 coats of painting over new M.S. doors and windows including T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 185.92	₹ 7,162.00

16	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	m <sup>2</sup>	156.14	₹ 99.67	₹ 15,562.00
17	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	m <sup>2</sup>	714.46	₹ 107.61	₹ 76,883.00
18	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	159.62	₹ 184.86	₹ 29,507.00
19	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	114.49	₹ 207.99	₹ 23,813.00
20	16mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	175.77	₹ 267.13	₹ 46,953.00
21	20mm, thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	91.46	₹ 289.80	₹ 26,505.00
22	2.5cm thick A.S. flooring using c.c. (1:2:4) with 12 mm size c.b.g. chips including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	84.81	₹ 407.28	₹ 34,541.00
23	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	m <sup>2</sup>	714.46	₹ 90.05	₹ 64,337.00
24	Priming 1 coat with any approved Primer on newly plastered wall surface	m <sup>2</sup>	870.59	₹ 78.23	₹ 68,106.00
25	Supplying and fixing of M.S. doors and windows	qtl	6.8	₹ 12,000.00	₹ 81,600.00
26	Display board and photograph	no	1	₹ 2,966.10	₹ 2,966.00

Tender value = ₹ 14,96,446.00

  
Junior Engineer  
Birmaharajpur Block Office

  
Assistant Executive Engineer  
Birmaharajpur Block Office

  
B.D.O.  
Birmaharajpur

Name of the work:-Construction of Additional Class Room at Buroghat Primary School, Bagbar G.P.					
Tender Value:- ₹ 14,96,446/- Head of Account:-Samagra Siksha Abhiyaan(2024-25)					
Sl.no.	Description	unit	quantity	rate	amount
1	Excavation of foundation trench in hard soil including dressing of sides and levelling of bed etc. complete.	m <sup>3</sup>	43.2	₹ 270.89	₹ 11,702.00
2	Filling sand in foundation and plinth well watered and rammed including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	45.17	₹ 599.18	₹ 27,065.00
3	Cement concrete (1:3:6) using 40mm size h.g. metal including cost, conveyance and royalty etc. complete.	m <sup>3</sup>	12.8	₹ 6,173.77	₹ 79,024.00
4	R.C.C. work of M-20 grade with 20mm and down grade black hard granite(crusher broken) stone chips including hoisting and laying including cost, conveyance and royalty of all materials etc. complete.	m <sup>3</sup>	32.5	₹ 6,297.20	₹ 2,04,659.00
5	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	qtl	28.15	₹ 8,584.52	₹ 2,41,654.00
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- roof slab and chajja	m <sup>2</sup>	117.32	₹ 772.10	₹ 90,583.00
7	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- footings and plinth bend	m <sup>2</sup>	60.8	₹ 252.82	₹ 15,371.00
8	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- beams and columns	m <sup>2</sup>	67.5	₹ 1,188.95	₹ 80,254.00
9	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor- lintel	m <sup>2</sup>	25.28	₹ 570.03	₹ 14,410.00
10	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in foundation & plinth"	m <sup>3</sup>	12.66	₹ 5,520.33	₹ 69,887.00
11	Brick work with fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent cement mortar (1:6) in super structure	m <sup>3</sup>	29.07	₹ 5,558.67	₹ 1,61,591.00
12	Fixing ceramic tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of precast tiles	m <sup>2</sup>	4.32	₹ 957.90	₹ 4,138.00
13	Fixing tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	m <sup>2</sup>	15.73	₹ 978.49	₹ 15,392.00
14	1 coat of priming over new M.S. doors and windows including , T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 72.20	₹ 2,781.00
15	2 coats of painting over new M.S. doors and windows including T & P and labour charges etc. complete.	m <sup>2</sup>	38.52	₹ 185.92	₹ 7,162.00
16	Wall painting 2 coats with weather coat (I.S.I.) of approved shade on new work to give an even shade including cost of paint.	m <sup>2</sup>	156.14	₹ 99.67	₹ 15,562.00
17	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint	m <sup>2</sup>	714.46	₹ 107.61	₹ 76,883.00

18	12mm thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	159.62	₹ 184.86	₹ 29,507.00
19	6mm, thick cement mortar plaster (1:4) on R.C.C. works including closely deep chipping and slurry treatment plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	114.49	₹ 207.99	₹ 23,813.00
20	16mm, thick cement mortar plaster (1:6) on brick masonry walls including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	175.77	₹ 267.13	₹ 46,953.00
21	20mm, thick cement mortar plaster (1:4) on roof slab top as grading plaster including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	91.46	₹ 289.80	₹ 26,505.00
22	2.5cm thick A.S. flooring using c.c. (1:2:4) with 12 mm size c.b.g. chips including cost, conveyance and royalty etc. complete.	m <sup>2</sup>	84.81	₹ 407.28	₹ 34,541.00
23	Finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	m <sup>2</sup>	714.46	₹ 90.05	₹ 64,337.00
24	Priming 1 coat with any approved Primer on newly plastered wall surface	m <sup>2</sup>	870.59	₹ 78.23	₹ 68,106.00
25	Supplying and fixing of M.S. doors and windows	qtl	6.8	₹ 12,000.00	₹ 81,600.00
26	Display board and photograph	no	1	₹ 2,966.10	₹ 2,966.00

Tender value = ₹ 14,96,446.00

  
Junior Engineer  
Birmaharajpur Block Office

  
Assistant Executive Engineer  
Birmaharajpur Block Office

  
Birmaharajpur