


## BILL OF QUANTITY

|      |                                  |   |
|------|----------------------------------|---|
| i    | NAME OF THE WORK                 | Const. of GPLF Office Building with Market Complex at GP level Singhijuba |
| ii   | Estimated cost                   | Rs.3000000.00   |
|      | Bidding amount                   | Rs.2417985.0/-  |
| iii  | Earnest money to be deposited    | Rs-24179.00/-   |
| iv   | Cost of tender paper             | RS=6000/-   |
| v    | Dt.of sale and Receipt of tender | 03/05/2025 to 16/05/2025  |
| vi   | Class of contractor              | "C"   |
| vii  | Date of opening of tender paper  | 20-05-2025  |
| viii | Time of completion               | FOUR CALENDER MONTH   |

| ABSTRACT |  |        |      |          |               |   |
|----------|--|--------|------|----------|---------------|---|
|          | Description  | QTY    | UNIT | RATE     | Amount        | IN WORD   |
| 1        | Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.   | 63.50  | cum  | ₹ 271.48 | ₹ 17,240.00   | Rupees Seventeen Thousand Two Hundred Fourty Only                   |
| 2        | Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.   | 84.68  | Cum  | 739.6    | ₹ 62,629.00   | Rupees SixtyTwo Thousand Six Hundred TwentyNine Only                |
| 3        | Providing & laying plain cement concrete 1:3:6 ( 1 cement 3 coarse and 6 graded stone aggregate fo 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming , watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundnes, T & P required for the work complete including dewatering if required as epr instructon of Engineer-in- charge. | 22.375 | Cum  | 6201     | ₹ 1,38,747.00 | Rupees One Lakh ThirtyEight Thousand Seven Hundred FourtySeven Only |
| 4        | Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75  | 19.432 | Cum  | 5514.9   | ₹ 1,07,166.00 | Rupees One Lakh Seven Thousand One Hundred SixtySix Only            |
| 5        | Providing Fly Ash Brick masonry in C.M (1:6) in superstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.  | 50.634 | Cum  | 5552.8   | ₹ 2,81,160.00 | Rupees Two Lakh EightyOne Thousand One Hundred Sixty Only           |
| ii       | first floor  | 5.656  | Cum  | 6196.82  | ₹ 35,049.00   | Rupees ThirtyFive Thousand FourtyNine Only                          |
| 6        | Brickwork with Fly Ash bricks in cement mortar (1:4) inSuperstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.   | 2.583  | Cum  | 5827.5   | ₹ 15,054.00   | Rupees Fifteen Thousand FiftyFour Only                              |
| 7        | R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work wirh cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.  | 48.83  | Cum  | 6357.8   | ₹ 3,10,451.00 | Rupees Three Lakh Ten Thousand Four Hundred FiftyOne Only           |



|     |  |         |      |          |               |   |
|-----|--|---------|------|----------|---------------|---|
| 3   | Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.  | 48.83   | Qntl | 8625.20  | ₹ 4,21,169.00 | Rupees Four Lakh TwentyOne Thousand One Hundred SixtyNine Only    |
| 9   | Rigid and smooth centering & shuttering for RCC works  |         |      |          | ₹ 0.00        |   |
| i   | Footing,Plinth   | 85.218  | Sqm  | 250.2    | ₹ 21,322.00   | Rupees TwentyOne Thousand Three Hundred TwentyTwo Only            |
| ii  | Column,beam  | 132.238 | Sqm  | 1170.3   | ₹ 1,54,758.00 | Rupees One Lakh FiftyFour Thousand Seven Hundred FiftyEight Only  |
| iii | Lintel   | 26.568  | Sqm  | 563.9    | ₹ 14,982.00   | Rupees Fourteen Thousand Nine Hundred EightyTwo Only              |
| iv  | Chajja / Roof slab   | 151.903 | Sqm  | 738.9    | ₹ 1,12,241.00 | Rupees One Lakh Twelve Thousand Two Hundred FourtyOne Only        |
| 10  | 2.5cm thick grading concrete (1:2:2) on roof slab using 6mm size hard granite chips including watering, curing etc.complete  | 125.308 | Sqm  | 385.38   | ₹ 48,291.00   | Rupees FourtyEight Thousand Two Hundred NinetyOne Only            |
| 11  | 6mm thick cement plaster (1:4),finished smooth to R.C.C. surfaces after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties &  | 136.98  | Sqm  | ₹ 164.10 | ₹ 22,478.00   | Rupees TwentyTwo Thousand Four Hundred SeventyEight Only          |
| 12  | 16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)  | 334.664 | Sqm  | 267.3    | ₹ 89,456.00   | Rupees EightyNine Thousand Four Hundred FiftySix Only             |
| ii  | FIRST FLOOR  | 22.364  | Sqm  | 273.9    | ₹ 6,125.00    | Rupees Six Thousand One Hundred TwentyFive Only                   |
| 13  | 12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)   | 440.357 | Sqm  | 185.5    | ₹ 81,686.00   | Rupees EightyOne Thousand Six Hundred EightySix Only              |
| ii  | FIRST FLOOR  | 23.539  | Sqm  | 291.5    | ₹ 6,862.00    | Rupees Six Thousand Eight Hundred SixtyTwo Only                   |
| 14  | Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per  | 1534.75 | kg   | 100      | ₹ 1,53,475.00 | Rupees One Lakh FiftyThree Thousand Four Hundred SeventyFive Only |
| 15  | Supplying fitting and fixing of PVC Door including the cost of all materials and fittings etc. complete as per   | 2       | each | 4000     | ₹ 8,000.00    | Rupees Eight Thousand Only  |
| 16  | Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with   | 13.504  | Sqm  | 1126.8   | ₹ 15,216.00   | Rupees Fifteen Thousand Two Hundred Sixteen Only                  |
| 17  | Fixing the glazed tile cliding on wall over 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost of all materials, labour T&P etc rrequired for the work all  | 27.491  | Sqm  | 1292.3   | ₹ 35,527.00   | Rupees ThirtyFive Thousand Five Hundred TwentySeven Only          |
| 18  | Supplying, fitting and fixing Chequred tile in floors approved make conforming to IS :13755 laid on 20 mm thick cement motar(1:4) filling joints with white cement of approved quality including cost of all material,labour T&P etc required for the work all complete as per direction of E.I.C. | 11.699  | Sqm  | 671      | ₹ 7,850.00    | Rupees Seven Thousand Eight Hundred Fifty Only                    |
| 19  | Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material,T&P and labour etc complete. ( for Iron work )  | 93.256  | Sqm  | 265.4    | ₹ 24,750.00   | Rupees TwentyFour Thousand Seven Hundred Fifty Only               |
| 20  | Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.   | 957.901 | Sqm  | 83.1     | ₹ 79,602.00   | Rupees SeventyNine Thousand Six Hundred Two Only                  |
| 21  | Weather coat painting two coats with approved shade incl. cost of all material,T&P and labour etc complete.  | 463.896 | Sqm  | 101.6    | ₹ 47,132.00   | Rupees FourtySeven Thousand One Hundred ThirtyTwo Only            |
| 22  | Distempering two coats with approved shade incl. cost of all material, labour and T&P etc. complete.   | 494.005 | SQM  | 90       | ₹ 44,460.00   | Rupees FourtyFour Thousand Four Hundred Sixty Only                |

|    |   |        |     |           |                       |   |
|----|---|--------|-----|-----------|-----------------------|---|
|    | Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect. Data for 3.26 sqm. | 5.793  | RMT | 3555.2    | ₹ 20,595.00           | Rupees Twenty Thousand Five Hundred NinetyFive Only                           |
| 24 | Labour for fixing GCI sheets in roof including fixing of ridges and wind ties etc. complete but excluding cost of   | 22.491 | Sqm | 268       | ₹ 6,028.00            | Rupees Six Thousand TwentyEight Only  |
| 25 | 2.5cm thick artificial stone flooring with cc (1:2:4) including punning using 12mm size hard granite chips  | 70.275 | Sqm | 405.34    | ₹ 28,485.00           | Rupees TwentyEight Thousand Four Hundred EightyFive Only                      |
|    | <b>TOTAL</b>  |        |     | <b>RS</b> | <b>₹ 24,17,985.00</b> | <b>Rupees TwentyFour Lakh Seventeen Thousand Nine Hundred EightyFive Only</b> |

BOQ Checked by:-

*[Signature]*  
09/05/25  
Assistant Executive Engineer  
Binka Block

I am willing to execute the work at

- i).....% Excess (in words.....)  
ii).....% Less (in words.....)

Signature of Contractor

Sold for  
the work:-

Const. of GPLF Office Building with Market Complex at GP level Singhijuba

On realisation of Rs6,000/- (Rupees six thousand) only towards cost of tender paper in the shape of Demand draft  
No.....Dt.....

APPROVED  
*[Signature]*  
Block Development Officer,  
Binka Block

*[Signature]*  
Block Development Officer,  
Binka Block


## BILL OF QUANTITY

|                                  |  |
|----------------------------------|--|
| NAME OF THE WORK                 | Const. of GPLF Office Building with Market Complex at GP level Kuhibahal |
| Estimated cost                   | Rs.3000000.00  |
| Bidding amount                   | Rs.2463136.0/-   |
| Earnest money to be deposited    | Rs-24631.00/-  |
| Cost of tender paper             | RS=6000/-  |
| Dt.of sale and Receipt of tender | 03/05/2025 to 16/05/2025   |
| Class of contractor              | "C"  |
| Date of opening of tender paper  | 20-05-2025   |
| Time of completion               | FOUR CALENDER MONTH  |

| ABSTRACT |  |        |      |            |               |  |
|----------|--|--------|------|------------|---------------|--|
|          | Description  | QTY    | UNIT | RATE       | Amount        | IN WORD  |
| 1        | Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.   | 63.50  | cum  | ₹ 271.48   | ₹ 17,239.79   | Rupees Seventeen Thousand Two Hundred ThirtyNine Paise SeventyNine Only              |
| 2        | Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.   | 84.68  | Cum  | 739.6      | ₹ 62,629.33   | Rupees SixtyTwo Thousand Six Hundred TwentyNine Paise ThirtyThree Only               |
| 3        | Providing & laying plain cement concrete 1:3:6 ( 1 cement 3 coarse and 6 graded stone aggregate fo 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming , watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundnes, T & P required for the work complete including dewatering if required as epr instructon of Engineer-in- charge. | 22.375 | Cum  | ₹ 6,201.00 | ₹ 1,38,747.38 | Rupees One Lakh ThirtyEight Thousand Seven Hundred FortySeven Paise ThirtyEight Only |
| 4        | Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.   | 26.664 | Cum  | 5514.9     | ₹ 1,47,049.29 | Rupees One Lakh FourtySeven Thousand FourtyNine Paise TwentyNine Only                |
| 5        | Providing Fly Ash Brick masonry in C.M (1:6) in superstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.  | 50.634 | Cum  | 5552.8     | ₹ 2,81,160.48 | Rupees Two Lakh EightyOne Thousand One Hundred Sixty Paise FortyEight Only           |
| ii       | first floor  | 5.656  | Cum  | 6196.82    | ₹ 35,049.21   | Rupees ThirtyFive Thousand FourtyNine Paise TwentyOne Only                           |
| 6        | Brickwork with Fly Ash bricks in cement mortar (1:4) inSuperstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with  | 2.583  | Cum  | 5827.5     | ₹ 15,053.95   | Rupees Fifteen Thousand FiftyThree Paise NinetyFive Only                             |
| 7        | R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work wirh cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per  | 48.83  | Cum  | 6357.8     | ₹ 3,10,451.37 | Rupees Three Lakh Ten Thousand Four Hundred FiftyOne Paise ThirtySeven Only          |



|     |  |         |      |          |               |   |
|-----|--|---------|------|----------|---------------|---|
|     | Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.                              | 48.83   | Qntl | 8625.20  | ₹ 4,21,168.52 | Rupees Four Lakh TwentyOne Thousand One Hundred SixtyEight Paise FiftyTwo Only  |
| 9   | Rigid and smooth centering & shuttering for RCC works including false works and dismantling then after casting   |         |      |          | ₹ 0.00        |   |
| i   | Footing,Plinth   | 85.218  | Sqm  | 250.2    | ₹ 21,321.54   | Rupees TwentyOne Thousand Three Hundred TwentyOne Paise                         |
| ii  | Column,beam  | 132.238 | Sqm  | 1170.3   | ₹ 1,54,758.13 | Rupees One Lakh FiftyFour Thousand Seven Hundred FiftyEight Paise Thirteen Only |
| iii | Lintel   | 26.568  | Sqm  | 563.9    | ₹ 14,981.70   | Rupees Fourteen Thousand Nine Hundred EightyOne Paise Seventy Only              |
| iv  | Chajja / Roof slab   | 151.903 | Sqm  | 738.9    | ₹ 1,12,241.13 | Rupees One Lakh Twelve Thousand Two Hundred FourtyOne Paise Thirteen Only       |
| 10  | 2.5cm thick grading concrete (1:2:2) on roof slab using 6mm size hard granite chips including watering, curing etc.complete  | 125.308 | Sqm  | 385.38   | ₹ 48,291.20   | Rupees FourtyEight Thousand Two Hundred NinetyOne Paise Twenty Only             |
| 11  | 6mm thick cement plaster (1:4),finished smooth to R.C.C. surfaces after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction   | 136.98  | Sqm  | ₹ 164.10 | ₹ 22,477.76   | Rupees TwentyTwo Thousand Four Hundred SeventySeven Paise SeventySix Only       |
| 12  | 16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)  | 334.664 | Sqm  | 267.3    | ₹ 89,455.69   | Rupees EightyNine Thousand Four Hundred FiftyFive Paise SixtyNine Only          |
| ii  | FIRST FLOOR  | 22.364  | Sqm  | 273.9    | ₹ 6,125.50    | Rupees Six Thousand One Hundred TwentyFive Paise Fifty Only                     |
| 13  | 12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)   | 454.584 | Sqm  | 185.5    | ₹ 84,325.33   | Rupees EightyFour Thousand Three Hundred TwentyFive Paise ThirtyThree Only      |
| ii  | FIRST FLOOR  | 23.539  | Sqm  | 291.5    | ₹ 6,861.62    | Rupees Six Thousand Eight Hundred SixtyOne Paise SixtyTwo Only                  |
| 14  | Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.   | 1534.75 | kg   | 100      | ₹ 1,53,475.00 | Rupees One Lakh FiftyThree Thousand Four Hundred SeventyFive Only               |
| 15  | Supplying fitting and fixing of PVC Door including the cost of all materials and fittings etc. complete as per direction of Engineer in charge.  | 2       | each | 4000     | ₹ 8,000.00    | Rupees Eight Thousand Only  |
| 16  | Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including rubbing and polishing etc all complete. ( Data for 10 Sqm ) A/ R Page - 90, Sl.(17) | 13.504  | Sqm  | 1126.8   | ₹ 15,216.31   | Rupees Fifteen Thousand Two Hundred Sixteen Paise ThirtyOne Only                |
| 17  | Fixing the glazed tile cliding on wall over 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost of all materials, labour T&P etc rrequired for the work all completeas per direction of Engineer-in-charge.  | 27.491  | Sqm  | 1292.3   | ₹ 35,526.62   | Rupees ThirtyFive Thousand Five Hundred TwentySix Paise SixtyTwo Only           |



|    |   |              |     |           |                       |   |
|----|---|--------------|-----|-----------|-----------------------|---|
|    | supplying, fitting and fixing Chequered tile in floors approved make conforming to IS :13755 laid on 20 mm thick cement motar(1:4) filling joints with white cement of approved quality including cost of all material,labour T&P etc required for the work all complete as per direction of E.I.C. | 11.699       | Sqm | 671       | ₹ 7,850.03            | Rupees Seven Thousand Eight Hundred Fifty Paise Three Only                                      |
| 19 | Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material,T&P and labour etc complete. ( for Iron work )   | 93.256       | Sqm | 265.4     | ₹ 24,750.14           | Rupees TwentyFour Thousand Seven Hundred Fifty Paise Fourteen Only                              |
| 20 | Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.  | 972.128      | Sqm | 83.1      | ₹ 80,783.84           | Rupees Eighty Thousand Seven Hundred EightyThree Paise EightyFour Only                          |
| 21 | Weather coat painting two coats with approved shade incl. cost of all material,T&P and labour etc complete.   | 478.123      | Sqm | 101.6     | ₹ 48,577.30           | Rupees FourtyEight Thousand Five Hundred SeventySeven Paise                                     |
| 22 | Distempering two coats with approved shade incl. cost of all material, labour and T&P etc. complete.  | 494.005      | SQM | 90        | ₹ 44,460.45           | Rupees FourtyFour Thousand Four Hundred Sixty Paise FourtyFive Only                             |
| 23 | Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design  | 5.793        | RMT | 3555.2    | ₹ 20,595.27           | Rupees Twenty Thousand Five Hundred NinetyFive Paise TwentySeven Only                           |
| 24 | Labour for fixing GCI sheets in roof including fixing of ridges and wind ties etc. complete but excluding cost of fitting   | 22.491       | Sqm | 268       | ₹ 6,027.59            | Rupees Six Thousand TwentySeven Paise FiftyNine Only  |
| 25 | 2.5cm thick artificial stone flooring with cc (1:2:4) including punning using 12mm size hard granite chips  | 70.275       | Sqm | 405.34    | ₹ 28,485.27           | Rupees TwentyEight Thousand Four Hundred EightyFive Paise                                       |
|    |   | <b>TOTAL</b> |     | <b>RS</b> | <b>₹ 24,63,136.73</b> | <b>Rupees TwentyFour Lakh SixtyThree Thousand One Hundred ThirtySix Paise SeventyThree Only</b> |

BOQ Checked by:-

*Oh* 02/05/25  
Assistant Executive Engineer  
Binka Block

I am willing to execute the work at

i).....% Excess (in words.....)

ii).....% Less (in words.....)

Signature of Contractor

APPROVED  
*Oh*  
Block Development Officer,  
Binka Block 02/05/25

Sold for the work:- Const. of GPLF Office Building with Market Complex at GP level Kuhibahal


On realisation of Rs6,000/- (Rupees six thousand) only towards cost of tender  
paper in the shape of Demand draft  
No.....Dt.....

  
Block Development Officer,  
Binka Block

## BILL OF QUANTITY

|      |                                  |   |
|------|----------------------------------|---|
| i    | NAME OF THE WORK                 | Const. of GPLF Office Building with Market Complex at GP level Baunsuni |
| ii   | Estimated cost                   | Rs.3000000.00   |
|      | Bidding amount                   | Rs.2417985.0/-  |
| iii  | Earnest money to be deposited    | Rs-24179.00/-   |
| iv   | Cost of tender paper             | RS=6000/-   |
| v    | Dt.of sale and Receipt of tender | 03/05/2025 to 16/05/2025  |
| vi   | Class of contractor              | "C"   |
| vii  | Date of opening of tender paper  | 20-05-2025  |
| viii | Time of completion               | FOUR CALENDER MONTH   |

| ABSTRACT |  |        |      |          |               |  |
|----------|--|--------|------|----------|---------------|--|
|          | Description  | QTY    | UNIT | RATE     | Amount        | IN WORD  |
| 1        | Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.   | 63.50  | cum  | ₹ 271.48 | ₹ 17,240.00   | Rupees Seventeen Thousand Two Hundred Forty Only                   |
| 2        | Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.   | 84.68  | Cum  | 739.6    | ₹ 62,629.00   | Rupees SixtyTwo Thousand Six Hundred TwentyNine Only               |
| 3        | Providing & laying plain cement concrete 1:3:6 ( 1 cement 3 coarse and 6 graded stone aggregate fo 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming , watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundnes, T & P required for the work complete including dewatering if required as epr instrucion of Engineer-in- charge. | 22.375 | Cum  | 6201     | ₹ 1,38,747.00 | Rupees One Lakh ThirtyEight Thousand Seven Hundred FortySeven Only |
| 4        | Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75  | 19.432 | Cum  | 5514.9   | ₹ 1,07,166.00 | Rupees One Lakh Seven Thousand One Hundred SixtySix Only           |
| 5        | Providing Fly Ash Brick masonry in C.M (1:6) in superstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.  | 50.634 | Cum  | 5552.8   | ₹ 2,81,160.00 | Rupees Two Lakh EightyOne Thousand One Hundred Sixty Only          |
| ii       | first floor  | 5.656  | Cum  | 6196.82  | ₹ 35,049.00   | Rupees ThirtyFive Thousand FortyNine Only                          |
| 6        | Brickwork with Fly Ash bricks in cement mortar (1:4) inSuperstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.   | 2.583  | Cum  | 5827.5   | ₹ 15,054.00   | Rupees Fifteen Thousand FiftyFour Only                             |
| 7        | R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work wirth cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.   | 48.83  | Cum  | 6357.8   | ₹ 3,10,451.00 | Rupees Three Lakh Ten Thousand Four Hundred FiftyOne Only          |



|     |  |         |      |          |               |   |
|-----|--|---------|------|----------|---------------|---|
| 8   | Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.  | 48.83   | Qntl | 8625.20  | ₹ 4,21,169.00 | Rupees Four Lakh TwentyOne Thousand One Hundred SixtyNine Only    |
| 9   | Rigid and smooth centering & shuttering for RCC works  |         |      |          | ₹ 0.00        |   |
| i   | Footing,Plinth   | 85.218  | Sqm  | 250.2    | ₹ 21,322.00   | Rupees TwentyOne Thousand Three Hundred TwentyTwo Only            |
| ii  | Column,beam  | 132.238 | Sqm  | 1170.3   | ₹ 1,54,758.00 | Rupees One Lakh FiftyFour Thousand Seven Hundred FiftyEight Only  |
| iii | Lintel   | 26.568  | Sqm  | 563.9    | ₹ 14,982.00   | Rupees Fourteen Thousand Nine Hundred EightyTwo Only              |
| iv  | Chajja / Roof slab   | 151.903 | Sqm  | 738.9    | ₹ 1,12,241.00 | Rupees One Lakh Twelve Thousand Two Hundred FourtyOne Only        |
| 10  | 2.5cm thick grading concrete (1:2:2) on roof slab using 6mm size hard granite chips including watering, curing etc.complete  | 125.308 | Sqm  | 385.38   | ₹ 48,291.00   | Rupees FourtyEight Thousand Two Hundred NinetyOne Only            |
| 11  | 6mm thick cement plaster (1:4),finished smooth to R.C.C. surfaces after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties &  | 136.98  | Sqm  | ₹ 164.10 | ₹ 22,478.00   | Rupees TwentyTwo Thousand Four Hundred SeventyEight Only          |
| 12  | 16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)  | 334.664 | Sqm  | 267.3    | ₹ 89,456.00   | Rupees EightyNine Thousand Four Hundred FiftySix Only             |
| ii  | FIRST FLOOR  | 22.364  | Sqm  | 273.9    | ₹ 6,125.00    | Rupees Six Thousand One Hundred TwentyFive Only                   |
| 13  | 12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)   | 440.357 | Sqm  | 185.5    | ₹ 81,686.00   | Rupees EightyOne Thousand Six Hundred EightySix Only              |
| ii  | FIRST FLOOR  | 23.539  | Sqm  | 291.5    | ₹ 6,862.00    | Rupees Six Thousand Eight Hundred SixtyTwo Only                   |
| 14  | Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per  | 1534.75 | kg   | 100      | ₹ 1,53,475.00 | Rupees One Lakh FiftyThree Thousand Four Hundred SeventyFive Only |
| 15  | Supplying fitting and fixing of PVC Door including the cost of all materials and fittings etc. complete as per   | 2       | each | 4000     | ₹ 8,000.00    | Rupees Eight Thousand Only  |
| 16  | Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with   | 13.504  | Sqm  | 1126.8   | ₹ 15,216.00   | Rupees Fifteen Thousand Two Hundred Sixteen Only                  |
| 17  | Fixing the glazed tile cliding on wall over 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost of all materials, labour T&P etc rrequired for the work all  | 27.491  | Sqm  | 1292.3   | ₹ 35,527.00   | Rupees ThirtyFive Thousand Five Hundred TwentySeven Only          |
| 18  | Supplying, fitting and fixing Chequred tile in floors approved make conforming to IS :13755 laid on 20 mm thick cement motar(1:4) filling joints with white cement of approved quality including cost of all material,labour T&P etc required for the work all complete as per direction of E.I.C. | 11.699  | Sqm  | 671      | ₹ 7,850.00    | Rupees Seven Thousand Eight Hundred Fifty Only                    |
| 19  | Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material,T&P and labour etc complete. ( for Iron work )  | 93.256  | Sqm  | 265.4    | ₹ 24,750.00   | Rupees TwentyFour Thousand Seven Hundred Fifty Only               |
| 20  | Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.   | 957.901 | Sqm  | 83.1     | ₹ 79,602.00   | Rupees SeventyNine Thousand Six Hundred Two Only                  |
| 21  | Weather coat painting two coats with approved shade incl. cost of all material,T&P and labour etc complete.  | 463.896 | Sqm  | 101.6    | ₹ 47,132.00   | Rupees FourtySeven Thousand One Hundred ThirtyTwo Only            |
| 22  | Distempering two coats with approved shade incl. cost of all material, labour and T&P etc. complete.   | 494.005 | SQM  | 90       | ₹ 44,460.00   | Rupees FourtyFour Thousand Four Hundred Sixty Only                |

|    |   |              |     |        |                       |  |
|----|---|--------------|-----|--------|-----------------------|--|
| 23 | Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect. Data for 3.26 sqm. | 5.793        | RMT | 3555.2 | ₹ 20,595.00           | Rupees Twenty Thousand Five Hundred NinetyFive Only                    |
| 24 | Labour for fixing GCI sheets in roof including fixing of ridges and wind ties etc. complete but excluding cost of   | 22.491       | Sqm | 268    | ₹ 6,028.00            | Rupees Six Thousand TwentyEight Only                                   |
| 25 | 2.5cm thick artificial stone flooring with cc (1:2:4) including punning using 12mm size hard granite chips  | 70.275       | Sqm | 405.34 | ₹ 28,485.00           | Rupees TwentyEight Thousand Four Hundred EightyFive Only               |
|    |   | <b>TOTAL</b> |     | RS     | <b>₹ 24,17,985.00</b> | Rupees TwentyFour Lakh Seventeen Thousand Nine Hundred EightyFive Only |

BOQ Checked by:-

*Olly*  
 Assistant Executive Engineer  
 Binka Block  
 02/05/25

I am willing to execute the work at

- i).....% Excess (in words.....)  
 ii).....% Less (in words.....)

Signature of Contractor

Sold for the work:- Const. of GPLF Office Building with Market Complex at GP level Baunsuni

On realisation of Rs6,000/- (Rupees six thousand) only towards cost of tender paper in the shape of Demand draft  
 No.....Dt.....

APPROVED


*Sh. 02/05/25*  
 Block Development Officer,  
 Binka Block

*02/05/25*  
 Block Development Officer,  
 Binka Block

## BILL OF QUANTITY

|      |                                  |  |
|------|----------------------------------|--|
| i    | NAME OF THE WORK                 | Const. of GPLF Office Building with Market Complex at GP level Sindurpur |
| ii   | Estimated cost                   | Rs.3000000.00  |
|      | Bidding amount                   | Rs.2417985.0/-   |
| iii  | Earnest money to be deposited    | Rs-24179.00/-  |
| iv   | Cost of tender paper             | RS=6000/-  |
| v    | Dt.of sale and Receipt of tender | 03/05/2025 to 16/05/2025   |
| vi   | Class of contractor              | "C"  |
| vii  | Date of opening of tender paper  | 20-05-2025   |
| viii | Time of completion               | FOUR CALENDER MONTH  |

| ABSTRACT |  |        |      |          |               |   |
|----------|--|--------|------|----------|---------------|---|
|          | Description  | QTY    | UNIT | RATE     | Amount        | IN WORD   |
| 1        | Earth work in ordinary soil within 50mtr initial lead and 1.5mtr initial lift including rough dressing and breaking of clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3mtr in depth as per direction of Engineer -in - charge.   | 63.50  | cum  | ₹ 271.48 | ₹ 17,240.00   | Rupees Seventeen Thousand Two Hundred Fourty Only                   |
| 2        | Filling in foundation & plinth with clean coarse river sand including watering & ramming in layers upto 1.5m depth with all lead labour T&P charges etc.required (only consolidated volume shall be taken for payment) including supplying of all materials, labour & T&P with cost, conveyance, royalty, taxes etc all complete as per specification & direction of Engineer in charge.   | 84.68  | Cum  | 739.6    | ₹ 62,629.00   | Rupees SixtyTwo Thousand Six Hundred TwentyNine Only                |
| 3        | Providing & laying plain cement concrete 1:3:6 ( 1 cement 3 coarse and 6 graded stone aggregate fo 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming , watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundnes, T & P required for the work complete including dewatering if required as epr instrucion of Engineer-in- charge. | 22.375 | Cum  | 6201     | ₹ 1,38,747.00 | Rupees One Lakh ThirtyEight Thousand Seven Hundred FourtySeven Only |
| 4        | Providing Fly Ash Brick masonry in C.M (1:6) in foundation & plinth using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75  | 19.432 | Cum  | 5514.9   | ₹ 1,07,166.00 | Rupees One Lakh Seven Thousand One Hundred SixtySix Only            |
| 5        | Providing Fly Ash Brick masonry in C.M (1:6) in superstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.  | 50.634 | Cum  | 5552.8   | ₹ 2,81,160.00 | Rupees Two Lakh EightyOne Thousand One Hundred Sixty Only           |
| ii       | first floor  | 5.656  | Cum  | 6196.82  | ₹ 35,049.00   | Rupees ThirtyFive Thousand FourtyNine Only                          |
| 6        | Brickwork with Fly Ash bricks in cement mortar (1:4) inSuperstructure using 25cm x 12cm x 8cm size Fly Ash bricks having crushing strength not less than 75 kg/cm2 with lowering & curing including cost, conveyance,royalties & all taxes of materials to work site etc. all complete as per direction of E.I. C.   | 2.583  | Cum  | 5827.5   | ₹ 15,054.00   | Rupees Fifteen Thousand FiftyFour Only                              |
| 7        | R.C.C. M20 with 20mm and 10mm size CBHG chips including lowering laying the concrete and curing etc. compacting to required depth & levels, including supply of all materials labour T&P required for the work wirh cost, conveyance royalty taxes but excluding cost and labour charges of M.S. reinforcement etc. all complete as per direction of E.I.C.  | 48.83  | Cum  | 6357.8   | ₹ 3,10,451.00 | Rupees Three Lakh Ten Thousand Four Hundred FiftyOne Only           |



|     |  |         |      |          |               |   |
|-----|--|---------|------|----------|---------------|---|
| 8   | Providing M.S. reinforcement for R.C.C. work with cutting, bending, binding and tying the grills as per approved design & placing in position including cost conveyance M.S. Rod & binding wire 18 to 20 gauge etc. all complete as per direction of E.I.C.  | 48.83   | Qntl | 8625.20  | ₹ 4,21,169.00 | Rupees Four Lakh TwentyOne Thousand One Hundred SixtyNine Only    |
| 9   | Rigid and smooth centering & shuttering for RCC works  |         |      |          | ₹ 0.00        |   |
| i   | Footing,Plinth   | 85.218  | Sqm  | 250.2    | ₹ 21,322.00   | Rupees TwentyOne Thousand Three Hundred TwentyTwo Only            |
| ii  | Column,beam  | 132.238 | Sqm  | 1170.3   | ₹ 1,54,758.00 | Rupees One Lakh FiftyFour Thousand Seven Hundred FiftyEight Only  |
| iii | Lintel   | 26.568  | Sqm  | 563.9    | ₹ 14,982.00   | Rupees Fourteen Thousand Nine Hundred EightyTwo Only              |
| iv  | Chajja / Roof slab   | 151.903 | Sqm  | 738.9    | ₹ 1,12,241.00 | Rupees One Lakh Twelve Thousand Two Hundred FortyOne Only         |
| 10  | 2.5cm thick grading concrete (1:2:2) on roof slab using 6mm size hard granite chips including watering, curing etc.complete  | 125.308 | Sqm  | 385.38   | ₹ 48,291.00   | Rupees FourtyEight Thousand Two Hundred NinetyOne Only            |
| 11  | 6mm thick cement plaster (1:4),finished smooth to R.C.C. surfaces after cleaning the surface incl.watering, curing etc. complete with cost, conveyance, royalties &  | 136.98  | Sqm  | ₹ 164.10 | ₹ 22,478.00   | Rupees TwentyTwo Thousand Four Hundred SeventyEight Only          |
| 12  | 16mm. thick cement plaster in cement mortar (1:6) for brick work or stone masonry. (per sqm.)  | 334.664 | Sqm  | 267.3    | ₹ 89,456.00   | Rupees EightyNine Thousand Four Hundred FiftySix Only             |
| ii  | FIRST FLOOR  | 22.364  | Sqm  | 273.9    | ₹ 6,125.00    | Rupees Six Thousand One Hundred TwentyFive Only                   |
| 13  | 12mm. thick cement plaster in cement mortar (1:6) for brick work. (per sqm.)   | 440.357 | Sqm  | 185.5    | ₹ 81,686.00   | Rupees EightyOne Thousand Six Hundred EightySix Only              |
| ii  | FIRST FLOOR  | 23.539  | Sqm  | 291.5    | ₹ 6,862.00    | Rupees Six Thousand Eight Hundred SixtyTwo Only                   |
| 14  | Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per  | 1534.75 | kg   | 100      | ₹ 1,53,475.00 | Rupees One Lakh FiftyThree Thousand Four Hundred SeventyFive Only |
| 15  | Supplying fitting and fixing of PVC Door including the cost of all materials and fittings etc. complete as per   | 2       | each | 4000     | ₹ 8,000.00    | Rupees Eight Thousand Only  |
| 16  | Fixing vetrified tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster (1:3) jointed with   | 13.504  | Sqm  | 1126.8   | ₹ 15,216.00   | Rupees Fifteen Thousand Two Hundred Sixteen Only                  |
| 17  | Fixing the glazed tile cliding on wall over 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost of all materials, labour T&P etc rrequired for the work all  | 27.491  | Sqm  | 1292.3   | ₹ 35,527.00   | Rupees ThirtyFive Thousand Five Hundred TwentySeven Only          |
| 18  | Supplying, fitting and fixing Chequred tile in floors approved make conforming to IS :13755 laid on 20 mm thick cement motar(1:4) filling joints with white cement of approved quality including cost of all material,labour T&P etc required for the work all complete as per direction of E.I.C. | 11.699  | Sqm  | 671      | ₹ 7,850.00    | Rupees Seven Thousand Eight Hundred Fifty Only                    |
| 19  | Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material,T&P and labour etc complete. ( for Iron work )  | 93.256  | Sqm  | 265.4    | ₹ 24,750.00   | Rupees TwentyFour Thousand Seven Hundred Fifty Only               |
| 20  | Priming one coat of Wall cement Primer (Water bound) including cost of primer all labour T&P etc complete.   | 957.901 | Sqm  | 83.1     | ₹ 79,602.00   | Rupees SeventyNine Thousand Six Hundred Two Only                  |
| 21  | Weather coat painting two coats with approved shade incl. cost of all material,T&P and labour etc complete.  | 463.896 | Sqm  | 101.6    | ₹ 47,132.00   | Rupees FourtySeven Thousand One Hundred ThirtyTwo Only            |
| 22  | Distempering two coats with approved shade incl. cost of all material, labour and T&P etc. complete.   | 494.005 | SQM  | 90       | ₹ 44,460.00   | Rupees FourtyFour Thousand Four Hundred Sixty Only                |

|    |   |              |     |           |                       |   |
|----|---|--------------|-----|-----------|-----------------------|---|
| 23 | Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect. Data for 3.26 sqm. | 5.793        | RMT | 3555.2    | ₹ 20,595.00           | Rupees Twenty Thousand Five Hundred NinetyFive Only                           |
| 24 | Labour for fixing GCI sheets in roof including fixing of ridges and wind ties etc. complete but excluding cost of   | 22.491       | Sqm | 268       | ₹ 6,028.00            | Rupees Six Thousand TwentyEight Only  |
| 25 | 2.5cm thick artificial stone flooring with cc (1:2:4) including punning using 12mm size hard granite chips  | 70.275       | Sqm | 405.34    | ₹ 28,485.00           | Rupees TwentyEight Thousand Four Hundred EightyFive Only                      |
|    |   | <b>TOTAL</b> |     | <b>RS</b> | <b>₹ 24,17,985.00</b> | <b>Rupees TwentyFour Lakh Seventeen Thousand Nine Hundred EightyFive Only</b> |

BOQ Checked by:-

*02/05/25*  
 Assistant Executive Engineer  
 Binka Block

I am willing to execute the work at

- i).....% Excess (in words).....  
 ii).....% Less (in words).....

Signature of Contractor

APPROVED  
*02/05/25*  
 Block Development Officer,  
 Binka Block

Sold for the work:- Const. of GPLF Office Building with Market Complex at GP level Sindurpur

On realisation of Rs6,000/- (Rupees six thousand) only towards cost of tender paper in the shape of Demand draft  
 No.....Dt.....

*02/05/25*  
 Block Development Officer,  
 Binka Block